



**MINISTRY OF EDUCATION
SOUTHERN PROVINCE**

**BIDDING DOCUMENT
FOR**

**CONSTRUCTION TOILET FOR AT
G/BATAPOLA M.M.V.**

Issued to :

Date :

Contract No :

Employer

**The Secretary,
Ministry of Education- Southern Province,
Ground Floor, “Dakshinapaya”,
Ministry Complex,
Labuduwa, Galle**

CONTENT

Volume 1

Section 1	Instructions to Bidders
Section 2	Standard Forms (Contract)
Section 3	Conditions of Contract

Volume 2

	Invitation for Bids
Section 4	Form of Bid and Qualification Information
Section 5	Schedule
Section 6	Specifications
Section 7	Bills of Quantities
Section 8	Drawings
Section 9	Standard Forms (Bid)

Volume 1 consisting of section 1, section 2, section 3 will be applicable for this contract shall be given volume 1 of “Standard Bidding Document, Procurement of Works, Minor Contracts”, CIDA publication no: CIDA/SBD/03, Second Edition, January 2007, publish by Construction Industry Development Authority (CIDA), Savusiripaya, 123. Wijerama Mawatha, Colombo 07.

The above Document will not be issued with the Bidding Document and Bidder is advised to purchase it from CIDA.

INVITATION FOR BIDS

ප්‍රසම්පාදන දැන්වීම

දකුණු පළාත් අධ්‍යාපන, ඉඩම් හා ඉඩම් සංවර්ධන, මහා මාර්ග හා ප්‍රවාහන අමාත්‍යාංශය

දකුණු පළාත් සභාව

පළාත් නිශ්චිත සංවර්ධන ප්‍රදාන, ක්ලීන් ශ්‍රී ලංකා වැඩසටහන හා නඩත්තු සැලැස්ම 2025 යටතේ ක්‍රියාත්මක කරනු ලබන පහත සඳහන් වැඩ යෝජනා සඳහා සුදුසුකම් ලත් කොන්ත්‍රාත් කරුවන්ගෙන්, දකුණු පළාත් අධ්‍යාපන අමාත්‍යාංශයේ ප්‍රසම්පාදන කමිටු සභාපති විසින් ලංසු පත් කැඳවනු ලැබේ.

අනු අංකය	ව්‍යාපෘති අංකය	පාසල	වැඩ විස්තරය	කර්මාන්තය ඉටු කරනු ලබන ව්‍යාපෘති සැලැස්ම	ආපසු නොගෙවනු ලබන ඇප තැන්පත් මුදල රු.	ලංසු සුරක්ෂණ වටිනාකම රු.	අවශ්‍ය CID A ලියාපදිංචිය	මුළු පිරිවැය ඇස්තමේන්තු මුදල vat සමග රු. මි.
1	G/C/25/34	ගා/උඩුගම ම.වි	70*25 දෙමහල් ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	පළාත් නිශ්චිත	2,500.00	34,000.00	C 8 හෝ ඉහළ	4.34
2	G/C/25/35	ගා/හියාරේ නැහෙනහිර ක.වි	90*25 ගොඩනැගිල්ලේ කොරිඩෝර් ඉදිකිරීම	පළාත් නිශ්චිත	1,500.00	26,000.00	C 9 හෝ ඉහළ	3.40
3	G/C/25/36	ගා/තිත්තගල්ල අපානිකික ක.වි	180*25 ප්‍රධාන ශාලාවේ වහල අලුත්වැඩියාව	පළාත් නිශ්චිත	2,500.00	35,000.00	C 8 හෝ ඉහළ	4.41
4	G/C/25/37	ගා/හපුගල ප්‍රා.වි	මායිම් තාප්පය ඉදි කිරීම	නඩත්තු සැලැස්ම	1,500.00	27,000.00	C 9 හෝ ඉහළ	3.46
5	G/C/25/38	ගා/නරාවල ම.වි	80*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	32,000.00	C 8 හෝ ඉහළ	4.10
6	G/C/25/39	ගා/පංචාලිය ප්‍රා.වි	පාසල් ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	21,000.00	C 9 හෝ ඉහළ	2.73

7	G/C/25/40	ගා/කළායාණනිස්ස විද්‍යාලය	80*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	22,000.00	C 9 හෝ ඉහළ	2.88
8	G/C/25/41	ගා/ජයවර්ධන විද්‍යාලය	80*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	25,000.00	C 9 හෝ ඉහළ	3.14
9	G/C/25/42	ගා/පැදිත්තොරුව සරණපාල ජයන්ති ප්‍රා.වි	60*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	26,000.00	C 9 හෝ ඉහළ	3.35
10	G/C/25/43	ගා/ඇත්තිලිගොඩ සුදර්ශි ම.වි	100*25 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	30,000.00	C 9 හෝ ඉහළ	3.91
11	G/C/25/44	ගා/මීගහගොඩ ක.වි	50*20 විද්‍යාගාර ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	31,000.00	C 9 හෝ ඉහළ	3.93
12	G/C/25/45	ගා/කඩිහිංගල ම.වි	70*20 දෙමහල් ගොඩනැගිල්ලේ විදුලි පද්ධතිය නවීකරණය	නඩත්තු සැලැස්ම	1,500.00	17,000.00	C 9 හෝ ඉහළ	2.12
13	G/C/25/46	අම්බලන්ගොඩ කලාප අධ්‍යාපන කාර්යාලය	කාර්යාල ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	20,000.00	C 9 හෝ ඉහළ	2.49
14	G/C/25/47	ගා/වටරැක ශ්‍රී සෝභිත විද්‍යාලය	40*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	25,000.00	C 9 හෝ ඉහළ	3.22
15	G/C/25/48	ගා/විද්‍යානන්ද ක.වි	පැති බැම්ම අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	34,000.00	C 8 හෝ ඉහළ	4.40
16	G/C/25/49	ගා/උනන්තවිටිය රේවත ම.වි	90*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	36,000.00	C 8 හෝ ඉහළ	4.66
17	G/C/25/50	ගා/සිරි පඬුකර ප්‍රා.වි	80*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	25,000.00	C 9 හෝ ඉහළ	3.15

18	G/C/25/51	ගා/බද්දුව සිරි රතනජෝති ම.වි	90*25 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	26,000.00	C 9 හෝ ඉහළ	3.28
19	G/C/25/52	ගා/අක්මිමණ ම.වි	100*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	38,000.00	C 8 හෝ ඉහළ	4.97
20	G/C/25/53	ගා/ආනන්ද විජය විද්‍යාලය	90*25 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	25,000.00	C 9 හෝ ඉහළ	3.21
21	G/C/25/54	ගා/ඉදුරුව ම.වි	120*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	3,000.00	49,000.00	C 8 හෝ ඉහළ	6.47
22	G/C/25/55	ගා/තලංගහ සරස්වතී දෙමළ පාසල	වැසිකිළ පද්ධතිය ඉදි කිරීම	පළාත් නිශ්චිත	1,000.00	16,000.00	C 9 හෝ ඉහළ	1.99
23	G/C/25/56	ගා/දික්කුඹුර සිද්ධාර්ථ ම.වි	120*30 ප්‍රධාන ශාලාව නවීකරණය	පළාත් නිශ්චිත	2,500.00	40,000.00	C 8 හෝ ඉහළ	5.29
24	G/C/25/57	ගා/ලේල්වල ක.වි	80*20 ගොඩනැගිල්ල අලුත්වැඩියාව	පළාත් නිශ්චිත	3,500.00	75,000.00	C 8 හෝ ඉහළ	9.93
25	G/C/25/58	ගා/පොරවගම ක.වි	පැති බැම්ම අලුත්වැඩියාව	පළාත් නිශ්චිත	2,500.00	34,000.00	C 8 හෝ ඉහළ	4.39
26	G/C/25/59	ගා/ගනේගම රෝමානු කතෝලික පාසල	80*20 නව ගොඩනැගිල්ල ඉදි කිරීම	පළාත් නිශ්චිත	1,500.00	20,000.00	C 9 හෝ ඉහළ	2.60
27	G/C/25/60	ගා/ශ්‍රීපති ම.වි	80*20 දෙමහල් ගොඩනැගිල්ල ඉදි කිරීම	පළාත් නිශ්චිත	2,500.00	37,000.00	C 8 හෝ ඉහළ	4.79
28	G/C/25/61	ගා/මාමනදොළ ක.වි	90*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	පළාත් නිශ්චිත	2,500.00	32,000.00	C 8 හෝ ඉහළ	4.15

29	G/C/25/62	ගා/උක්වත්ත විද්‍යාලය	90*25 තෙමහල් ගොඩනැගිල්ලේ ඉදි කිරීම (ඉතිරි වැඩ)	පළාත් නිශ්චිත	2,500.00	41,000.00	C 8 හෝ ඉහළ	5.42
30	G/C/25/63	ගා/අක්කරවිස්ස ක.වි	මායිම් තාප්පය අලුත්වැඩියාව	පළාත් නිශ්චිත	1,500.00	25,000.00	C 9 හෝ ඉහළ	3.21
31	G/C/25/64	ගා/කළුචලගල ක.වි	40*20 ගොඩනැගිල්ල ඉදි කිරීම	පළාත් නිශ්චිත	3,000.00	46,000.00	C 8 හෝ ඉහළ	6.07
32	G/C/25/65	ගා/අවිත්තාව නාලන්දා ම.වි	80*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	පළාත් නිශ්චිත	1,500.00	29,000.00	C 9 හෝ ඉහළ	3.73
33	G/C/25/66	ගා/මහින්ද රාජපක්ෂ ම.වි	මායිම් තාප්පය අලුත්වැඩියාව	පළාත් නිශ්චිත	3,000.00	61,000.00	C 8 හෝ ඉහළ	7.88
34	G/C/25/67	ගා/ගුණානන්ද ප්‍රා.වි	50*25 ගොඩනැගිල්ල අලුත්වැඩියාව	පළාත් නිශ්චිත	1,500.00	17,000.00	C 9 හෝ ඉහළ	2.16
35	G/C/25/68	ගා/බී.ටී.එස් විද්‍යාලය	80*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	32,000.00	C 8 හෝ ඉහළ	4.07
36	G/C/25/69	ගා/මාවඩවිල ම.වි	90*25 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	24,000.00	C 9 හෝ ඉහළ	3.01
37	G/C/25/70	ගා/සිරිනිවාස ම.වි	100*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	40,000.00	C 8 හෝ ඉහළ	5.31
38	G/C/25/71	ගා/දොළහේන ක.වි	80*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	43,000.00	C 8 හෝ ඉහළ	5.69
39	G /C/25/72	ගා/පිලාන තක්ෂිලා ප්‍රා.වි.	මායිම් තාප්පය නවීකරණය	පළාත් නිශ්චිත	1,000.00	14,000.00	C9 හෝ ඉහළ	1.8

40	G /C/25/73	ගා/සංසරනන ප්‍රා.වි.	100*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව.	පළාත් නිශ්චිත	2,500.00	34,000.00	C8 හෝ ඉහළ	4.4
41	G/C/25/74	ගා/තෙලිකඩ ම.වි.	80*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	පළාත් නිශ්චිත	2,500.00	35,000.00	C8 හෝ ඉහළ	4.5
42	G/C/25/75	ගා/කරන්දෙණිය ක.වි.	80*20 ගොඩනැගිල්ල අලුත්වැඩියාව	පළාත් නිශ්චිත	1,500.00	29,000.00	C9 හෝ ඉහළ	3.7
43	G/C/25/76	ගා/ලේනගල්පලා ත ක.වි.	80*20 ගොඩනැගිල්ල අලුත්වැඩියාව	පළාත් නිශ්චිත	1,500.00	27,000.00	C9 හෝ ඉහළ	3.4
44	G /C/25/77	ගා/රතනසාර ම.වි.	100*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	පළාත් නිශ්චිත	1,500.00	23,000.00	C9 හෝ ඉහළ	2.9
45	G /C/25/78	ගා/යටගල ම.වි.	මායිම් තාප්පය අලුත්වැඩියා කිරීම.	පළාත් නිශ්චිත	2,500.00	39,000.00	C8 හෝ ඉහළ	5.1
46	G /C/25/79	ගා/ඔල්කට් ම.වි	80*20 ගොඩනැගිල්ල අලුත්වැඩියාව	පළාත් නිශ්චිත	2,500.00	40,000.00	C8 හෝ ඉහළ	5.3
47	G /C/25/80	ගා/තෙල්ලඹුර විජය ක.වි.	පැති බැම්ම ඉදි කිරීම.	පළාත් නිශ්චිත	2,500.00	34,000.00	C8 හෝ ඉහළ	4.3
48	G /C/25/81	ගා/හියාරේ ම.වි.	80*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	පළාත් නිශ්චිත	2,500.00	45,000.00	C8 හෝ ඉහළ	5.8
49	G /C/25/82	ගා/උස්වතුන් හසානා ම.වි.	160*25 තෙමහල් ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව.	පළාත් නිශ්චිත	2,500.00	34,000.00	C8 හෝ ඉහළ	4.4
50	G /C/25/83	ගා/බුද්ධදත්ත ප්‍රා.වි.	120*20 ප්‍රධාන ශාලාව අලුත්වැඩියාව	පළාත් නිශ්චිත	3,500.00	64,000.00	C8 හෝ ඉහළ	8.4
51	G /C/25/84	ගා/සිරි අභයතිස්ස ක.වි.	දෙමහල් ගොඩනැගිල්ලේ යකඩ ග්‍රිල් සවි කිරීම.	නඩත්තු සැලැස්ම	1,000.00	16,000.00	C9 හෝ ඉහළ	1.9
52	M/C/25/31	මාර/පර්සි අබේවර්ධන විද්‍යාලය	80*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව.	නඩත්තු සැලැස්ම	2,500.00	40,000.00	C8 හෝ ඉහළ	5.3
53	M/C/25/44	මාර/පිනරාජ ක.වි.	වැසිකිළි පද්ධතිය අලුත්වැඩියා කිරීම.	පළාත් නිශ්චිත	1,500.00	22,000.00	C9 හෝ ඉහළ	2.1
54	M/C/25/52	අකුරැස්ස කලාප අධ්‍යාපන කාර්යාලය	පැති බැම්ම ප්‍රතිසංස්කරණය කිරීම	නඩත්තු සැලැස්ම	1,500.00	28,000.00	C 9 හෝ ඉහළ	3.59

55	M/C/25/53	මාර/කරගොඩ උයන්ගොඩ ම.වි	වැසිකිළි පද්ධතිය ඉදි කිරීම	පළාත් නිශ්චිත	1,500.00	20,000.00	C 9 හෝ ඉහළ	2.57
56	M/C/25/54	මාර/බැරගම ක.වි	වැසිකිළි පද්ධතිය ඉදි කිරීම	පළාත් නිශ්චිත	1,500.00	19,000.00	C 9 හෝ ඉහළ	2.42
57	M/C/25/55	මාර/පොල්වත්ත ප්‍රා.වි	ප්‍රධාන ශාලාව අලුත්වැඩියා කිරීමේ ඉතිරි වැඩ සම්පූර්ණ කිරීම	පළාත් නිශ්චිත	2,500.00	34,000.00	C 8 හෝ ඉහළ	4.48
58	M/C/25/56	මාර/මාතර ආදර්ශ ප්‍රා.වි	වැසි ජලය කළමනාකරණ පද්ධතිය නවීකරණය කිරීම	පළාත් නිශ්චිත	1,500.00	21,000.00	C 9 හෝ ඉහළ	2.69
59	M/C/25/57	මාර/කිරින්ද ආදර්ශ ප්‍රා.වි	70*25 දෙමහල් ගොඩනැගිල්ල නවීකරණය කිරීම	පළාත් නිශ්චිත	4,000.00	79,000.00	C 7 හෝ ඉහළ	10.43
60	M/C/25/58	මාර/තල්පාවිල ම.ම.වි	ක්‍රීඩා පිටිය සංවර්ධනය කිරීම	පළාත් නිශ්චිත	2,500.00	42,000.00	C 8 හෝ ඉහළ	5.47
61	M/C/25/59	මාර/කඹුරුගමුව ම.වි	80*20 තනි මහල් ගොඩනැගිල්ල 90*25 දෙමහල් ගොඩනැගිල්ලට නවීකරණය කිරීම (අදියර 01)	පළාත් නිශ්චිත සංවර්ධන ප්‍රදාන	4,000.00	88,000.00	C 7 හෝ ඉහළ	11.69
62	M/C/25/60	මාර/බෙලිදෙණිය ම.වි	60*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියා කිරීම	පළාත් නිශ්චිත	1,500.00	27,000.00	C 9 හෝ ඉහළ	3.57
63	H/C/25/26	හ/මහගල්වැව ක.වි	90*25 දෙමහල් ගොඩනැගිල්ලේ බිම් මහලේ කාර්යාල කාමරය සකස් කිරීම	නඩත්තු සැලැස්ම	1,500.00	21,000.00	C 9 හෝ ඉහළ	2.73
64	H/C/25/27	හ/දුටුගැමුණු ම.වි	90*25 තෙමහල් ගොඩනැගිල්ලේ වහලය අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	23,000.00	C 9 හෝ ඉහළ	3.05
65	H/C/25/28	හ/සපුතන්ත්‍රිකන්ද ප්‍රා.වි	පැති බැම්ම හා ජල කුළුණ ඉදි කිරීම	පළාත් නිශ්චිත	1,500.00	20,500.00	C 9 හෝ ඉහළ	2.7
66	H/C/25/29	හ/මිද්දෙනිය ම.වි	රැඳවුම් තාප්පය ඉදිකිරීම (ක්‍රීඩා පිටිය සඳහා ආරක්ෂක තාප්පය)	පළාත් නිශ්චිත	3,000.00	47,500.00	C 8 හෝ ඉහළ	6.27
67	H/C/25/30	හ/ගඟේයාය ක.වි	80*20 ගොඩනැගිල්ල අලුත්වැඩියාව	පළාත් නිශ්චිත	1,500.00	27,000.00	C 9 හෝ ඉහළ	3.55

68	H/C/25/31	තංගල්ල කලාප අධ්‍යාපන කාර්යාලයේ	මායිම් තාප්පය ඉදිකිරීම(ඉතිරි වැඩ)	පළාත් නිශ්චිත	1,000.00	12,000.00	C 9 හෝ ඉහළ	1.49
69	H/C/25/32	හ/බෙලිඅත්ත ම.ම.වි	100*20 තාක්ෂණික විද්‍යාගාරය ගොඩනැගිල්ල නවීකරණය	පළාත් නිශ්චිත	3,500.00	67,500.00	C 8 හෝ ඉහළ	8.91
70	H/C/25/33	හ/කදිරගොඩ ප්‍රා.වි	වැසිකිළි අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	18,000.00	C 9 හෝ ඉහළ	2.28
71	H/C/25/34	හ/ගොඩවානගොඩ ක.වි	වැසිකිළි අලුත්වැඩියාව සහ මායිම් තාප්පය අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	21,000.00	C 9 හෝ ඉහළ	2.67
72	H/C/25/35	හ/කුඩාවැල්ල ක.වි	වැසිකිළි අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,000.00	14,000.00	C 9 හෝ ඉහළ	1.82
73	H/C/25/36	හ/රදනිආර ම.වි	පරිගණක විද්‍යාගාරය අලුත්වැඩියා කිරීම	නඩත්තු සැලැස්ම	1,500.00	23,000.00	C 9 හෝ ඉහළ	2.94
74	H/C/25/37	හ/කිරම ධම්මානන්ද ප්‍රා.වි	80*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	37,000.00	C 8 හෝ ඉහළ	4.80
75	H/C/25/38	හ/කැරදෙනිය ක.වි	40*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	28,000.00	C 9 හෝ ඉහළ	3.69
76	H/C/25/39	හ/අගලබඩ ක.වි	60*20 ගොඩනැගිල්ල අලුත්වැඩියා කිරීම	නඩත්තු සැලැස්ම	1,500.00	23,000.00	C 9 හෝ ඉහළ	2.97
77	H/C/25/40	හ/අල්අමීර් මුස්ලිම් විද්‍යාලය	මායිම් තාප්පය අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	16,000.00	C 9 හෝ ඉහළ	2.08
78	H/C/25/41	හ/පල්ලෙපුලම්පිටිය ම.වි	60*20 ගොඩනැගිල්ල අලුත්වැඩියා කිරීම	නඩත්තු සැලැස්ම	1,500.00	30,000.00	C 9 හෝ ඉහළ	3.93
79	H/C/25/42	හ/කැකිරිඔබ ක.වි	පුස්තකාල ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	39,000.00	C 8 හෝ ඉහළ	5.1
80	H/C/25/43	හ/බෙරලිහෙල ම.වි	80*20 ගොඩනැගිල්ල සහ 50*25 කාර්යාල ගොඩනැගිල්ල වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	21,000.00	C 9 හෝ ඉහළ	2.74
81	H/C/25/44	හ/ගැටමාන්න දකුණ ම.වි	100*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	37,000.00	C 8 හෝ ඉහළ	4.87
82	H/C/25/45	හ/ගැටමාන්න උතුර ක.වි	100*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	39,000.00	C 8 හෝ ඉහළ	5.07

83	H/C/25/46	හ/බුන්දල ක.වි	80*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	32,000.00	C 8 හෝ ඉහළ	4.22
84	H/C/25/47	හ/පලපොත ම.වි	100*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	27,000.00	C 9 හෝ ඉහළ	3.55
85	H/C/25/48	හ/බටහන දකුණ ක.වි	40*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	19,000.00	C 9 හෝ ඉහළ	2.49
86	H/C/25/49	හ/කහවත්ත ම.වි	නෙප්වුන් ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	3,000.00	61,000.00	C 8 හෝ ඉහළ	8.00
87	H/C/25/50	හ/කණුකැටිය ක.වි	80*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	24,000.00	C 9 හෝ ඉහළ	3.06
88	H/C/25/51	හ/දෙබරවැව ජනාධිපති විද්‍යාලය	120*20 ගොඩනැගිල්ල වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	40,000.00	C 8 හෝ ඉහළ	5.25
89	H/C/25/52	හ/දෙනිය පිංගම ක.වි	80*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	19,000.00	C 9 හෝ ඉහළ	2.44
90	H/C/25/53	හ/මිහඟවෙල ක.වි	120*20 ගොඩනැගිල්ලේ වහල සහ වැසිකිළි අලුත්වැඩියාව	පළාත් නිශ්චිත	1,500.00	17,000.00	C 9 හෝ ඉහළ	2.2
91	H/C/25/54	හ/මොරයාය ම.වි	120*20 ගොඩනැගිල්ල අලුත්වැඩියාව	පළාත් නිශ්චිත	3,000.00	60,000.00	C 8 හෝ ඉහළ	7.94
92	H/C/25/55	හ/වැකඳවල ජනපද ම.වි	120*20 ගොඩනැගිල්ල අලුත්වැඩියාව	පළාත් නිශ්චිත	3,500.00	63,000.00	C 8 හෝ ඉහළ	8.33
93	H/C/25/56	හ/හිඟුරකන්ද ම.වි	72*16 ගොඩනැගිල්ල ප්‍රතිසංස්කරණය කිරීම	පළාත් නිශ්චිත	1,000.00	14,000.00	C 9 හෝ ඉහළ	1.81
94	H/C/25/57	හ/ලුණුගම්වෙහෙර ම.වි	වැසිකිළි පද්ධතිය ඉදිකිරීම	පළාත් නිශ්චිත	1,500.00	16,000.00	C 9 හෝ ඉහළ	2.00
95	H/C/25/58	හ/කටුවන ප්‍රා.වි	විද්‍යාලයේ පැති පැමිම ඉදි කිරීම	පළාත් නිශ්චිත සංවර්ධන ප්‍රදාන	2,500.00	35,000.00	C 8 හෝ ඉහළ	4.55
96	H/C/25/59	හ/රතනපෝති ප්‍රා.වි,ගඟලන්දෙනි ය	පැතිබැම්ම ඉදි කිරීම (ක්‍රීඩා පිටිය ඉදිරිපස)	පළාත් නිශ්චිත	2,500.00	40,000.00	C 8 හෝ ඉහළ	5.28
97	H/C/25/60	හ/වැවේගම ක.වි	60*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	24,000.00	C 9 හෝ ඉහළ	3.10

98	H/C/25/61	හ/පොළොම්මාරුව ආදර්ශ විද්‍යාලය	වැසිකිළි අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	17,000.00	C 9 හෝ ඉහළ	2.2
99	G/CSL/25/01	ගා/උනන්විටිය රේවත ම.වි.	පැති බැම්ම ඉදි කිරීම	ක්ලින් ශ්‍රී ලංකා	1,500.00	23,000.00	C 9 හෝ ඉහළ	2.8
100	G/CSL/25/02	ගා/ඇත්තිලිගොඩ සුදර්ශි ම.වි.	80 X 20 ගොඩනැගිල්ල නවීකරණය	ක්ලින් ශ්‍රී ලංකා	1,000.00	16,000.00	C 9 හෝ ඉහළ	1.9
101	G/CSL/25/03	ගා/දෙල්ලව ම.වි.	පැති බැම්ම ඉදි කිරීම	ක්ලින් ශ්‍රී ලංකා	1,500.00	29,000.00	C 9 හෝ ඉහළ	3.6
102	M/CSL/25/01	මාර/දම්පැල්ල ම.වි.	සංගීත හා නැටුම් කාමර නවීකරණය	ක්ලින් ශ්‍රී ලංකා	1,000.00	9,000.00	C 9 හෝ ඉහළ	1.1
10 3	G/CSL/25/0 4	ගා/ රතනසිරි රාජකීය විද්‍යාලය	ගැහැණු වැසිකිළි ඉදි කිරීම	ක්ලින් ශ්‍රී ලංකා	1,500.00	29,000.00	C 9 හෝ ඉහළ	3.7
10 4	G/CSL/25/0 5	ගා/ අනුරුද්ධ ක.වි.	වැසිකිළි නවීකරණය (පිරිමි වැසිකිළි 02 හා ගැහැණු වැසිකිළි 04)	ක්ලින් ශ්‍රී ලංකා	1,000.00	8,000.00	C 9 හෝ ඉහළ	1.0
10 5	G/CSL/25/0 6	ගා/සිරි අභයතිස්ස ම.වි.	ගුරුවරුන්ගේ සහ සිසුන්ගේ වැසිකිළි නවීකරණය	ක්ලින් ශ්‍රී ලංකා	1,500.00	22,000.00	C 9 හෝ ඉහළ	2.8
10 6	G/CSL/25/0 7	ගා/දික්කුඹුර ප්‍රා.වි.	වැසිකිළි පද්ධතියක් ඉදි කිරීම	ක්ලින් ශ්‍රී ලංකා	2,500.00	33,000.00	C 8 හෝ ඉහළ	4.2
10 7	G/CSL/25/0 8	ගා/හව්සේ ම.වි.	වැසිකිළි නවීකරණය	ක්ලින් ශ්‍රී ලංකා	1,000.00	7,000.00	C 9 හෝ ඉහළ	0.9
10 8	G/CSL/25/0 9	ගා/හප්පිටිය ක.වි.	ගුරුවරුන්ගේ වැසිකිළි ඉදි කිරීම	ක්ලින් ශ්‍රී ලංකා	1,500.00	29,000.00	C 9 හෝ ඉහළ	3.7
10 9	G/CSL/25/1 0	ගා/බටපොල ම.ම.වි.	වැසිකිළි ඉදි කිරීම	ක්ලින් ශ්‍රී ලංකා	2,500.00	34,000.00	C 8 හෝ ඉහළ	4.3

02. ජාතික තරඟකාරී ලංසු පටිපාටිය මත ලංසු ඉදිරිපත් කළ යුතුය. කොන්ත්‍රාත් ප්‍රදානයේදී සුදුසුකම් ලබන සාර්ථක ලංසුකරුවන් අසාධු ලේඛනගත නොවිය යුතු අතර ඉදිකිරීම් කර්මාන්ත සංවර්ධන අධිකාරියේ ඉහත කාණ්ඩ යටතේ ලියාපදිංචි වී සිටිය යුතුය.

03.ලංසු අයදුම්පත් 2025.06.18 දින සිට 2025.07.03 දින දක්වා පෙ.ව 9.00 සිට ප.ව 3.00 දක්වා ඉහත දක්වා ඇති පරිදි ආපසු නොගෙවන ගාස්තුව අධ්‍යාපන අමාත්‍යාංශයේ ගිණුම් අංශයේ සරප් වෙත මුදල්

ගෙවීමෙන් අනතුරුව ලබාදෙන මුදල් කුවිතාන්සිය ඉදිරිපත් කර හෝ ආපසු නොගෙවන ගාස්තුව අධ්‍යාපන අමාත්‍යාංශ ලේකම් නමින් ගාල්ල කොටුව ලංකා බැංකුවේ ඇති ගිණුම් අංක 1587423 ට බැර කර රිසිට පත සමග ඔබගේ ඉල්ලීම් ලිපිය ද.ප. අධ්‍යාපන අමාත්‍යාංශයේ **070 7130700** දරණ වටිස්අප් අංකයට පමණක් හෝ acc.moesp@gmail.com ඊ මේල් ලිපිනයට පමණක් යොමු කිරීමෙන් ඔබට අවශ්‍ය ලංසු පත්‍රිකා තැපැල් මගින් හෝ කුරියර් කර හෝ ඊමේල් මගින් හෝ වටිස්අප් මගින් ගෙන්වා ගැනීමට හෝ ලබුදුව, දක්ෂිණපාය අධ්‍යාපන අමාත්‍යාංශයෙන් (බිම් මහල) ගිණුම් අංශයෙන් ලබා ගත හැකිය. වැඩි විස්තර අමාත්‍යාංශයේ 091-2030700 දුරකථන අංකයට වැඩ කරන දින ඇමතීමෙන් හෝ ද.ප. අධ්‍යාපන අමාත්‍යාංශ වෙබ් අඩවියට www.edumin.sp.gov.lk පිවිසීමෙන් අදාළ ලංසු පත්‍රිකා පරීක්ෂා කළ හැකිය.

04. මුද්‍රා තබන ලද ලංසු පත්‍රිකා 2025.07.04 පෙ.ව 11.00 ට පෙර ලැබෙන සේ ලේකම්, දකුණු පළාත් අධ්‍යාපන අමාත්‍යාංශය, දක්ෂිණපාය, ලබුදුව, ගාල්ල යන ලිපිනයට ලියාපදිංචි තැපෑලෙන් එවීමට හෝ අතින් රැගෙන විත් ප්‍රධාන ගණකාධිකාරී නිල කාමරයේ තබා ඇති ටෙන්ඩර් පෙට්ටියට බහාලිය හැකිය. ප්‍රමාද වී ලැබෙන ලංසු ප්‍රතික්ෂේප කරනු ලැබේ.

05. ලංසු විවෘත කිරීම 2025.07.04 දින පෙ.ව 11.00 ට ලංසු පත්‍රිකා භාරගෙන අවසන් වූ විභාග දකුණු පළාත් අධ්‍යාපන අමාත්‍යාංශයේ ප්‍රසම්පාදන කමිටු සභාපතිගේ ප්‍රධානත්වයෙන් අමාත්‍යාංශයේදී සිදු කරන අතර එම අවස්ථාවට ලංසුකරුට හෝ ලංසුකරුගේ බලයලත් නියෝජිතයන් හට සහභාගී විය හැක.

06. ලංසුව සමඟ ඉදිරිපත් කරන ලංසු සුරක්ෂණය ශ්‍රී ලංකා වාණිජ බැංකුවකින් දකුණු පළාත් අධ්‍යාපන අමාත්‍යාංශයේ ලේකම් නමට ලබා ගත් 2025.07. 04 දින සිට 2025.10.04 දක්වා වලංගු ලංසු ඇපකරයක් හෝ අධ්‍යාපන අමාත්‍යාංශයේ ගිණුම් අංශය වෙත මුදල් ගෙවීමෙන් අනතුරුව ලබාදෙන මුදල් කුවිතාන්සියේ පිටපත ලංසු පත්‍රිකාව සමඟ ඉදිරිපත් කළ යුතුය.

07. ලංසු වලංගු කාලය දින 77 කි.

08. ඉදිරිපත් කරනු ලබන කර්මාන්තයට අදාළ ලංසු පිටපත් දෙකකින් යුතුව ඉදිරිපත් කළයුතු අතර එහි මුල් පිටපතෙහි “ මුල් පිටපත “ යනුවෙන් සඳහන් කළ යුතු අතර අනු පිටපතෙහි “ අනුපිටපත “ යනුවෙන් සඳහන් කළ යුතුය. ලංසුපත් වල මුල් පිටපත හා අනුපිටපත වෙන වෙනම කවරවල බහා මුද්‍රා තබා එම කවර දෙක එක් කවරයක බහා එම කවරය මුද්‍රා තබා කවරයේ වම් පස උඩකෙළවරේ කර්මාන්තයේ නම සහ අංකය සඳහන් කළ යුතුය.

09. ඔබ විසින් ඉදිරිපත් කිරීමට නියමිත සෑම ලංසු පත්‍රිකාවෙහිම මිල ගණන් සඳහන් කර ඇති පිටු අංකයන්හි ඔබ විසින් සඳහන් කළ යුතු ඒකක මිල ගණන් හා මුළු මුදල දැක්වෙන තීරය සහ සාරාංශයද (වට්ටම් දැක්වෙන තීරයද ඇතුළත්ව) විනිවිද පෙනෙන සේ සෙලෝටේප් කර ලංසු ඉදිරිපත් කිරීම අනිවාර්ය වේ.

10. ද.ප. අධ්‍යාපන අමාත්‍යාංශය දැනටමත් දකුණු පළාතේ පාසල්වල ඉදිකිරීම් අලුත්වැඩියා හා නඩත්තු කටයුතුවලට අදාළ ව්‍යාපෘති සියයක පමණ ප්‍රසම්පාදන කටයුතු අවසන් කර ඉදිකිරීම් කටයුතු ආරම්භ කර ඇත. එමෙන්ම මෙම ව්‍යාපෘති එකසිය නමයෙහි ද ප්‍රසම්පාදන කටයුතු හැකි ඉක්මනින් අවසන් කර ව්‍යාපෘතිවල වැඩ 2025 වසරේ දෙසැම්බර් මස වනවිට අවසන් කළ යුතු බැවින් ලංසුකරුවන්ගේ ධාරිතාවය පිළිබඳ ලංසු ප්‍රදානයේදී සලකා බලනු ලැබේ.

11.අඩුපාඩු සහිත ලංසුපත්‍රිකා ප්‍රතික්ෂේප කරනු ලබන ලැබේ. මෙම ප්‍රසම්පාදනය සම්බන්ධයෙන් ප්‍රසම්පාදන කමිටුවේ තීරණය අවසාන තීරණය බව සැලකිය යුතුය.

ඒ.යූ.වේලාරත්න,
ප්‍රසම්පාදන කමිටු සභාපති,
දකුණු පළාත් අධ්‍යාපන අමාත්‍යාංශය,
පළමු මහල, දක්ෂිණපාය, ලබුදූව, ගාල්ල.

2025.06.18

දුරකථන අංකය - 0912030700 ඊමේල් - acc.moesp@gmail.com

SECTION 4

FORM OF BID AND QUALIFICATION

INFORMATION

FORM OF BID

Name of Contract : Construction Toilet For at G/ Batapola M.M.V.

To : Secretary
Ministry of Education, Southern Province

Gentleman,

- 1, Having examined the Standard Bidding Document - Procurement of Works - Minor Contracts [ICTAD/ SBD/ 03 - Second Edition, January 2007], Schedule, Specifications, Drawings and Bills of Quantities and addenda for the execution of the above named Works, we/I the undersigned, offer to execute and complete such Works and remedy any defect therein in conformity with the aforesaid Conditions of Contract, Schedule, Specifications, Drawings, Bill of Quantities and Addenda for the sum of Sri Lankan Rupees

(LKR) or such other sums as may be ascertained in accordance with the said Conditions.

- 2, We/I acknowledge that the Schedule forms part of our/my Bid.
- 3, We/I undertake, if our Bid is accepted, to commence the Works as stipulated in the Schedule, and to complete the whole of the Works comprised in the Contract within the time stated in the Schedule.
- 4, We/I agree to abide by this bid for the period stated in the Sub-Clause 15 of Instructions to Bidders or any extended period and it shall remain binding upon us and may be accepted at any time before the expiration of that period.
- 5, Unless and until a formal agreement is prepared and executed this Bid, together with your written acceptance thereof, shall constitute a binding contract between us/me.
- 6, We/I understand that you are not bound to accept the lowest or any Bid you may receive.

Dated this day of 20..... in the capacity of
duly authorized to sign tenders for and on behalf of
..... (IN BLOCK CAPITALS)

Signature :

Name :

Designation :

Address :

Witness :

QUALIFICATION INFORMATION*(to be completed by the bidder and submitted with the Bid)*

Registration	Eligibility Requirement	Bidder's Qualification
Registration number		
Grade	CIDA C8 or above	
Specialty	Buildings	
Expiry Date		

Backlisted Contractors	
Have you been declared as a defaulted contractor by NPA or any other Agency?	
IF yes provide details	

VAT Registration Number	
Construction Program	(attach as annex)
Legal status	Public company/Private Company/Partnership/Sole proprietor

Qualification and experience of key staff	Eligibility Requirement		Bidder's Qualification
	Category, Experience and Qualifications	Required No	Proposed by bidder (Name, experience and Qualifications)
	1 Site Supervisors	1	
	2		
	3		
	4		
List Other information required			

Signature of the Bidder : _____

SECTION 5

SCHEDULE

SCHEDULE

ITB Clause	Conditions of Contract Clause	Item	Data
1	1.1.8	Employer is	<p>Name : <i>Secratory</i></p> <p>Address : <i>Ministry of Education, Southern Province</i> <i>“Dakshinapaya”, Labuduwa, Galle</i></p>
	1.1.10	Engineer is	<p>Name : <i>District Engineer (Buildings)</i></p> <p>Address : <i>District Engineer (Buildings) Office</i> <i>Pettigalawaththa, Galle</i></p>
1 & 13	1.1.21	Summary of Works	<p>The Works consists of</p> <p>Located at : <i>AMBALANGODA</i></p> <p>Contract : <i>Construction Toilet For at G/ Batapola M.M.V.</i></p> <p>Contract Number : <i>G/CSL/25/10</i></p>
1	1.1.14	Intended Completion Date	Intended Completion Date is 90 Days from the Start Date
2		Source of Funds	The source of funds is Clean Sri Lanka
3		Eligibility	The requirement is CIDA C8 or above Buildings
12		Documents of the Bid	Any other information
13	10.10	Price Adjustment	<p>The Contract is not subject to price adjustment in accordance with Sub-Clause 10.10 of the Conditions of Contract.</p> <p>The price adjustment shall be computed in accordance with Option B under sub clause 10.10.</p> <p>Non adjustable element shall be:</p> <p>BOQ Item Numbers :</p> <p>Option B:</p> <p>Type of Construction : Non residential buildings</p>

ITB Clause	Conditions of Contract Clause	Item	Data
16	Bid Security	Bid shall include a Bid Security:	<ul style="list-style-type: none"> ● for an amount LKR 34,000.00 issued by an agency acceptable to Employer using the form for bid security (unconditional guarantee) included in Section 9, Standard Forms, remain valid till 04.10.2025 OR ● Bid Security amount can be paid by cash to the Employer
31	4.4	Performance Security	<p>Amount of Performance Security required is 5% of the Initial Contract Price</p> <p>The form acceptable is unconditional guarantee as standard form as per SBD/03</p>
	6.4	Late Completion	The amount to be paid is 0.05 % of Initial Contract Price per Day, subjected to maximum of 10 % of Initial Contract Price.
	8.1	Notification of Defects	The period for Defect Notification is 90 Days from Taking Over.
	10.3	Retention	<p>The amount of retention is 10 % of certified work done.</p> <p>The maximum amount of retention is 5 % of Initial Contract Price.</p>
	10.12	Advance Payment	Upon the payment of the advance payment in full the Employer shall return the original of the advance payment guarantee to the Contractor.
	13.1 (c)	Insurance, third party	Minimum amount for third party insurance is LKR 100,000.00
	13.1 (a)	Insurance for Works, Material and plant	The minimum cover for insurance of the works and plant and materials is 110% of initial contract price.
	13.1	Insurance for Contractor's Personnel	Minimum amount for Insurance is LKR 500,000.00
33	1.1.11	Adjudicator	CIDA
	14.0	Resolution of Disputes	<p>Deputy Chief Secretary (Engineering Services), Southern Province</p> <p>Fees and types of reimbursable expenses to be paid to the Adjudicator shall be on a case to case basis and shall be shared by the Contractor and the Employer.</p>

SECTION 6

SPECIFICATIONS

TECHNICAL SPECIFICATIONS

Technical specification that are applicable to this project are listed below:

- SCA/3/1 - Irrigation and Land Drainage
- SCA/3/2 - Water Supply Sewerage and Storm Water Drainage
- SCA/3/3 - Reclamation Works
- SCA/3/4 - Ground Water Exploration & Exploitation
- SCA/4/I - Building Works (Vol I)
- SCA/4/II - Building Works (Vol II)
- SCA/5 - Roads and Bridges
- SCA/6 - Coastal Harbour Engineering Works
- SCA/8 - Electrical and Mechanical Works
- ICTAD/DEV/16 - Board & Cast In situ Reinforced Concrete Piles
- ICTAD/DEV/17 - Site Investigation for Building Works & Sample Bill of Quantities

- Any other specification approved by the Government.

Above publications shall be purchase from the Construction Industry Development Authority (CIDA), Savusiripaya, 123. Wijerama Mawatha, Colombo 07.

SECTION 7

BILLS OF QUANTITIES

CONSTRUCTION TOILET FOR AT G/ BATAPOLA M.M.V.

ID	Description	Unit	Qty.	Rate	Amount
(No Topic Assigned)					
	<u>Earth Work</u>				
1	Excavation for foundation by manually in any material except rock requiring blasting, part return fill in and ram, and disposing surplus within site as directed. (not exceeding 5ft depth)-for columns	cu.m	3.00		
2	Excavation for foundation by manually in any material except rock requiring blasting, part return fill in and ram, and disposing surplus within site as directed. (not exceeding 5ft depth)-RRM foundation	cu.m	4.77		
3	Filling under floors with gravel or other approved quality of filling, spread, watered and well rammed in 3" layers (materials not available at site)(Transport within first mile)	cu.m	4.00		
	<i>Total carried to summary</i>				
	<u>Brick Work</u>				
4	Brickwork 112mm in cement : sand mortar 1:5 (Ground Floor)	sq.m	85.00		
5	Construction of soakage pit 1200 x 1200 x 2700 mm (8'-6") invert depth, (8'-6" deep from the sewer pipe) Brick walls 225 mm thick in 1:5 ct: sand mortar, including 1:2 ct, & sand plastering 1/2" thick finished smooth with neat ct. floating up to a depth of 6" below from the invert level of the sewer pipe & surround the con. pad . Concreting Ring beam, cover slab and pad (curb) with 1:2:4(3/4") conc. mixture. Reinforcing cover slab with 10.0 mm twisted deformed steel @ 6" cts. bothways and plastering curb 1:3 ct. & sand, 1/2" thick finished smooth with neat ct. floating 6" below ground level.inc: 2 nr of 10mm dia lifting handles (as per Draw No.SPES/Rate23/Bk-10.)	nr	1.00		
6	Manhole 1'-6"x 1'-6"x 1'-3" (internally) concreting base 4" thick & channels with 1:2:4 (3/4") ct. concrete including 2" thick, concrete screed with 1:3:6 (1") con. mixture. 4" concrete wall with 1:2:4 (3/4")con. mixture . Internally Plastered with 1:3, 3/4" thick ct. mortar with water proofing compound 10% (by cement) weight of cement as super latex 302 or equivalent finished smooth with neat ct. floating including channels & Pad plaster 1:3, 1/2" thick finished smooth with cement floating.shall be water tight. Rate to include for concrete cover slab 3" thick with 1:2:4 (3/4") con. mixture r/f with.10 mm dia. T.S rods @ 6" c/s. both ways, with 2 nos lifting handles. (as per detail Draw No.SPES/Rate23/Bk-15.)	nr	1.00		
	<i>Total carried to summary</i>				

ID	Description	Unit	Qty.	Rate	Amount
	<u>Concretor</u>				
	<i>1.Up to DPC</i>				
7	Cement concrete 1:3:6 (1") up to 3.00 m3(Shuttering paid separately) incl: curing(Grade 15)-Under column base	cu.m	0.65		
8	Cement concrete 1:3:6 (1") up to 3.00 m3(Shuttering paid separately) incl: curing(Grade 15)-Under 110 PVC pipe	cu.m	0.40		
9	Cement concrete 1:2 1/2:5(1") mix: up to 3.0 m3 (Shuttering paid separately) incl: curing-Floor and ramp	cu.m	3.10		
10	Cement Concrete 1 : 1 1/2 : 3 (3/4") (R/F and Shuttering paid separately) (GRADE 25)incl: mixer vibrater and curing-column base	cu.m	0.80		
11	Cement concrete 1 : 1 1/2 : 3 (3/4") in 225x225mm column shafts in ground floor, using mixer and vibrator. (Reinforcement, shuttering and finishes paid separately). (GRADE 25).including curing	cu.m	0.25		
12	Cement Concrete 1 : 1 1/2 : 3 (3/4") (R/F and Shuttering paid separately) (GRADE 25)incl: mixer vibrater and curing-plinth beam	cu.m	0.60		
13	Concreting valve chamber 9"x 9" x 9" (internally) with 1:2:4(3/4) ct. Con. Mixture 3" thick, plastered with 1:2, 1/2" thick ct. mortar , finished smooth with neat ct. floating.. Including 2" thick cover slab R/F with 6 mm dia. M.S. @ 4" c/c. both ways	nr	1.00		
	<i>2.DPC to Roof level</i>				
14	Cement concrete 1 : 1 1/2 : 3 (3/4") in 225 x225mm columns in ground floor, using mixer and vibrator. (Reinforcement, shuttering and finishes paid separately). (GRADE 25).including curing	cu.m	1.10		
15	R.C.C. 1: 1 1/2: 3(3/4") in 4" thick slab in ground floor, using mixer and vibrator. (Reinforcement and shuttering paid separately). (GRADE 25).including curing	cu.m	0.45		
16	Cement concrete 1: 1 1/2: 3(3/4") in 225x225mm beams in ground floor, using mixer and vibrator. Incl. curing (Reinforcement, shuttering and finishes paid separately).(GRADE 25).	cu.m	0.60		
17	Lintel, cement concrete 1:2:4(3/4") (Gr. 20) 4 1/2" x 6" (Reinforcement paid separately). Rate including shuttering & curing	m	12.00		
18	Concrete work table with 1:2:4(3/4") con. mixture 3" thick R/F with 10mm dia: tore steel at 150mm c/c bothways including 15mm plywood formwork to achieve the smooth finish of the soffit.	sq.m	1.80		

ID	Description	Unit	Qty.	Rate	Amount
19	Cement concrete 1:2:4(3/4") (Gr.20 concrete) (R/F and Shuttering paid separately)incl: curing.Rate to include using mixture & vibrator-window sill,stiffner	cu.m	0.65		
	<i>Total carried to summary</i>				
	<u>Reinforcement</u>				
	<u>1.Up to DPC</u>				
20	10mm Tor steel in Column base,stiffner-Up to DPC	kg	32.00		
21	12 mm Tor steel in column shaft	kg	37.50		
22	10mm Tor steel in plinth	kg	51.00		
23	6mm Steel links in column shaft and plinth	kg	12.50		
	<u>2.DPC to Roof level</u>				
24	12mm Tor steel in column	kg	75.00		
25	12mm Tor steel in beams	kg	56.50		
26	10mm Tor steel Lintol,stifner>window sill Ground floor	kg	61.00		
27	10mm Tor steel in slab at 150 mm c/c both ways	kg	33.70		
28	6mm Mild Steel in columns ,Beams, lintol,stifner,sill	kg	48.00		
	<i>Total carried to summary</i>				
	<u>R R Masonry</u>				
29	Random Rubble Masonry in cement mortar 1:5 in substructure (6"- 9" rubble)	cu.m	6.50		
	<i>Total carried to summary</i>				
	<u>Pavior</u>				
30	600 x 600 mm Ceramic tiles with all specials supplying and fixing to floors including raking plaster 1:3 and bedding in Tile Motar(Swistec/ tokyo super) & pointed with tile grout. (Lanka tiles Mat finish, Prime cost Rs. 1,700)as per the engineer's instruction.	sq.m	23.00		
31	Wall Tiles glazed colour 300 x 600 mm with all specials , supplying and fixing to walls including raking 1:3 plaster bedding in tile mortar and pointed with tile grout to match the tiles.(Use Lanka tiles)as per the engineer's instruction.	sq.m	23.10		
32	Tile skirting 100 mm high and all specials supplying and fixing to walls including raking plaster and bedding in tile mortar 1:3 & pointed with tile grout.(Lanka 600 x 600 mm Gloss finish tiles - Prime Cost Rs. 1,600)as per the engineer's instruction. (swistec)	m	4.65		
	<i>Total carried to summary</i>				

ID	Description	Unit	Qty.	Rate	Amount
Plasterer					
33	Cement Sand plastering to wall 1:5, (5/8") thick semi rough G: floor rate to include curing-external	sq.m	112.00		
34	Cement Sand plastering to wall 1:5, (5/8") thick semi rough G: floor rate to include curing-Internal	sq.m	42.00		
35	3/4" thk Rendering in Cement and sand 1:3 in floors finished smooth Rate to include curing, - Ground floor-In plinth	sq.m	6.20		
36	1/2" thk 1:3 Cement Rendering finished smooth with neat cement floating, Ground floor(sand to be sieved with 1/8" nets) Rate to include curing	sq.m	20.00		
37	3/8 " Thick plastering to RCC beams, slab soffit , column in cement and sand 1:3 (G: Floor)	sq.m	7.00		
38	Reveals exceeding 100 mm, but not exceeding 200 mm wde with 1:5 ct : sand mortar 16.0 mm thick finished semi rough. (Ground floor)	m	35.50		
39	1:3 Rendering cement ,1" thick cement coping finish smooth with neat cement floating (in Ground Floor)	sq.m	6.70		
40	3/4" thick in cement,sand 1:3 with Water proofing compound(10% by weight of cement)as super latex-302 or equivalent finished smooth with cement floating	sq.m	4.00		
41	Prepare (travel cuts) revels (25 x 12.5 mm deep) on external plastered wall surface at 300mm C/C intervals	m	58.00		
	<i>Total carried to summary</i>				
Tinker					
42	Zn coated (.47 mm thick AZ150 - thickness certificate necessary)colour sheet - Flashing 1'-6"girth overall 3 times bent with end lap not less than 6" lead soldered, turned and tucked up to not less than 6" into o chase cut in wall and pointed in cement mortar 1:3 and dressed over roof covering not less than 1'-0" wide.	m	1.80		
	<i>Total carried to summary</i>				
Electrical					
43	Supply and fixing 01 No. Pendent type lamp(9 W LED Bulb - efficacy:85 lumen/W or above with two years warranty) with GANG switch Complete with necessary concealed conduit wiring as per working order.(Switch - ACL/Chint/Krypton/Orange) (Cable - ACL/Kelani/Orange/Sierra) (fittings - krypton/Polycrome/Orange) (Conduit - krypton/Polycrome) (Bulb - Orange electric ECO LITE/ ZENOI/ Kelani)) [Cable SLS 733 Switch SLS 1000 Bulb SLS 984	nr	5.00		

ID	Description	Unit	Qty.	Rate	Amount
44	Supplying and fixing 1 Nr. 1 pole MCB (6 A/ 10A/ 16A/ 20A/ 32A) (Make -Orange electric 10kA/ Schneider/Chint NB7/EB) Original Makes with company warranty Certificate. all complete as per instruction	nr	1.00		
45	Supplying and fixing (7/0.67)(Cu/PVC/PVC) (Twin) P.V.C (Cu) Sub Main Wire (2.5 mm ²) [(Cable - ACL/Kelani/Orange/Sierra) Cable SLS 733]	m	15.00		
46	Supplying and fixing Ceramic pulley with "D" bracket for Electricity connection. all complete as per instruction	nr	1.00		
47	Supply and Fixing 20mm Dia PVC conduit including fixing materials. All complete as per instruction.(Conduit - krypton/Polycrome)	m	10.00		
48	Supplying and Fixing 400ABC Enclosure Box (Surface mounted) fixed with brass screws all complete as per Instruction.(Enclosure-Polycrome)	nr	1.00		
49	Supplying and fixing 40Amp/30mA/ 2 pole -RCCB (Make - Orange electric 10kA/ Schneider/Chint NL1) Original Makes with company warranty Certificate. all complete as per instruction	nr	1.00		
	<i>Total carried to summary</i>				
	<u>Roofer</u>				
50	Approved Quality Corrugated Asbestos sheets roofing 1/4"x7" j bolt with nut & washers on imported timber frame 100 x 75 mm wall plate, 150 x 50 mm ridge, 100 x 50 mm rafters and 50 x 50mm beares supplied fixed complete including frame with applied two coats of clear wood preservative (100 x 50 mm rafter fixed in 750mm C/C) -Ridging measured separately. Ground floor. (Reffer draw. No. SPES/Rate23/Ro- 14)	sq.m	32.50		
51	Ridging, Calicut pattern, bedded in cement and lime mortar 1:1:4, colour to match tiles. (Keep went opening every vally point).	m	4.75		
	<i>Total carried to summary</i>				
	<u>Carpenter & Joiner</u>				
52	8"x3/4 " (200x20mm) Boards , barge , valance, fascia, 3/4" (20mm) thick in class II local (Ginisapu) timber prepared by using multi purpose wood working machine , fixed complete with necessary 2" Iron screws .applying one coat of wood presavative, one coat of aluminium primer & two coats of enamel paint	m	11.20		

ID	Description	Unit	Qty.	Rate	Amount
53	10" x 3/4 " Boards , barge , valance, fascia, 3/4" thick in class II local (Ginisapu) timber prepared by using multi purpose wood working machine , fixed complete with necessary 2" Iron screws applying one coat of wood preservative, one coat of aluminium primer & two coats of enamel paint	m	14.80		
	<i>Total carried to summary</i>				
<u>Painter & Decorator</u>					
54	Painting walls with one coats of Acrylic wall filler for external wall (new work or after preparation of old wall) -Ground floor	sq.m	113.00		
55	Applying skim coat & one coats of wall filler for internal wall. (semi rough plastered new work or after preparation of old wall)	sq.m	42.00		
56	Wethershield paint to external and internal faces of wall 02coat apply using roller brush 2" brush (ground Floor)-External and Internal walls	sq.m	155.00		
57	Painting plinth with floor paint, 2 coats including preparing surface	sq.m	6.20		
	<i>Total carried to summary</i>				
<u>Plumber</u>					
58	Supplying and fixing, Closet, pedestal type, with low level glazed earthenware flushing cistern,plastic seat cover(OTTO, RSL or equivalent.) rate to include 1/2" watertec angle valve, 450mm flexible hose (all accessories water tech or s lon)Suitable fittings can be decided by the engineer depending on the site situation	nr	1.00		
59	Supplying and fixing Bidet shower Plastic (water tec or equivalent)" with 1/2" angle valve PVC	nr	2.00		
60	Supplying and fixing Closet squatting type (OTTO) with trap and foot rest complete with cistern (high level)etc. including 1/2" stop valve and special flushing cistern(OTTO) complete with flush pipes, chain, overflow pipe ...etc.	nr	1.00		
61	Suppling and fixing PVC 1/2"bib tap, (Water Tec/ S lon)	nr	2.00		
62	Supplying & fixing 150 mm x 150mm plastic Gully trap with cover	nr	4.00		
63	Supplying and fixing urinal ball type (OTTO , RSL, ceramic or equivalent) with urinal flush valve c x 2001 (Rocell), (A-186) round bottle trap (1 1/4") Rocell and waste coupling with waste outlet	Nr	4.00		

ID	Description	Unit	Qty.	Rate	Amount
64	Supply & fixing sub zero wash basin (Rocell) white on work table with (A186) round bottle trap (1 1/4") (Rocell), pillar basin tap (Rocell), wash basin coupling waste outlet without overflow - brass (1 1/4). Rate to include angle valve, 450mm long flexible horse spain. (Rocell / Desigle or equivalent)	Nr	2.00		
65	Supplying and fixing Pipes P. V. C. 1/2" - PNT 14 rate to include socket & joints and also include excavating backfilling or breaking wall or floor upto required depth	m	15.00		
66	Supplying and fixing Pipes P. V. C. 1" - PNT 7 rate to include socket & joints and also include excavating backfilling or breaking wall or floor upto required depth	m	6.00		
67	Supplying and fixing Pipes P. V. C. 1 1/4" - PNT 7 rate to include socket & joints and also include excavating backfilling or breaking wall or floor upto required depth	m	4.00		
68	Supplying and fixing Pipes P. V. C. 1 1/2" - 600 Type PNT 7 rate to include socket & joints and also include excavating backfilling or breaking wall or floor upto required depth	m	3.00		
69	P.V.C. pipes 110 mm dia.(4") type 250 laid under ground not exceeding 600 mm depth. Rate to include for necessary excavation, ct.Con. Bedding & covering with 1:3:6 (1") conc. mixture. Concrete Paid Seperately. For special purpose only	m	6.00		
70	Supplying and fixing Stop valve, Plastic 1/2" ."S-lon"/"Water Tec"	nr	1.00		
71	Supplying and fixing Stop valve, Plastic 1" ."S-lon /Water Tec"	nr	1.00		
72	Supplying and fixing 1000 liters Arpico Plastishell water Tank - hybrid double layer (Pipes, Stop Valve, Ball Valve,Float valve measured separately)	nr	1.00		
73	Supplying and fixing, 1/2" tank float valve plastic	nr	1.00		
74	Supplying and fixing Soap tray (ABS Plastic)	nr	4.00		
75	Mirror, bevelled, bath room type, square shape ("Desigle or equivalent") suppling and Fixing to wall with Rawl plugs (18"x24")	nr	2.00		
76	Supplying and fixing Pipes P. V. C. 2" - 600 Type PNT 7 rate to include socket & joints and also include excavating backfilling or breaking wall or floor upto required depth	m	15.00		
77	Supplying and fixing PVC Door bend 110mm	nr	1.00		
78	Supplying and fixing stop valve, Plastic 1 1/2" ."S-lon /Water Tec"	nr	1.00		
79	Supplying and fixing Towel rail ABS plastic(navrang/sliva world) or approved quality, to walls with rawl plug- (600 mm long)	nr	1.00		
	Total carried to summary				
	Alluminium				

ID	Description	Unit	Qty.	Rate	Amount
80	Supplying, fabricating and fixing Aluminium natural anodized fully composite board (Al/PVC Composite board) door with frame (1 Nr door sash) as per Drg. No. SPES/RATE23/D/04. Overall size of the door frame is 750x1950mm. (Size may be changed according to the site) Door frame consisting top and side bars (50x25x0.9mm box bars) with 18x11mm door stopper bar using 5/32x3/8" Al rivets and fixing with 38x38x2.5mm Al bracket using 1/8x3/8" Al rivets. Frame should be fixed to wall with 8 Nrs of No 6 rowl plugs and 8x3" ST screws. Door sash consisting top, sides, bottom and 2 Nrs of middle bars (50x25x0.9mm box bars). Sash frame should be fixed with 38x38x2.5mm Al bracket using 1/8x3/8" Al rivets, 3mm thick Al/PVC double side composite board for full door should be fixed using 1/8x3/8" Al rivets. Rate should be included for supplying and fixing required Mohair beading, 3 Nrs of 100x75mm Aluminium hinges using 5/32x3/8" Al rivets, 2 Nrs of Aluminium plate door handle, 2 Nrs of 2" Al Barrel Bolt, Screws, Pop rivets, Silicone etc.	sq.m	3.00		
81	Supplying, fabricating and fixing Aluminium natural anodized paneled door (Top panel and bottom panel – Al/PVC Composite board) with frame (1 Nr door sash and 2 Nrs 450mm height louver panels at the top) as per Drg. No. SPES/RATE23/D/L/02, Option 1. Overall size of the door frame is 1050x2550mm including 450mm high louvers. (Size may be changed according to the site) Door frame consisting top bar (76x32mm), side bars (76x32mm, use 18x11mm door stopper bar at louver height with required Al rivets) horizontal middle bar (76x32mm with 70x4mm clip bar) and vertical middle bar (46x41mm) with 18x11mm door stopper bar around door frame using 5/32x3/8" Al rivets, and fixing with 50x18x2mm Al bracket using 1/8x3/8" Al rivets and 8x1 1/2" ST screws. Louver blades (52x34mm) should be fixed to louver frame bars (20x37mm) using 1/8x1/2" Al rivets, and louver panel fixed to frame using 1/8x1/2" Al rivets. Frame should be fixed to wall with 12 Nrs of No 6 rowl plugs and 8x3" ST screws. Door sash consisting top bar (80x42mm), side bars (66x45mm hinges side, 70x45mm lock side), middle bar (100x42mm) and bottom bar (120x42mm). 16x15mm clip bar should be used for required bars. Sash frame should be fixed with 38x38x2.5mm Al bracket using 1/8x3/8" Al rivets, 8mm dia. treaded bar with nuts for top and bottom bars. 4mm thick Al/PVC double side composite board for bottom panel and top panel should be fixed. Rate should be included for supplying and fixing required Mohair beading, 3303, 3303A and 455S Rubber beadings, 4 Nrs of 100x75mm Al hinges using 5/32x3/8" Al rivets, Al natural anodized door handle (102x40mm) pair with cap nuts, Door lock (CL or equivalent approved by the Engineer), Screws, Pop rivets, Silicone etc.	m ²	2.74		

ID	Description	Unit	Qty.	Rate	Amount
82	Supplying, fabricating and fixing Aluminium natural anodized casement Fanlight with frame (1 Nrs fanlight sash and 1 Nrs louver at the top) as per Drg. No. SPES/RATE23/FL/L/01. Overall size of the fanlight frame is 600x1050mm. (Size may be changed according to the site) Fanlight frame consisting top, bottom, side bars (41x31mm) and horizontal middle bar (46x41mm), and fixing using 38x38x2.5mm Al angle bracket with 1/8x3/8" Al rivets. Frame should be fixed to wall with 10 Nrs of No 6 rowl plugs and 8x2" ST screws. Louver blades (52x34mm) should be fixed to louver frame bars (20x37mm) using 1/8x1/2" Al rivets, and louver panel fixed to frame using 1/8x1/2" Al rivets. Fanlight sash consisting top, bottom and side bars (40x35mm) should be fixed using 8x1 1/2" ST screws, and 5mm thick clear glass. Rate should be included for supplying and fixing required 437K Rubber beading, 674U Rubber beading, 2 Nrs of 14" SS 304 bar hinges using 5/32x3/8" Al rivets, 1 Nrs of heavy quality Al fasteners using 5/32x3/8" Al rivets, Screws, Pop rivets, Silicone etc.	sq.m	0.81		
83	Supplying, fabricating and fixing Aluminium natural anodized sliding window with frame (2 Nrs window sashes and 2 Nrs louvers at the top) as per Drg. No. SPES/RATE23/SW/L/01. Overall size of the window frame is 1200x1650mm including 450mm high louvers. (Size may be changed according to the site) Window frame consisting top bars (70x30mm), bottom bar (70x30mm) and side bars (73x25mm), horizontal middle bar (70x32mm) with 70x18mm clip bar, vertical side clip bars (73x18mm) for louver height, vertical middle bar (46x41mm) for louver height, and fixing with 8x1 1/2" ST screws and required Al rivets. Louver blades (52x34mm) should be fixed to louver frame bars (20x37mm) using 1/8x1/2" Al rivets, and louver panel fixed to frame using 1/8x1/2" Al rivets. Frame should be fixed to wall with 14 Nrs of No 6 rowl plugs and 8x2" ST screws. Window sash consisting top bar (28x32mm), bottom bar (22x56mm) and side bars (30x26mm one side, 30x32mm lock side) should be fixed using 8x1 1/2" ST screws, and 5mm thick clear glass. Rate should be included for supplying and fixing required 674U Rubber beading, 4 Nrs of Adjustable rollers, 8 Nrs of Guide runners for top, 1 Nr of heavy quality Crescent lock using 5/32x3/8" Al rivets, Screws, Pop rivets, Hole buttons, Silicone etc.	sq.m	2.28		

G/CSL/25/10/1

ID	Description	Unit	Qty.	Rate	Amount
84	Supplying, fabricating and fixing Aluminium natural anodized sliding window with frame (4 Nrs window sashes and 4 Nrs louvers at the top) as per Drg. No. SPES/RATE23/SW/L/02. Overall size of the window frame is 2400x1650mm including 450mm high louvers. (Size may be changed according to the site) Window frame consisting top bars (70x30mm), bottom bar (70x30mm) and side bars (73x25mm), horizontal middle bar (70x32mm) with 70x18mm clip bar, vertical side clip bars (73x18mm) for louver height, vertical middle bar (46x41mm) for louver height, and fixing with 8x1 1/2" ST screws and required Al rivets. Louver blades (52x34mm) should be fixed to louver frame bars (20x37mm) using 1/8x1/2" Al rivets, and louver panel fixed to frame using 1/8x1/2" Al rivets. Frame should be fixed to wall with 18 Nrs of No 6 rowl plugs and 8x2" ST screws. Window sash consisting top bar (28x32mm), bottom bar (22x56mm) and side bars (30x26mm one side, 30x32mm lock side) should be fixed using 8x1 1/2" ST screws, and 5mm thick clear glass. 30x16mm bar should be fixed to one middle sash using 5/32x1/2" Al rivets. Rate should be included for supplying and fixing required Mohair beading, 674U Rubber beading, 8 Nrs of Adjustable rollers, 16 Nrs of Guide runners for top, 2 Nr of heavy quality Crescent lock using 5/32x3/8" Al rivets, Screws, Pop rivets, Hole buttons, Silicone etc.	sq.m	3.68		
	<i>Total carried to summary</i>				
	<u>Form work</u>				
85	Shuttering for column shaft 225x225mm including 2mm iron plate and 25mm x 25mm x3mm angle iron welded to bended plate horizontally at 300mm c/c. Rate to include U clips,acro jacks.and dismantling same when required (Rate to include 100mm high 3mm thick sponge layer stick on around concrete column at every lapping face) -(As per detail Drawing No SPES/Rate 23/Fw-09)Ground floor	sq.m	3.80		
86	Shuttering for column shaft 225x225mm including 2mm iron plate and 25mm x 25mm x3mm angle iron welded to bended plate horizontally at 300mm c/c. Rate to include U clips,acro jacks.and dismantling same when required (Rate to include 100mm high 3mm thick sponge layer stick on around concrete column at every lapping face) -(As per detail Drawing No SPES/Rate 23/Fw-09)Ground floor	sq.m	19.00		
87	Shuttering for floor slab concrete including 15 mm plywood sheets, 4" x 2" Class (II) timber joists and necessary props. up to 12'-00" height. (Rate to include dismantling same when required). Ground floor	sq.m	3.50		
88	Shuttering for beam sides & soffit in 15 mm thk plywood sheets ,Class (II) timber, joists and necessary props 450mm c/c etc. (Rate to include dismantling same when required) ground floor	sq.m	7.20		

ID	Description	Unit	Qty.	Rate	Amount
89	Shuttering for 4 1/2"X 3"concrete coping using Class (II) timber planks (Rate to include dismantling same when required).for both sides	m	8.50		
90	Shuttering for 0'-4 1/2"x0'-9"concrete stiffener including Class (II) timber planks and joists necessary props. (Rate to include dismantling same when required).	sq.m	6.75		
91	Sawn timber (class II) formwork for sides of foundation footings.	sq.m	8.75		
92	Shuttering for 1"X 3"Plinth beam using Class (II) timber planks (Rate to include dismantling same when required).for both sides	m	24.50		
	<i>Total carried to summary</i>				

CONSTRUCTION TOILET FOR AT G/ BATAPOLA M.M.V.

Rate Schedule	Amount
(No Topic Assigned)	
<i>Earth Work</i>	
<i>Brick Work</i>	
<i>Concretor</i>	
<i>Reinforcement</i>	
<i>R R Masonry</i>	
<i>Pavior</i>	
<i>Plasterer</i>	
<i>Tinker</i>	
<i>Electrical</i>	
<i>Roofer</i>	
<i>Carpenter & Joiner</i>	
<i>Painter & Decorator</i>	
<i>Plumber</i>	
<i>Alluminium</i>	
<i>Form work</i>	
Total	

Total :

Less PS:

.....

Discounts (.....%):

.....

(+) PS:

Contract Amount:

Construction Toilet For at G/ Batapola M.M.V.

(A) BOQ Total	= LKR	_____
(B) Less for Provisional Sums	= LKR	_____ -
(C) Sub Total (A-B)	= LKR	_____
(D) Less for Discount (If Any) (..... %)	= LKR	_____
(E) Sub Total (C-D)	= LKR	_____
(F) Add for Provisional Sums	= LKR	_____ -
Total Bid Amount (E+F)	= LKR	=====
<i>(Excluding VAT, Carried to Form of Bid)</i>		

Total Bid Amount in Words _____

VAT 18%	= LKR	_____
Grand Total	= LKR	=====

Note:

Bidders are requested to provide discounts, if any, as a percentage. Otherwise, it will be converted to a percentage. Your discount will also be applied to variations in quantity."

Signature of Bidder

SECTION 8

DRAWINGS

SECTION 9

STANDARD FORMS

- **Form of Bid Security**

[Letter heading paper of the procuring entity]

[this Guarantee form shall be filled in accordance with the instructions indicated in brackets]

-----[insert
issuing agency's name, and address of issuing branch or office]

Beneficiary : -----[insert
employer position, office and address]

Date : ----- [insert date]

BID SECURITY

BID GUARANTEE No. : ----- [insert number]

We have been informed that [insert name
of the bidder] (hereinafter called "the bidder") has submitted to you its bid dated
[insert date](hereinafter called "the Bid") for the execution of
.....[insert name of
Contract] under Invitation for Bids No.[insert IFB number] ("the IFB").

Furthermore, we understand that, according to your conditions, Bids must be supported by a Bid Guarantee.

At the request of the bidder, we.....
..... [insert name of issuing agency] hereby irrevocably undertake to pay you any sum or sums
not exceeding in total an amount of LKR....., [insert amount in figures]
..... [insert amount in words] upon
receipt by us of your first demand in writing accompanied by a written statement stating that the Bidder is in
breach of its obligation(s) under the bid conditions, because the Bidder:"

- (a) has withdrawn its Bid during the period of bid validity specified; or
- (b) does not accept the correction of errors in accordance with the Instructions to Bidders
(hereinafter "the ITB"); or
- (c) having been notified of the acceptance of its Bid by the Employer during the period of bid validity,
(i) fails or refuses to execute the Contract Form, if required, or (ii) fails or refuses to furnish the
Performance Security, in accordance with the ITB.

This Guarantee shall expire: (a) if the bidder is the successful bidder, upon our receipt of copies of the
Contract signed by the bidder and of the Performance Security issued to you by the bidder; or (b) if the
bidder is not the successful bidder, upon the earlier of the successful bidder furnishing the performance
security, otherwise it will remain in force up to[insert date]

Consequently, any demand for payment under this Guarantee must be received by us at the office on or before
that date.

[signature(s) of authorized representative(s)]

Check List for Bidders

Bidders are advised to fill the following table:

ITEM	ITB Clause	YES (tick)	REFERENCE
Form of Bid			
Addressed to the Employer?	18		
Completed?	18		
Signed?	18		
Bid Security (if required)			
Addressed to the Employer?	16		
Format as required?	16		
Issuing Agency as specified?	16		
Amount as requested?	16		
Validity 28 days beyond the validity of Bid?	16		
Qualification Information			
All relevant information completed?	4		
Signed?	4		
Addendum			
Content of the addendum (if any) taken in to account?	10		
BID Package			
All the documents given in ITB Clause 12 enclosed in the original and copy?	12		
ITB Clause 19 followed before Sealing the Bid Package?	19		