



**MINISTRY OF EDUCATION
SOUTHERN PROVINCE**

BIDDING DOCUMENT

FOR

**PREPARATION A OFFICE ROOM IN THE GROUND FLOOR OF
90X25 TWO STORY BUILDING AT H/ MAHAGALWEWA K.V.**

Issued to :

Date :

Contract No :

Employer : Secretary,
Ministry of Education,
Southern Province.

CONTENTS

Volume 1

Section 1	Instructions to Bidders
Section 2	Standard Forms (Contract)
Section 3	Conditions of Contract

Volume 2

	Invitation for Bids
Section 4	Form of Bid and Qualification Information
Section 5	Schedule
Section 6	Specifications
Section 7	Bills of Quantities
Section 8	Drawings
Section 9	Standard Forms (Bid)

Volume 1 consisting of section 1, section 2, section 3 will be applicable for this contract shall be given volume 1 of “Standard Bidding Document, Procurement of Works, Minor Contracts”, CIDA publication no: CIDA/SBD/03, Second Edition, January 2007, publish by Construction Industry Development Authority (CIDA), Savusiripaya, 123. Wijerama Mawatha, Colombo 07.

The above Document will not be issued with the Bidding Document and Bidder is advised to purchase it from CIDA.

INVITATION FOR BIDS

ප්‍රසම්පාදන දැන්වීම

දකුණු පළාත් අධ්‍යාපන, ඉඩම් හා ඉඩම් සංවර්ධන, මහා මාර්ග හා ප්‍රවාහන අමාත්‍යාංශය

දකුණු පළාත් සභාව

පළාත් නිශ්චිත සංවර්ධන ප්‍රදාන, ක්ලීන් ශ්‍රී ලංකා වැඩසටහන හා නඩත්තු සැලැස්ම 2025 යටතේ ක්‍රියාත්මක කරනු ලබන පහත සඳහන් වැඩ යෝජනා සඳහා සුදුසුකම් ලත් කොන්ත්‍රාත් කරුවන්ගෙන්, දකුණු පළාත් අධ්‍යාපන අමාත්‍යාංශයේ ප්‍රසම්පාදන කමිටු සභාපති විසින් ලංසු පත් කැඳවනු ලැබේ.

අනු අංකය	ව්‍යාපෘති අංකය	පාසල	වැඩ විස්තරය	කර්මාන්තය ඉටු කරනු ලබන ව්‍යාපෘති සැලැස්ම	ආපසු නොගෙවනු ලබන ඇප තැන්පත් මුදල රු.	ලංසු සුරක්ෂණ වටිනාකම රු.	අවශ්‍ය CIDA ලියාපදිංචිය	මුළු ඊරිවැය ඇස්තමේන්තු මුදල vat සමග රු. මි.
1	G/C/25/34	ගා/උඩුගම ම.වි	70*25 දෙමහල් ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	පළාත් නිශ්චිත	2,500.00	34,000.00	C 8 හෝ ඉහළ	4.34
2	G/C/25/35	ගා/හියාරේ නැහෙනහිර ක.වි	90*25 ගොඩනැගිල්ලේ කොරිඩෝර් ඉදිකිරීම	පළාත් නිශ්චිත	1,500.00	26,000.00	C 9 හෝ ඉහළ	3.40
3	G/C/25/36	ගා/තිත්තගල්ල අවනිකිත ක.වි	180*25 ප්‍රධාන ශාලාවේ වහල අලුත්වැඩියාව	පළාත් නිශ්චිත	2,500.00	35,000.00	C 8 හෝ ඉහළ	4.41
4	G/C/25/37	ගා/හපුගල ප්‍රා.වි	මායිම් තාප්පය ඉදි කිරීම	නඩත්තු සැලැස්ම	1,500.00	27,000.00	C 9 හෝ ඉහළ	3.46
5	G/C/25/38	ගා/නරාවල ම.වි	80*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	32,000.00	C 8 හෝ ඉහළ	4.10
6	G/C/25/39	ගා/පංචාලිය ප්‍රා.වි	පාසල් ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	21,000.00	C 9 හෝ ඉහළ	2.73
7	G/C/25/40	ගා/කළුයාණනිස්ස විද්‍යාලය	80*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	22,000.00	C 9 හෝ ඉහළ	2.88
8	G/C/25/41	ගා/ජයවර්ධන විද්‍යාලය	80*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	25,000.00	C 9 හෝ ඉහළ	3.14
9	G/C/25/42	ගා/පැදින්තොරුව සරණපාල	60*20 ගොඩනැගිල්ලේ වහල	නඩත්තු සැලැස්ම	1,500.00	26,000.00	C 9 හෝ	3.35

		ජයන්ති ප්‍රා.වි	අලුත්වැඩියාව				ඉහළ	
10	G/C/25/43	ගා/ඇත්තිලිගොඩ සුදර්ශි ම.වි	100*25 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	30,000.00	C 9 හෝ ඉහළ	3.91
11	G/C/25/44	ගා/මීගහගොඩ ක.වි	50*20 විද්‍යාගාර ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	31,000.00	C 9 හෝ ඉහළ	3.93
12	G/C/25/45	ගා/කඩිනිංගල ම.වි	70*20 දෙමහල් ගොඩනැගිල්ලේ විදුලි පද්ධතිය නවීකරණය	නඩත්තු සැලැස්ම	1,500.00	17,000.00	C 9 හෝ ඉහළ	2.12
13	G/C/25/46	අම්බලන්ගොඩ කලාප අධ්‍යාපන කාර්යාලය	කාර්යාල ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	20,000.00	C 9 හෝ ඉහළ	2.49
14	G/C/25/47	ගා/වටරැක ශ්‍රී සෝභිත විද්‍යාලය	40*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	25,000.00	C 9 හෝ ඉහළ	3.22
15	G/C/25/48	ගා/විද්‍යානන්ද ක.වි	පැති බැම්ම අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	34,000.00	C 8 හෝ ඉහළ	4.40
16	G/C/25/49	ගා/උනන්නවිටිය රේවත ම.වි	90*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	36,000.00	C 8 හෝ ඉහළ	4.66
17	G/C/25/50	ගා/සිරි පඬංකර ප්‍රා.වි	80*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	25,000.00	C 9 හෝ ඉහළ	3.15
18	G/C/25/51	ගා/බටදූව සිරි රතනචෝති ම.වි	90*25 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	26,000.00	C 9 හෝ ඉහළ	3.28
19	G/C/25/52	ගා/අක්මීමණ ම.වි	100*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	38,000.00	C 8 හෝ ඉහළ	4.97
20	G/C/25/53	ගා/ආනන්ද විජය විද්‍යාලය	90*25 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	25,000.00	C 9 හෝ ඉහළ	3.21
21	G/C/25/54	ගා/ඉඳුරුව ම.වි	120*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	3,000.00	49,000.00	C 8 හෝ ඉහළ	6.47
22	G/C/25/55	ගා/තලංගහ සරස්වතී දෙමළ	වැසිකිළ පද්ධතිය	පළාත්	1,000.00	16,000.00	C 9 හෝ	1.99

		පාසල	ඉදි කිරීම	නිශ්චිත			ඉහළ	
23	G/C/25/56	ගා/දික්කුඹුර සිද්ධාර්ථ ම.වි	120*30 ප්‍රධාන ශාලාව නවීකරණය	පළාත් නිශ්චිත	2,500.00	40,000.00	C 8 හෝ ඉහළ	5.29
24	G/C/25/57	ගා/ලේල්වල ක.වි	80*20 ගොඩනැගිල්ල අලුත්වැඩියාව	පළාත් නිශ්චිත	3,500.00	75,000.00	C 8 හෝ ඉහළ	9.93
25	G/C/25/58	ගා/පොරවගම ක.වි	පැති බැම්ම අලුත්වැඩියාව	පළාත් නිශ්චිත	2,500.00	34,000.00	C 8 හෝ ඉහළ	4.39
26	G/C/25/59	ගා/ගනේගම රෝමානු කතෝලික පාසල	80*20 නව ගොඩනැගිල්ල ඉදි කිරීම	පළාත් නිශ්චිත	1,500.00	20,000.00	C 9 හෝ ඉහළ	2.60
27	G/C/25/60	ගා/ශ්‍රීපති ම.වි	80*20 දෙමහල් ගොඩනැගිල්ල ඉදි කිරීම	පළාත් නිශ්චිත	2,500.00	37,000.00	C 8 හෝ ඉහළ	4.79
28	G/C/25/61	ගා/මාමනදොළ ක.වි	90*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	පළාත් නිශ්චිත	2,500.00	32,000.00	C 8 හෝ ඉහළ	4.15
29	G/C/25/62	ගා/උක්වත්ත විද්‍යාලය	90*25 තෙමහල් ගොඩනැගිල්ලේ ඉදි කිරීම (ඉතිරි වැඩ)	පළාත් නිශ්චිත	2,500.00	41,000.00	C 8 හෝ ඉහළ	5.42
30	G/C/25/63	ගා/අක්කරවිස්ස ක.වි	මායිම් තාප්පය අලුත්වැඩියාව	පළාත් නිශ්චිත	1,500.00	25,000.00	C 9 හෝ ඉහළ	3.21
31	G/C/25/64	ගා/කළුවලගල ක.වි	40*20 ගොඩනැගිල්ල ඉදි කිරීම	පළාත් නිශ්චිත	3,000.00	46,000.00	C 8 හෝ ඉහළ	6.07
32	G/C/25/65	ගා/අවිත්තාව නාලන්දා ම.වි	80*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	පළාත් නිශ්චිත	1,500.00	29,000.00	C 9 හෝ ඉහළ	3.73
33	G/C/25/66	ගා/මහින්ද රාජපක්ෂ ම.වි	මායිම් තාප්පය අලුත්වැඩියාව	පළාත් නිශ්චිත	3,000.00	61,000.00	C 8 හෝ ඉහළ	7.88
34	G/C/25/67	ගා/ගුණානන්ද ප්‍රා.වි	50*25 ගොඩනැගිල්ල අලුත්වැඩියාව	පළාත් නිශ්චිත	1,500.00	17,000.00	C 9 හෝ ඉහළ	2.16
35	G/C/25/68	ගා/බී.ටී.එස් විද්‍යාලය	80*20 ගොඩනැගිල්ල	නඩත්තු සැලැස්ම	2,500.00	32,000.00	C 8 හෝ	4.07

			අලුත්වැඩියාව				ඉහළ	
36	G/C/25/69	ගා/මාවඩවිල ම.වි	90*25 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	24,000.00	C 9 හෝ ඉහළ	3.01
37	G/C/25/70	ගා/සිරිනිවාස ම.වි	100*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	40,000.00	C 8 හෝ ඉහළ	5.31
38	G/C/25/71	ගා/දොළහේන ක.වි	80*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	43,000.00	C 8 හෝ ඉහළ	5.69
39	G /C/25/72	ගා/පිලාන තක්ෂිලා ප්‍රා.වි.	මායිම් තාප්පය නවීකරණය	පළාත් නිශ්චිත	1,000.00	14,000.00	C9 හෝ ඉහළ	1.8
40	G /C/25/73	ගා/සංඝරතන ප්‍රා.වි.	100*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව.	පළාත් නිශ්චිත	2,500.00	34,000.00	C8 හෝ ඉහළ	4.4
41	G/C/25/74	ගා/තෙලිකඩ ම.වි.	80*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	පළාත් නිශ්චිත	2,500.00	35,000.00	C8 හෝ ඉහළ	4.5
42	G/C/25/75	ගා/කරන්දෙණිය ක.වි.	80*20 ගොඩනැගිල්ල අලුත්වැඩියාව	පළාත් නිශ්චිත	1,500.00	29,000.00	C9 හෝ ඉහළ	3.7
43	G/C/25/76	ගා/ලේනගල්පලා ත ක.වි.	80*20 ගොඩනැගිල්ල අලුත්වැඩියාව	පළාත් නිශ්චිත	1,500.00	27,000.00	C9 හෝ ඉහළ	3.4
44	G /C/25/77	ගා/රතනසාර ම.වි.	100*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	පළාත් නිශ්චිත	1,500.00	23,000.00	C9 හෝ ඉහළ	2.9
45	G /C/25/78	ගා/යටගල ම.වි.	මායිම් තාප්පය අලුත්වැඩියා කිරීම.	පළාත් නිශ්චිත	2,500.00	39,000.00	C8 හෝ ඉහළ	5.1
46	G /C/25/79	ගා/ඕල්කට් ම.වි	80*20 ගොඩනැගිල්ල අලුත්වැඩියාව	පළාත් නිශ්චිත	2,500.00	40,000.00	C8 හෝ ඉහළ	5.3
47	G /C/25/80	ගා/තෙල්ලඹුර		පළාත්			C8 හෝ	

		විජය ක.වි.	පැති බැම්ම ඉදි කිරීම.	නිශ්චිත	2,500.00	34,000.00	ඉහළ	4.3
48	G /C/25/81	ගා/හියාරේ ම.වි.	80*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	පළාත් නිශ්චිත	2,500.00	45,000.00	C8 හෝ ඉහළ	5.8
49	G /C/25/82	ගා/උස්වතුන් හසානා ම.වි.	160*25 තෙමහල් ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව.	පළාත් නිශ්චිත	2,500.00	34,000.00	C8 හෝ ඉහළ	4.4
50	G /C/25/83	ගා/බුද්ධදත්ත ප්‍රා.වි.	120*20 ප්‍රධාන ශාලාව අලුත්වැඩියාව	පළාත් නිශ්චිත	3,500.00	64,000.00	C8 හෝ ඉහළ	8.4
51	G /C/25/84	ගා/සිරි අභයනිස්ස ක.වි.	දෙමහල් ගොඩනැගිල්ලේ යකඩ ග්‍රීල් සවි කිරීම.	නඩත්තු සැලැස්ම	1,000.00	16,000.00	C9 හෝ ඉහළ	1.9
52	M/C/25/31	මාර/පර්සි අබේවර්ධන විද්‍යාලය	80*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව.	නඩත්තු සැලැස්ම	2,500.00	40,000.00	C8 හෝ ඉහළ	5.3
53	M/C/25/44	මාර/ජිනරාජ ක.වි.	වැසිකිළි පද්ධතිය අලුත්වැඩියා කිරීම.	පළාත් නිශ්චිත	1,500.00	22,000.00	C9 හෝ ඉහළ	2.1
54	M/C/25/52	අකුරැස්ස කලාප අධ්‍යාපන කාර්යාලය	පැති බැම්ම ප්‍රතිසංස්කරණය කිරීම	නඩත්තු සැලැස්ම	1,500.00	28,000.00	C 9 හෝ ඉහළ	3.59
55	M/C/25/53	මාර/කරගොඩ උයන්ගොඩ ම.වි	වැසිකිළි පද්ධතිය ඉදි කිරීම	පළාත් නිශ්චිත	1,500.00	20,000.00	C 9 හෝ ඉහළ	2.57
56	M/C/25/54	මාර/බැරගම ක.වි	වැසිකිළි පද්ධතිය ඉදි කිරීම	පළාත් නිශ්චිත	1,500.00	19,000.00	C 9 හෝ ඉහළ	2.42
57	M/C/25/55	මාර/පොල්වත්ත ප්‍රා.වි	ප්‍රධාන ශාලාව අලුත්වැඩියා කිරීමේ ඉතිරි වැඩ සම්පූර්ණ කිරීම	පළාත් නිශ්චිත	2,500.00	34,000.00	C 8 හෝ ඉහළ	4.48
58	M/C/25/56	මාර/මාතර ආදර්ශ ප්‍රා.වි	වැසි ජලය කළමනාකරණ පද්ධතිය නවීකරණය කිරීම	පළාත් නිශ්චිත	1,500.00	21,000.00	C 9 හෝ ඉහළ	2.69
59	M/C/25/57	මාර/කිරිින්ද ආදර්ශ ප්‍රා.වි	70*25 දෙමහල් ගොඩනැගිල්ල නවීකරණය	පළාත් නිශ්චිත	4,000.00	79,000.00	C 7 හෝ	10.43

			කිරීම				ඉහළ	
60	M/C/25/58	මාර/තල්පාවිල ම.ම.වි	ක්‍රීඩා පිටිය සංවර්ධනය කිරීම	පළාත් නිශ්චිත	2,500.00	42,000.00	C 8 හෝ ඉහළ	5.47
61	M/C/25/59	මාර/කඹුරුගමුව ම.වි	80*20 තනි මහල් ගොඩනැගිල්ල 90*25 දෙමහල් ගොඩනැගිල්ලට නවීකරණය කිරීම (අදියර 01)	පළාත් නිශ්චිත සංවර්ධන ප්‍රදාන	4,000.00	88,000.00	C 7 හෝ ඉහළ	11.69
62	M/C/25/60	මාර/බෙලිදෙණිය ම.වි	60*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියා කිරීම	පළාත් නිශ්චිත	1,500.00	27,000.00	C 9 හෝ ඉහළ	3.57
63	H/C/25/26	හ/මහගල්වැව ක.වි	90*25 දෙමහල් ගොඩනැගිල්ලේ බිම් මහලේ කාර්යාල කාමරය සකස් කිරීම	නඩත්තු සැලැස්ම	1,500.00	21,000.00	C 9 හෝ ඉහළ	2.73
64	H/C/25/27	හ/දුටුගැමුණු ම.වි	90*25 තෙමහල් ගොඩනැගිල්ලේ වහලය අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	23,000.00	C 9 හෝ ඉහළ	3.05
65	H/C/25/28	හ/සපුතන්ත්‍රීකන්ද ප්‍රා.වි	පැනි බැම්ම හා ජල කුළුණ ඉදි කිරීම	පළාත් නිශ්චිත	1,500.00	20,500.00	C 9 හෝ ඉහළ	2.7
66	H/C/25/29	හ/මිද්දෙනිය ම.වි	රැඳවුම් තාප්පය ඉදිකිරීම (ක්‍රීඩා පිටිය සඳහා ආරක්ෂක තාප්පය)	පළාත් නිශ්චිත	3,000.00	47,500.00	C 8 හෝ ඉහළ	6.27
67	H/C/25/30	හ/ගඟේයාය ක.වි	80*20 ගොඩනැගිල්ල අලුත්වැඩියාව	පළාත් නිශ්චිත	1,500.00	27,000.00	C 9 හෝ ඉහළ	3.55
68	H/C/25/31	තංගල්ල කලාප අධ්‍යාපන කාර්යාලයේ	මායිම් තාප්පය ඉදිකිරීම(ඉතිරි වැඩ)	පළාත් නිශ්චිත	1,000.00	12,000.00	C 9 හෝ ඉහළ	1.49
69	H/C/25/32	හ/බෙලිඅත්ත ම.ම.වි	100*20 තාක්ෂණික විද්‍යාගාරය ගොඩනැගිල්ල නවීකරණය	පළාත් නිශ්චිත	3,500.00	67,500.00	C 8 හෝ ඉහළ	8.91

70	H/C/25/33	හ/කදිරගොඩ ප්‍රා.වි	වැසිකිළි අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	18,000.00	C 9 හෝ ඉහළ	2.28
71	H/C/25/34	හ/ගොඩවානගොඩ ක.වි	වැසිකිළි අලුත්වැඩියාව සහ මායිම් නාප්පය අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	21,000.00	C 9 හෝ ඉහළ	2.67
72	H/C/25/35	හ/කුඩාවැල්ල ක.වි	වැසිකිළි අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,000.00	14,000.00	C 9 හෝ ඉහළ	1.82
73	H/C/25/36	හ/රදනිආර ම.වි	පරිගණක විද්‍යාගාරය අලුත්වැඩියා කිරීම	නඩත්තු සැලැස්ම	1,500.00	23,000.00	C 9 හෝ ඉහළ	2.94
74	H/C/25/37	හ/කිරම ධම්මානන්ද ප්‍රා.වි	80*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	37,000.00	C 8 හෝ ඉහළ	4.80
75	H/C/25/38	හ/කැරදෙනිය ක.වි	40*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	28,000.00	C 9 හෝ ඉහළ	3.69
76	H/C/25/39	හ/අගලබඩ ක.වි	60*20 ගොඩනැගිල්ල අලුත්වැඩියා කිරීම	නඩත්තු සැලැස්ම	1,500.00	23,000.00	C 9 හෝ ඉහළ	2.97
77	H/C/25/40	හ/අල්අමීර් මුස්ලිම් විද්‍යාලය	මායිම් නාප්පය අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	16,000.00	C 9 හෝ ඉහළ	2.08
78	H/C/25/41	හ/පල්ලෙපුලම්පි ටිය ම.වි	60*20 ගොඩනැගිල්ල අලුත්වැඩියා කිරීම	නඩත්තු සැලැස්ම	1,500.00	30,000.00	C 9 හෝ ඉහළ	3.93
79	H/C/25/42	හ/කැකිරිඔබඩ ක.වි	පුස්තකාල ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	39,000.00	C 8 හෝ ඉහළ	5.1
80	H/C/25/43	හ/බෙරලිහෙල ම.වි	80*20 ගොඩනැගිල්ල සහ 50*25 කාර්යාල ගොඩනැගිල්ල වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	21,000.00	C 9 හෝ ඉහළ	2.74
81	H/C/25/44	හ/ගැටමාන්ත දකුණ ම.වි	100*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	37,000.00	C 8 හෝ ඉහළ	4.87

82	H/C/25/45	හ/ගැටමාන්ත උතුර ක.වි	100*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	39,000.00	C 8 හෝ ඉහළ	5.07
83	H/C/25/46	හ/බුන්දල ක.වි	80*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	32,000.00	C 8 හෝ ඉහළ	4.22
84	H/C/25/47	හ/පලපොත ම.වි	100*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	27,000.00	C 9 හෝ ඉහළ	3.55
85	H/C/25/48	හ/බටහන දකුණ ක.වි	40*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	19,000.00	C 9 හෝ ඉහළ	2.49
86	H/C/25/49	හ/කහවත්ත ම.වි	නෙප්වුන් ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	3,000.00	61,000.00	C 8 හෝ ඉහළ	8.00
87	H/C/25/50	හ/කණුකැටිය ක.වි	80*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	24,000.00	C 9 හෝ ඉහළ	3.06
88	H/C/25/51	හ/දෙබරවැව ජනාධිපති විද්‍යාලය	120*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	40,000.00	C 8 හෝ ඉහළ	5.25
89	H/C/25/52	හ/දෙණිය පිංගම ක.වි	80*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	19,000.00	C 9 හෝ ඉහළ	2.44
90	H/C/25/53	හ/මීගහවෙල ක.වි	120*20 ගොඩනැගිල්ලේ වහල සහ වැසිකිළි අලුත්වැඩියාව	පළාත් නිශ්චිත	1,500.00	17,000.00	C 9 හෝ ඉහළ	2.2
91	H/C/25/54	හ/මොරයාය ම.වි	120*20 ගොඩනැගිල්ල අලුත්වැඩියාව	පළාත් නිශ්චිත	3,000.00	60,000.00	C 8 හෝ ඉහළ	7.94
92	H/C/25/55	හ/වැකඳවල ජනපද ම.වි	120*20 ගොඩනැගිල්ල අලුත්වැඩියාව	පළාත් නිශ්චිත	3,500.00	63,000.00	C 8 හෝ ඉහළ	8.33
93	H/C/25/56	හ/හිඟුරකන්ද ම.වි	72*16 ගොඩනැගිල්ල ප්‍රතිසංස්කරණය කිරීම	පළාත් නිශ්චිත	1,000.00	14,000.00	C 9 හෝ ඉහළ	1.81
94	H/C/25/57	හ/ලුණුගම්වෙහෙ	වැසිකිළි පද්ධතිය	පළාත්			C 9 හෝ	2.00

		ර ම.වි	ඉදිකිරීම	නිශ්චිත	1,500.00	16,000.00	ඉහළ	
95	H/C/25/58	හ/කටුවන ප්‍රා.වි	විද්‍යාලයේ පැති පැමිම ඉදි කිරීම	පළාත් නිශ්චිත සංවර්ධන ප්‍රදාන	2,500.00	35,000.00	C 8 හෝ ඉහළ	4.55
96	H/C/25/59	හ/රතනපෝති ප්‍රා.වි,ගඟුලන්දෙ නිය	පැතිබැම්ම ඉදි කිරීම (ක්‍රීඩා පිටිය ඉදිරිපස)	පළාත් නිශ්චිත	2,500.00	40,000.00	C 8 හෝ ඉහළ	5.28
97	H/C/25/60	හ/වැවේගම ක.වි	60*20 ගොඩනැගිල්ල අලුත්වැඩියාව	තඩත්තු සැලැස්ම	1,500.00	24,000.00	C 9 හෝ ඉහළ	3.10
98	H/C/25/61	හ/පොළොම්මාරු ව ආදර්ශ විද්‍යාලය	වැසිකිළි අලුත්වැඩියාව	තඩත්තු සැලැස්ම	1,500.00	17,000.00	C 9 හෝ ඉහළ	2.2
99	G/CSL/25/01	ගා/උනන්විටිය රේවත ම.වි.	පැති බැම්ම ඉදි කිරීම	ක්ලීන් ශ්‍රී ලංකා	1,500.00	23,000.00	C 9 හෝ ඉහළ	2.8
100	G/CSL/25/02	ගා/ඇත්තිලිගොඩ සුදර්ශි ම.වි.	80 X 20 ගොඩනැගිල්ල නවීකරණය	ක්ලීන් ශ්‍රී ලංකා	1,000.00	16,000.00	C 9 හෝ ඉහළ	1.9
101	G/CSL/25/03	ගා/දෙල්ලව ම.වි.	පැති බැම්ම ඉදි කිරීම	ක්ලීන් ශ්‍රී ලංකා	1,500.00	29,000.00	C 9 හෝ ඉහළ	3.6
102	M/CSL/25/01	මාර/දම්පැල්ල ම.වි.	සංගීත හා නැටුම් කාමර නවීකරණය	ක්ලීන් ශ්‍රී ලංකා	1,000.00	9,000.00	C 9 හෝ ඉහළ	1.1
103	G/CSL/25/04	ගා/ රතනසිරි රාජකීය විද්‍යාලය	ගැහැණු වැසිකිළි ඉදි කිරීම	ක්ලීන් ශ්‍රී ලංකා	1,500.00	29,000.00	C 9 හෝ ඉහළ	3.7
104	G/CSL/25/05	ගා/ අනුරුද්ධ ක.වි.	වැසිකිළි නවීකරණය (පිරිමි වැසිකිළි 02 හා ගැහැණු වැසිකිළි 04)	ක්ලීන් ශ්‍රී ලංකා	1,000.00	8,000.00	C 9 හෝ ඉහළ	1.0
105	G/CSL/25/06	ගා/සිරි අභයනිස්ස ම.වි.	ගුරුවරුන්ගේ සහ සිසුන්ගේ වැසිකිළි නවීකරණය	ක්ලීන් ශ්‍රී ලංකා	1,500.00	22,000.00	C 9 හෝ ඉහළ	2.8
106	G/CSL/25/07	ගා/දික්කුඹුර ප්‍රා.වි.	වැසිකිළි පද්ධතියක් ඉදි කිරීම	ක්ලීන් ශ්‍රී ලංකා	2,500.00	33,000.00	C 8 හෝ ඉහළ	4.2
107	G/CSL/25/08	ගා/හව්වේ ම.වි.	වැසිකිළි නවීකරණය	ක්ලීන් ශ්‍රී ලංකා	1,000.00	7,000.00	C 9 හෝ ඉහළ	0.9

108	G/CSL/25/09	ගා/හස්පිටිය ක.වි.	ගුරුවරුන්ගේ වැසිකිළි ඉදි කිරීම	ක්ලීන් ශ්‍රී ලංකා	1,500.00	29,000.00	C 9 හෝ ඉහළ	3.7
109	G/CSL/25/10	ගා/බටපොල ම.ම.වි.	වැසිකිළි ඉදි කිරීම	ක්ලීන් ශ්‍රී ලංකා	2,500.00	34,000.00	C 8 හෝ ඉහළ	4.3

02. ජාතික තරඟකාරී ලංසු පටිපාටිය මත ලංසු ඉදිරිපත් කළ යුතුය. කොන්ත්‍රාත් ප්‍රදානයේදී සුදුසුකම් ලබන සාර්ථක ලංසුකරුවන් අසාධු ලේඛනගත නොවිය යුතු අතර ඉදිකිරීම් කර්මාන්ත සංවර්ධන අධිකාරියේ ඉහත කාණ්ඩ යටතේ ලියාපදිංචි වී සිටිය යුතුය.

03. ලංසු අයදුම්පත් 2025.06.18 දින සිට 2025.07.03 දින දක්වා පෙ.ව 9.00 සිට ප.ව 3.00 දක්වා ඉහත දක්වා ඇති පරිදි ආපසු නොගෙවන ගාස්තුව අධ්‍යාපන අමාත්‍යාංශයේ ගිණුම් අංශයේ සරප් වෙත මුදල් ගෙවීමෙන් අනතුරුව ලබාදෙන මුදල් කුවිතාන්සිය ඉදිරිපත් කර හෝ ආපසු නොගෙවන ගාස්තුව අධ්‍යාපන අමාත්‍යාංශ ලේකම් නමින් ගාල්ල කොටුව ලංකා බැංකුවේ ඇති ගිණුම් අංක 1587423 ට බැර කර රිසිට් පත සමග ඔබගේ ඉල්ලීම් ලිපිය ද.ප. අධ්‍යාපන අමාත්‍යාංශයේ 070 7130700 දරණ වට්ස්ඇප් අංකයට පමණක් හෝ acc.moesp@gmail.com ඊ මේල් ලිපිනයට පමණක් යොමු කිරීමෙන් ඔබට අවශ්‍ය ලංසු පත්‍රිකා තැපැල් මගින් හෝ කුරියර් කර හෝ ඊමේල් මගින් හෝ වට්ස්ඇප් මගින් ගෙන්වා ගැනීමට හෝ ලබුදුව, දක්ෂිණපාය අධ්‍යාපන අමාත්‍යාංශයෙන් (බිම් මහල) ගිණුම් අංශයෙන් ලබා ගත හැකිය. වැඩි විස්තර අමාත්‍යාංශයේ 091-2030700 දුරකථන අංකයට වැඩ කරන දින ඇමතීමෙන් හෝ ද.ප. අධ්‍යාපන අමාත්‍යාංශ වෙබ් අඩවියට www.edumin.sp.gov.lk පිවිසීමෙන් අදාළ ලංසු පත්‍රිකා පරීක්ෂා කළ හැකිය.

04. මුද්‍රා තබන ලද ලංසු පත්‍රිකා 2025.07.04 පෙ.ව 11.00 ට පෙර ලැබෙන සේ ලේකම්, දකුණු පළාත් අධ්‍යාපන අමාත්‍යාංශය, දක්ෂිණපාය, ලබුදුව, ගාල්ල යන ලිපිනයට ලියාපදිංචි තැපෑලෙන් එවීමට හෝ අනිත් රැගෙන විත් ප්‍රධාන ගණකාධිකාරී නිල කාමරයේ තබා ඇති ටෙන්ඩර් පෙට්ටියට බහාලිය හැකිය. ප්‍රමාද වී ලැබෙන ලංසු ප්‍රතික්ෂේප කරනු ලැබේ.

05. ලංසු විවෘත කිරීම 2025.07.04 දින පෙ.ව 11.00 ට ලංසු පත්‍රිකා භාරගෙන අවසන් වූ වහාම දකුණු පළාත් අධ්‍යාපන අමාත්‍යාංශයේ ප්‍රසම්පාදන කමිටු සභාපතිගේ ප්‍රධානත්වයෙන් අමාත්‍යාංශයේදී සිදු කරන අතර එම අවස්ථාවට ලංසුකරුට හෝ ලංසුකරුගේ බලයලත් නියෝජිතයන් හට සහභාගී විය හැක.

06. ලංසුව සමඟ ඉදිරිපත් කරන ලංසු සුරක්ෂණය ශ්‍රී ලංකා වාණිජ බැංකුවකින් දකුණු පළාත් අධ්‍යාපන අමාත්‍යාංශයේ ලේකම් නමට ලබා ගත් 2025.07.04 දින සිට 2025.10.04 දක්වා වලංගු ලංසු ඇපකරයක් හෝ අධ්‍යාපන අමාත්‍යාංශයේ ගිණුම් අංශය වෙත මුදල් ගෙවීමෙන් අනතුරුව ලබාදෙන මුදල් කුවිතාන්සියේ පිටපත ලංසු පත්‍රිකාව සමඟ ඉදිරිපත් කළ යුතුය.

07. ලංසු වලංගු කාලය දින 77 කි.

08. ඉදිරිපත් කරනු ලබන කර්මාන්තයට අදාළ ලංසු පිටපත් දෙකකින් යුතුව ඉදිරිපත් කළයුතු අතර එහි මුල් පිටපතෙහි “මුල් පිටපත” යනුවෙන් සඳහන් කළ යුතු අතර අනු පිටපතෙහි “අනුපිටපත” යනුවෙන් සඳහන් කළ යුතුය. ලංසුපත් වල මුල් පිටපත හා අනුපිටපත වෙන වෙනම කවරවල බහා මුද්‍රා තබා එම කවර දෙක එක් කවරයක බහා එම කවරය මුද්‍රා තබා කවරයේ වම් පස උඩකෙළවරේ කර්මාන්තයේ නම සහ අංකය සඳහන් කළ යුතුය.

09. ඔබ විසින් ඉදිරිපත් කිරීමට නියමිත සෑම ලංසු පත්‍රිකාවෙහිම මිල ගණන් සඳහන් කර ඇති පිටු අංකයන්හි ඔබ විසින් සඳහන් කළ යුතු ඒකක මිල ගණන් හා මුළු මුදල දැක්වෙන තීරය සහ සාරාංශයද (වට්ටම් දැක්වෙන තීරයද ඇතුළත්ව) විනිවිද පෙනෙන සේ සෙලෝටේප් කර ලංසු ඉදිරිපත් කිරීම අනිවාර්ය වේ.

10. ද.ප. අධ්‍යාපන අමාත්‍යාංශය දැනටමත් දකුණු පළාතේ පාසල්වල ඉදිකිරීම් අලුත්වැඩියා හා නඩත්තු කටයුතුවලට අදාළ ව්‍යාපෘති සියයක පමණ ප්‍රසම්පාදන කටයුතු අවසන් කර ඉදිකිරීම් කටයුතු ආරම්භ කර ඇත. එමෙන්ම මෙම ව්‍යාපෘති එකසිය නමයෙහි ද ප්‍රසම්පාදන කටයුතු හැකි ඉක්මනින් අවසන් කර ව්‍යාපෘතිවල වැඩ 2025 වසරේ දෙසැම්බර් මස වනවිට අවසන් කළ යුතු බැවින් ලංසුකරුවන්ගේ ධාරිතාවය පිළිබඳ ලංසු ප්‍රදානයේදී සලකා බලනු ලැබේ.

11. අඩුපාඩු සහිත ලංසු පත්‍රිකා ප්‍රතික්ෂේප කරනු ලබන ලැබේ. මෙම ප්‍රසම්පාදනය සම්බන්ධයෙන් ප්‍රසම්පාදන කමිටුවේ තීරණය අවසාන තීරණය බව සැලකිය යුතුය.

ඒ.යූ.චේලාරත්න,
ප්‍රසම්පාදන කමිටු සභාපති,
දකුණු පළාත් අධ්‍යාපන අමාත්‍යාංශය,
පළමු මහල, දක්ෂිණපාය, ලබුදූව, ගාල්ල.

2025.06.18

දුරකථන අංකය - 0912030700 ඊමේල් - acc.moesp@gmail.com

SECTION 4

FORM OF BID AND QUALIFICATION INFORMATION

FORM OF BID

Name of Contract : Preparation a office room in the ground floor of 90x25 two story building at H/Mahagalwewa K.V.

To : Secretary, Ministry of Education, Southern Province.

Gentleman,

1. Having examined the Standard Bidding Document - Procurement of Works - Minor Contracts [ICTAD/ SBD/ 03 - Second Edition, January 2007], Schedule, Specifications, Drawings and Bills of Quantities and addenda for the execution of the above named Works, we/I the undersigned, offer to execute and complete such Works and remedy any defect therein in conformity with the aforesaid Conditions of Contract, Schedule, Specifications, Drawings, Bill of Quantities and Addenda for the sum of Sri Lankan Rupees (LKR) or such other sums as may be ascertained in accordance with the said Conditions.
2. We/I acknowledge that the Schedule forms part of our/my Bid.
3. We/I undertake, if our Bid is accepted, to commence the Works as stipulated in the Schedule, and to complete the whole of the Works comprised in the Contract within the time stated in the Schedule.
4. We/I agree to abide by this bid for the period stated in the Sub-Clause 15 of Instructions to Bidders or any extended period and it shall remain binding upon us and may be accepted at any time before the expiration of that period.
5. Unless and until a formal agreement is prepared and executed this Bid, together with your written acceptance thereof, shall constitute a binding contract between us/me.
6. We/I understand that you are not bound to accept the lowest or any Bid you may receive.

Dated this day of 20.... in the capacity of duly authorized to sign
tenders for and on behalf of
..... (IN BLOCK CAPITALS)

Signature :

Name :

Designation :

Address :

Witness :

Qualification Information

(to be completed by the bidder and submitted with the Bid)

	Eligibility Requirement	Bidder's Qualification	
ICTAD Registration			
Registration number			
Grade	C9 or Above		
Speciality	Buildings		
Expiry Date			
Backlisted Contractors			
Have you been declared as a defaulted contractor by NPA or any other Agency?		Yes /No	
IF yes provide details			
VAT Registration Number			
Construction Program	(attach as annex)		
Legal status	Public company/Private Company/Partnership/Sole proprietor		
	Eligibility Requirement	Bidder's Qualification	
Qualification and experience of key staff	Category, Experience and Qualifications <i>(Insert requirement)*</i>	Required Nos. *	Proposed by bidder (Name, experience and Qualifications)
	1		
	2		
	3		
List Other information required			

Signature of the Bidder :

SECTION 5

SCHEDULE

Schedule

ITB Clause	Conditions of Contract Clause	Item	Data
1.	1.1.8	Employer is :	Name : Secretary Address: Ministry of Education, Southern Province.
	1.1.10	Engineer is:	Name : District Engineer (Buildings) Address: District Engineer (Buildings) Office, 2nd Floor, Administrative Complex, Hambantota.
1 & 13	1.1.21	Summary of Works	The Works consists of: Located at : H/Mahagalwewa K.V. Contract Name : Preparation a office room in the ground floor of 90x25 two story building Contract Number M/C/25/26
	1.1.14	Intended Completion Date	Intended Completion Date is 75 Days from the Start Date
2.		Source of Funds	The source of funds is
3. 12.		Eligibility Documents of the Bid	The requirement is CIDA C9 or Above Any other information
13.	10.10	Price Adjustment	The Contract-is/ is not subject to price adjustment in accordance with Sub-Clause 10.10 of the Conditions of Contract. The price adjustment shall be computed in accordance with Option B under sub clause 10.10. Non adjustable element shall be: BOQ Item Numbers : Option B: Type of Construction: Non residential buildings

ITB Clause	Conditions of Contract Clause	Item	Data
16.		Bid Security	<p>Bid shall include a Bid Security:</p> <ul style="list-style-type: none"> for an amount LKR 21,000.00 issued by an agency acceptable to Employer using the form for bid security (unconditional guarantee) included in Section 9, Standard Forms, remain valid till 2025.10.04 or if paid by cash to the Employer, LKR 21,000.00
31.	4.4	Performance Security	<p>Amount of Performance Security required is 5% of the Initial Contract Price</p> <p>The form acceptable is unconditional guarantee as standard form as per SBD/03</p>
	6.4	Late Completion	The amount to be paid is 0.05 % of Initial Contract Price per Day, subjected to maximum of 10 % of Initial Contract Price.
	8.1	Notification of Defects	The period for Defect Notification is 180 Days from Taking Over.
	10.3	Retention	<p>The amount of retention is 10 % of certified work done.</p> <p>The maximum amount of retention is 5 % of Initial Contract Price.</p>
	10.12	Advance Payment	Upon the payment of the advance payment in full the Employer shall return the original of the advance payment guarantee to the Contractor.
	13.1 (c)	Insurance, third party	Minimum amount for third party insurance is LKR 100,000.00
	13.1 (a)	Insurance for Works, Material and plant	The minimum cover for insurance of the works and plant and materials is 110% of initial contract price.
	13.1	Insurance for Contractor's Personnel	Minimum amount for Insurance is LKR 500,000.00
33.	1.1.11	Adjudicator	<i>CIDA</i>
	14.0	Resolution of Disputes	<p>Deputy Chief Secretary (Engineering Services), Southern Province</p> <p><i>Fees and types of reimbursable expenses to be paid to the Adjudicator shall be on a case to case basis and shall be shared by the Contractor and the Employer.</i></p>

SECTION 6

SPECIFICATIONS

TECHNICAL SPECIFICATIONS

Technical specification that are applicable to this project are listed below:

- SCA/3/1 - Irrigation and Land Drainage
- SCA/3/2 - Water Supply Sewerage and Storm Water Drainage
- SCA/3/3 - Reclamation Works
- SCA/3/4 - Ground Water Exploration & Exploitation
- SCA/4/I - Building Works (Vol I)
- SCA/4/II - Building Works (Vol II)
- SCA/5 - Roads and Bridges
- SCA/6 - Coastal Harbour Engineering Works
- SCA/8 - Electrical and Mechanical Works
- ICTAD/DEV/16 - Board & Cast In situ Reinforced Concrete Piles
- ICTAD/DEV/17 - Site Investigation for Building Works & Sample Bill of Quantities
- Any other specification approved by the Government.

Above publications shall be purchase from the Construction Industry Development Authority (CIDA), Savusiripaya, 123. Wijerama Mawatha, Colombo 07.

SECTION 7

BILL OF QUANTITIES

PREPARATION A OFFICE ROOM IN THE GROUND FLOOR OF 90X25 TWO**STORY BUILDING AT H/
MAHAGALWEWA K.V.**

ID	Description	Unit	Qty.	Rate	Amount
----	-------------	------	------	------	--------

(No Topic Assigned)**DEMOLISH WORKS**

1	Removing and stacking ,Iron grill with frame from wall & modification & refixing necessary place	sq.m	12.27		
2	Removing and stacking Iron grill with frame from wall.	sq.m	5.75		
3	Demolishing brickwork in cement clearing debris away from site	cu.m	0.50		
4	Removing rendering, cement, and clearing debris away from cement concrete floors	sq.m	38.40		
5	Removing rendering, cement, and clearing debris away from brick walls	sq.m	3.35		
6	Removing lime plastering and clearing debris away from site	sq.m	19.40		
7	Demolishing Cement concrete floor , and clearing debris in away from site (3" thick)	cu.m	2.00		
	<i>Total carried to summary</i>				

BRICK WORKS

8	Brickwork 112mm in cement : sand	sq.m	6.36		
---	----------------------------------	------	------	--	--

	mortar 1:5 (Ground Floor)				
9	Manhole 2'-0"x 2'-0"x 2'-0" (internally) concreting base 4" thick & channels with 1:2:4 (3/4") ct. concrete including 2" thick, concrete screed with 1:3:6 (1") con. mixture.9" brick wall with 1:5 ct. mortar. Internally Plastered with 1:3, 3/4" thick ct. mortar with water proofing compound 10% (by cement) weight of cement as super latex 302 or equivalent finished smooth with neat ct. floating including channels & Pad plaster 1:3, 1/2" thick finished smooth with cement floating.shall be water tight. Rate to include for concrete cover slab 3" thick with 1:2:4 (3/4") con. mixture r/f with.10 mm dia. T.S rods @ 6" c/s. both ways, with 2 nos lifting handles. (as per Draw No.SPES/Rate23/Bk-13)	nr	1.00		
10	Construction of soakage pit 1200 x 1200 x 2700 mm (8'-6") invert depth, (8'-6" deep from the sewer pipe) Brick walls 225 mm thick in 1:5 ct: sand mortar, including 1:2 ct, & sand plastering 1/2" thick finished smooth with neat ct. floating up to a depth of 6" below from the invert level of the sewer pipe & surrund the con. pad . Concreting Ring beam, cover slab and pad (curb) with 1:2:4(3/4") conc. mixture. Reinforcing cover slab with 10.0 mm twisted deformed steel @ 6" cts. bothways and plastering curb 1:3 ct. & sand, 1/2" thick finished smooth with neat ct. floating 6" below ground level.inc: 2 nr of 10mm dia lifting handles (as per Draw No.SPES/Rate23/Bk-10.)	nr	1.00		

	<i>Total carried to summary</i>				
--	---------------------------------	--	--	--	--

ID	Description	Unit	Qty.	Rate	Amount
	<u>CONCRETE WORKS</u>				
11	Cement concrete 1:2:4(3/4") (Gr.20 concrete) (R/F and Shuttering paid separately)incl: curing.Rate to include using mixture & vibrator	cu.m	0.02		
12	Lintel, cement concrete 1:2:4(3/4") (Gr.20) 9" x 6" (Reinforcement paid separately). Rate including shuttering &curing	m	1.60		
13	Cement concrete 1:3:6 (1") up to 3.00 m3(Shuttering paid separately) incl: curing(Grade 15)	cu.m	0.45		
	<i>Total carried to summary</i>				
	<u>REINFORCEMENT WORKS</u>				
14	2T10,2T12 for coping,lintol	kg	6.03		
15	R6 for coping,lintol (600mm c/c)	kg	0.22		
	<i>Total carried to summary</i>				
	<u>PAVING WORKS</u>				
16	600 x 600 mm Ceramic tiles with all specials supplying and fixing to floors including raking plaster 1:3 and bedding in Tile Motar (swistech / tokyo super) & pointed with tile grout. (Use Rocell - Ceramic tiles Prime cost Rs. 2200) as per the engineer's instruction.	sq.m	38.60		

17	Tile skirting 100 mm high and all specials supplying and fixing to walls including raking plaster and bedding in Tile mortar 1:3 & pointed with tile grout.(Use Rocell 600 x 600 mm - ceramic tiles Prime cost Rs. 2200)as per the engineer's instruction.	m	25.00		
18	Wall Tiles glazed colour 300 x 600 mm with all specials , supplying and fixing to walls including raking plaster bedding 1:3 in tile mortar and pointed with tile grout to match the tiles. (Use Rocell tiles Prime cost Rs 980)as per the engineer's instruction.	sq.m	15.60		
	<i>Total carried to summary</i>				
	<u>PLASTER WORKS</u>				
19	Cement Sand plastering to wall 1:5, (5/8") thick semi rough G: floor rate to include curing	sq.m	21.00		
	<i>Total carried to summary</i>				
	<u>ELECTRICAL WORKS</u>				
20	Supplying and Fixing 100ABC Enclosure Box (Surface mounted) fixed with brass screws all complete as per Instruction.(Enclosure-Polycrome)	nr	1.00		

ID	Description	Unit	Qty.	Rate	Amount
21	Supplying and fixing 1 Nr. 1 pole MCB (6 A/ 10A/ 16A/ 20A/ 32A) (Make -Orange electric 10kA/ Schneider/Chint NB7/EB) Original Makes with company warranty Certificate. all complete as per instruction	nr	2.00		
22	Supplying and fixing 1/1.13 2 x 1C (Cu/PVC/PVC) single phase Wire (1 mm2) [(Cable - ACL/Kelani/Orange/Sierra) [Cable SLS 733]	m	20.00		
23	Supply and fixing 16" sweep wall fan with 13 maxAmp socket outlet ,Necessary concealed conduit wiring (1/1.13 wire 1.0mm2, 1/1.13 earth wire 1mm2) all complete as per instruction. Make KDK with warranty (SLSI Approved makes Model - M40C) fixed to wall with Philips screws (Socket - ACL/Chint/Krypton/Orange) (Cable - ACL/Kelani/Orange/Sierra) (Conduit - krypton/Polycrome) (fittings - krypton/Polycrome/Orange)	nr	2.00		
24	Refixing of existing ceiling fan including fixing materials / cleaning all complete as per the instruction.	nr	2.00		
25	Supply and fixing 13Amp socket outlet with necessary PVC casing wiring (7/0.53 PVC single wire 1.5mm2) 1 core x2, 7/0.53 earth wire (1.5mm2) all complete as per the instruction.(Socket - ACL/Chint/Krypton/Orange) (Cable - ACL/Kelani/Orange/Sierra) (Casing - krypton/Polycrome) (fittings - krypton/Polycrome/Orange)	nr	2.00		
	<i>Total carried to summary</i>				

CARPENTRY WORKS

26	Doors panelled with 4"x3" frames and 1 1/8" - 1 1/4" sashes in Jack timber fixed complete with new furniture (3 nrs 5"x3" Butt hinges, 01 nr 12" skelton bolt, 01 nr 6" barrel bolt, Union Mortice lock made in England (5 years warranty)) Rate to include one coat of primer & two coats of enamel paint. - Single hung door. Draw No/SPES/Rates23/Cp-21	sq.m	1.90		
	<i>Total carried to summary</i>				

IRON WORKS

27	Supplying and making 6 mm dia. M.S. rod grills for windows with 25x25x3 mm thick M.S. angle iron outer frame with 4 nr 25 x 25 x 3 mm angle iron (2 nr together) middle bar vertically and 2 nr together 25 x 25 x 3 mm angle iron middle bar horizontally & 6 mm dia. M.S. rods weld to frame, at 75 mm C/C. & to 70° angle both ways, horizontal & vertical distance should be 75 mm & 200 mm respectively. Frame fixed to window openings with 1 1/2" iron screws & applying one coats of metal primer & 2 coats of approved quality enamel paint (different colour) (9'-3"x6'-0" size) all complet as per detail Draw. No :SPES/Rate23/Ir-21	sq.m	0.37		
	<i>Total carried to summary</i>				

PAINTING WORKS

ID	Description	Unit	Qty.	Rate	Amount
28	Applying skim coat & one coats of wall filler (smooth plastered new work or after preparation of old wall)	sq.m	21.00		
29	Prepare and Painting Walls soffite with one coat of emulsion paint. (new work or after preparation of old wall) (Using roller brush)	sq.m	123.00		
30	Prepare and Painting steelwork, 1 coat with anticorrosive paint including removing scale and wire brushing.	sq.m	7.60		
	<i>Total carried to summary</i>				
<u>PLUMBING WORKS</u>					
31	Supplying and fixing, Closet, pedestal type, with low level glazed earthenware flushing cistern, plastic seat cover (OTTO, RSL or equivalent.) rate to include 1/2" watertec angle valve, 450mm flexible hose (all accessories water tech or S-lon) Suitable fittings can be decided by the engineer depending on the site situation	nr	1.00		
32	Supplying and fixing Pedestal type Wash basin, rate to include waste coupling, Pillar tap & 1/2" angle valve, 450mm flexible hose including nails. (all accessories water tec or S-lon) (Suitable fittings can be decided by the engineer depending on the site situation) (OTTO, RSL ceramic or equivalent)	nr	1.00		
33	Supplying and fixing Bidet shower Plastic (water tec or equivalent)" with 1/2" angle valve PVC	nr	1.00		

34	Mirror, bath room type, square shape ("Plastic")supplying and Fixing to wall with Rawl plugs (18"x24")	nr	1.00		
35	Supplying & fixing 150 mm x 150mm plastic Gully trap with cover	nr	1.00		
36	Supplying and fixing Pipes P. V. C. ½" - PNT 14 rate to include socket & joints and also include excavating backfilling or breaking wall or floor upto required depth	m	10.00		
37	Supplying and fixing Pipes P. V. C. 1 1/4" - PNT 7 rate to include socket & joints and also include excavating backfilling or breaking wall or floor upto required depth	m	10.00		
38	Supplying and fixing Pipes P. V. C. 1 1/2" - 600 Type PNT 7 rate to include socket & joints and also include excavating backfilling or breaking wall or floor upto required depth	m	10.00		
39	Supplying and fixing Pipes P. V. C. 2" - 600 Type PNT 7 rate to include socket & joints and also include excavating backfilling or breaking wall or floor upto required depth	m	5.00		
40	P.V.C. pipes 110 mm dia.(4") type 250 laid under ground not exceeding 600 mm depth. Rate to include for necessary excavation, ct.Con. Bedding & covering with 1:3:6 (1") conc. mixture. Concrete Paid Seperately. For special purpose only	m	5.00		
41	Supplying and fixing PVC Door bend 110mm	nr	1.00		
	<i>Total carried to summary</i>				
	<u>ALLUMINIUM WORKS</u>				

ID	Description	Unit	Qty.	Rate	Amount
42	<p>Supplying, fabricating and fixing Aluminium natural anodized sliding window with frame (2 Nrs window sashes) as per Drg. No. SPES/RATE23/SW/01. Overall size of the window frame is 1200x1200mm. (Size may be changed according to the site)</p> <p>Window frame consisting top bars (70x32mm), bottom bar (70x30mm) and side bars (73x25mm), and fixing with 8x1 1/2" ST screws. Frame should be fixed to wall with 12 Nrs of No 6 rowl plugs and 8x2" ST screws. Window sash consisting top bar (28x32mm), bottom bar (22x56mm) and side bars (30x26mm one side, 30x32mm lock side) should be fixed using 8x1 1/2" ST screws, and 5mm thick clear glass. Rate should be included for supplying and fixing required 674U Rubber beading, 4 Nrs of Adjustable rollers, 8 Nrs of Guide runners for top, 1 Nr of heavy quality Crescent lock using 5/32x3/8" Al rivets, Screws, Pop rivets, Hole buttons, Silicone etc.</p>	sq.m	1.45		

43	<p>Supplying, fabricating and fixing Aluminium natural anodized casement window with frame (4 Nrs window sashes) as per Drg. No. SPES/RATE23/CW/04. Overall size of the window frame is 2400x1200mm. (Size may be changed according to the site) Window frame consisting top, bottom and side bars (41x31mm), middle bars (46x41mm), and fixing with 38x38x2.5mm Al bracket using 1/8x3/8" Al rivets and 8x1 1/2" ST screws. Frame should be fixed to wall with 16 Nrs of No 6 rowl plugs and 8x2" ST screws. Window sash consisting top, bottom and side bars (40x35mm) should be fixed using 8x1 1/2" ST screws, and 5mm thick clear glass. Rate should be included for supplying and fixing required 437K Rubber beading, 674U Rubber beading, 8 Nrs of 14" SS 304 bar hinges using 5/32x3/8" Al rivets, 4 Nrs of heavy quality Al fasteners using 5/32x3/8" Al rivets, Screws, Pop rivets, Silicone etc.</p>	sq.m	5.77		
----	--	------	------	--	--

44	<p>Supplying, fabricating and fixing Aluminium natural anodized partition (Top and Bottom panels - Al/PVC Composite board, Middle panels - Glass) as per Drg. No. SPES/RATE23/FP/01, Option 1. (Door sashes pay separately) Overall height of the partition is up to ceiling or soffit. Bottom panel height is 900mm and middle panel height is 2100mm. (Heights may be changed according to the site) Partition panels in horizontal way should be divided in equal widths (Maximum width is 1200mm c/c). Partition frame consisting top bar (76x32mm), side bars (76x32mm), horizontal middle bars (75x32mm with 70x11mm clip bar and 31x19 clip bar), bottom bar (75x32mm with 31x19 clip bar) and vertical middle bars (76x32mm with 70x11mm clip bar), and fixing with 50x18x2mm Al bracket using 1/8x3/8" Al rivets and 8x1 1/2" ST screws. If required, Squire or Circular coner bars will be paid seperately (Net material cost + 10% + 20%). Frame should be fixed to wall, floor and soffit/ceiling with adequate Nrs of No 6 rowl plugs and 8x3" ST screws (Average distance 600mm). 4mm thick Al/PVC double side composite board for top and bottom panels, and 5mm thick clear glass for middle panels should be fixed. Rate should be included for supplying and fixing required 3303 and 3303A Rubber beadings, Screws, Pop rivets, Silicone etc.</p>	sq.m	18.20		
----	--	------	-------	--	--

ID	Description	Unit	Qty.	Rate	Amount
45	<p>Supplying, fabricating and fixing Aluminium natural anodized partition paneled door (Top panel - Glass, Bottom panel - Al/PVC Composite board) as per Drg. No. SPES/RATE23/PD/01, Option 1. Overall size of the door is 900x2070mm. (Size may be changed according to the site) Door frame around the door fixing with 18x11mm door stopper bar using 5/32x3/8" Al rivets. Door sash consisting top bar (80x42mm), side bars (66x45mm hinges side, 70x45mm lock side), middle bar (100x42mm) and bottom bar (120x42mm). 16x15mm clip bar should be used for required bars. Sash frame should be fixed with 38x38x2.5mm Al bracket using 1/8x3/8" Al rivets, 8mm dia. treaded bar with nuts for top and bottom bars. 4mm thick Al/PVC double side composite board for bottom panel and 5mm thick clear glass for top panel should be fixed. Rate should be included for supplying and fixing required Mohair beading, 3303, 3303A and 455S Rubber beadings, 3 Nrs of 100x75mm Al hinges using 5/32x3/8" Al rivets, Al natural anodized door handle (102x40mm) pair with cap nuts, Door lock (CL or equivalent approved by the Engineer), Screws, Pop rivets, Silicone etc.</p>	sq.m	3.80		

46	<p>Supplying, fabricating and fixing Aluminium natural anodized sliding window with frame (4 Nrs window sashes) as per Drg. No. SPES/RATE23/SW/02. Overall size of the window frame is 2400x1200mm. (Size may be changed according to the site)</p> <p>Window frame consisting top bars (70x32mm), bottom bar (70x30mm) and side bars (73x25mm), and fixing with 8x1 1/2" ST screws. Frame should be fixed to wall with 16 Nrs of No 6 rowl plugs and 8x2" ST screws. Window sash consisting top bar (28x32mm), bottom bar (22x56mm) and side bars (30x26mm one side, 30x32mm lock side) should be fixed using 8x1 1/2" ST screws, and 5mm thick clear glass. 30x16mm bar should be fixed to one middle sash using 5/32x1/2" Al rivets. Rate should be included for supplying and fixing required Mohair beading, 674U Rubber beading, 8 Nrs of Adjustable rollers, 16 Nrs of</p> <p>Guide runners for top, 2 Nr of heavy quality Crescent lock using 5/32x3/8" Al rivets, Screws, Pop rivets, Hole buttons, Silicone etc.</p>	sq.m	2.90		
----	--	------	------	--	--

47	<p>Supplying, fabricating and fixing Aluminium natural anodized casement Fanlight with frame (1 Nr Fanlight sash) as per Drg. No. SPES/RATE23/FL/01. Overall size of the fanlight frame is 600x600mm. (Size may be changed according to the site) Fanlight frame consisting top, bottom and side bars (41x31mm), and fixing using 38x38x2.5mm Al angle bracket with 1/8x3/8" Al rivets. Frame should be fixed to wall with 8 Nrs of No 6 rowl plugs and 8x2" ST screws. Fanlight sash consisting top, bottom and side bars (40x35mm) should be fixed using 8x1 1/2" ST screws, and 5mm thick clear glass. Rate should be included for supplying and fixing required 437K Rubber beading, 674U Rubber beading, 2 Nrs of 14" SS 304 bar hinges using 5/32x3/8" Al rivets, 1 Nrs of heavy quality Al fasteners using 5/32x3/8" Al rivets, Screws, Pop rivets, Silicone etc.</p>	sq.m	0.37		
----	--	------	------	--	--

ID	Description	Unit	Qty.	Rate	Amount
48	<p>Supplying, fabricating and fixing Aluminium natural anodized paneled door (Top and Bottom panel -Al/PVC Composite board) with frame (1 Nr door sash) as per Drg. No. SPES/RATE23/D/03. Overall size of the door frame is 750x2100mm. (Size may be changed according to the site)</p> <p>Door frame consisting top and side bars (76x23mm), and fixing with 38x38x2.5mm Al bracket using 1/8x3/8" Al rivets. Frame should be fixed to wall with 8 Nrs of No 6 rowl plugs and 8x3" ST screws. Door sash consisting top and bottom bar (80x42mm), side bars (66x45mm hinges side, 70x45mm lock side) and middle bar (100x42mm). 16x15mm clip bar should be used for required bars. Sash frame should be fixed with 38x38x2.5mm Al bracket using 1/8x3/8" Al rivets, 8mm dia. treaded bar with nuts for top and bottom bars. 3mm thick Al/PVC double side composite board for top and bottom panels should be fixed. Rate should be included for supplying and fixing required Mohair beading, 3303A Rubber beadings, 3 Nrs of 100x75mm Aluminium hinges using 5/32x3/8" Al rivets, 2 Nrs of Aluminium plate door handle, Door lock (CL or equivalent approved by the Engineer), 2 Nrs of 3" Al Barrel Bolt, Screws, Pop rivets, Silicone etc.</p>	sq.m	1.58		
49	making aluminium pantry cupboards under the worktable as directed.1nr size	PS	1.00	60,000.00	60,000.00

	0.53mx1.35m.4 nrs total.				
	<i>Total carried to summary</i>				

**PREPARATION A OFFICE ROOM IN THE GROUND FLOOR OF 90X25 TWO
STORY BUILDING AT H/MAHAGALWEWA K.V.**

SUMMARY

Demolish Works
Brick Works
Concrete Works
Reinforcement Works
Paving Works
Plaster Works
Electrical Works
Carpentary Works
Iron Works
Painting Works
Plumbing Works
Alluminium Works

SUB TOTAL

=====

**PREPARATION A OFFICE ROOM IN THE GROUND FLOOR OF 90X25 TWO
STORY BUILDING AT H/MAHAGALWEWA K.V.**

(A) BOQ Total	:	LKR
(B) Less for Provisional Sums	:	LKR 60,000.00
(C) Sub Total (A-B)	:	LKR
(D) Less for Discount (If Any) (..... %)	:	LKR
(E) Sub Total (C-D)	:	LKR
(F) Add for Provisional Sums	:	LKR 60,000.00
Total Bid Amount (E+F) (Excluding VAT, Carried to Form of Bid))	:	LKR =====

Total Bid Amount in Words

.....

18 % VAT : LKR

Grand Total : LKR =====

Note:

Bidders are requested to provide discounts, if any, as a percentage. Otherwise, it will be converted to a percentage. Your discount will also be applied to variations in quantity."

..... *Signature*
of Bidder

SECTION 8

DRAWINGS

SECTION 9

STANDARD FORMS

- **Form of Bid Security**
- **Form of Letter of Acceptance**
- **Form of Performance Security**
 - **Agreement**

[Letter heading paper of the procuring entity]

BID SECURITY

[this Guarantee form shall be filled in accordance with the instructions indicated in brackets]

----- *[insert issuing agency's name, and address of issuing branch or office]*

Beneficiary: Secretary, Ministry of Education, Southern Province.

Date: ----- *[insert date (by issuing agency)]*

BID GUARANTEE No.: ----- *[insert (by issuing agency) number]*

We have been informed that -----
[insert (by issuing agency) name of the bidder] (hereinafter called "the bidder") has submitted to you its bid dated ----- *[insert (by issuing agency) date]* (hereinafter called "the Bid") for the execution of **Preparation of office room in the ground floor of 90x25 two story building at H/Mahagalwewa K.V.** under Invitation for Bids No. ----- *[insert IFB number]* ("the IFB").

Furthermore, we understand that, according to your conditions, Bids must be supported by a Bid Guarantee.

At the request of the bidder, we -----
[insert name of issuing agency] hereby irrevocably undertake to pay you any sum or sums not exceeding in total an amount of ----- *[insert amount in figures]* -----
 ----- *[insert amount in words]* upon receipt by us of your first demand in writing accompanied by a written statement stating that the Bidder is in breach of its obligation(s) under the bid conditions, because the Bidder:

- (a) has withdrawn its Bid during the period of bid validity specified; or
- (b) does not accept the correction of errors in accordance with the Instructions to Bidders (hereinafter "the ITB"); or
- (c) having been notified of the acceptance of its Bid by the Employer during the period of bid validity, (i) fails or refuses to execute the Contract Form, if required, or (ii) fails or refuses to furnish the Performance Security, in accordance with the ITB.

This Guarantee shall expire: (a) if the bidder is the successful bidder, upon our receipt of copies of the Contract signed by the bidder and of the Performance Security issued to you by the bidder; or (b) if the bidder is not the successful bidder, upon the earlier of the successful bidder furnishing the performance security, otherwise it will remain in force up to ----- *(insert date)*

Consequently, any demand for payment under this Guarantee must be received by us at the office on or before that date.

[signature(s) of authorized representative(s)]

[Letter heading paper of the procuring entity]

LETTER OF ACCEPTANCE

.....*[Date]*

To:
[Name and address of the Contractor]

This is to notify you that your bid dated *[insert date]* for the construction and remedying defects of the
.....
[name of the Contract and identification number] for the Contract price ofLKR
.....
[amount in figures and words] as corrected in accordance with Instructions to Bidders, is hereby accepted.

The adjudicator shall be *[Name & Address of the Adjudicator, if agreed]* shall be appointed by the Institute for Construction Training & Development (ICTAD)

You are hereby instructed to proceed with the execution of the said Works in accordance with the Contract documents.

The Start Date shall be: *(fill the date as per Conditions of Contract)*.

The amount of Performance Security is : *(fill as per Conditions of Contract)*.

The Performance Security shall be submitted on or before *(fill as per Conditions of Contract)*.

Authorized Signature :

Name and title of Signatory :

Name of Agency :

[Letter heading paper of the procuring entity]

PERFORMANCE SECURITY

[this Guarantee form shall be filled in accordance with the instructions indicated in brackets]

----- *[insert issuing agency's name, and address of issuing branch or office]*

Beneficiary: Secretary, Ministry of Education, Southern Province.

Date: ----- *[insert date (by issuing agency)]*

PERFORMANCE GUARANTEE No.: ----- *[insert (by issuing agency) number]*

We have been informed that -----
[insert (by issuing agency) name of the contractor] (hereinafter called "the Contractor") has entered into Contract No. ----- *[reference number of the contract]* dated ----- with you, for the execution of **Preparation of office room in the ground floor of 90x25 two story building at H/Mahagalwewa K.V.** (hereinafter called "the Contract").

Furthermore, we understand that, according to the conditions of the Contract a performance guarantee is required.

At the request of the Contractor, we -----
[insert name of issuing agency] hereby irrevocably undertake to pay you any sum or sums not exceeding in total an amount of ----- *[insert amount in figures]* -----
 ----- *[insert amount in words]* upon receipt by us of your first demand in writing accompanied by a written statement stating that the Contractor is in breach of its obligation(s) under the Contract, without your needing to prove or to show grounds for your demand or the sum specified therein.

This guarantee shall expire, no later than the day of , 20..... *[insert date, 28 days beyond the scheduled contract completion date]* and any demand for payment under it must be received by us at this office on or before that date.

[signature(s) of authorized representative(s)]

AGREEMENT

This AGREEMENT, made the [day] day of [month] 20..... [year] between
 [name and address of Employer] (hereinafter called "the Employer") of the one part, and

 [name and address of Contractor] (hereinafter called "the Contractor") of the other part.

WHEREAS the Employer desires that the Contractor execute **Preparation of office room in the ground floor of 90x25 two story building at H/Mahagalwewa K.V.** (hereinafter called "the Works") and the Employer has accepted the Bid by the Contractor for the execution and completion of such Works and the remedying of any defects therein.

NOW THIS AGREEMENT WITNESSETH as follows:

1. In this Agreement, words and expressions shall have the same meanings as are respectively assigned to them in the Conditions of Contract hereinafter referred to, and they shall be deemed to form and be read and construed as part of this Agreement.
2. In consideration of the payments to be made by the Employer to the Contractor as hereinafter mentioned, the Contractor hereby covenants with the Employer to execute and complete the Works and remedy any defects therein in conformity in all respects with the provisions of the Contract.
3. The Employer hereby covenants to pay the Contractor in consideration of the execution and completion of the Works and the remedying of defects wherein the Contract Price or such other sum as may become payable under the provisions of the Contract at the times and in the manner prescribed by the Contract.

In Witness whereof the parties thereto have caused this Agreement to be executed the day and year aforementioned, in accordance with laws of Sri Lanka.

.....

Authorized signature of Contractor

.....

Authorized signature of Employer

COMMON SEAL

COMMON SEAL

In the presence of:

Witnesses:

1. Name and NIC No.
 Signature
 Address
2. Name and NIC No.
 Signature
 Address

Check List for Bidders

Bidders are advised to fill the following table:

ITEM	ITB Clause	YES (tick)	REFERENCE
Form of Bid			
Addressed to the Employer ?	18		
Completed?	18		
Signed?	18		
Bid Security (if required)			
Addressed to the Employer ?	16		
Format as required?	16		
Issuing Agency as specified?	16		
Amount as requested?	16		
Validity 28 days beyond the validity of Bid?	16		
Qualification Information			
All relevant information completed?	4		
Signed?	4		
Addendum			
Content of the addendum (if any) taken in to account?	10		
BID Package			
All the documents given in ITB Clause 12 enclosed in the original and copy?	12		
ITB Clause 19 followed before Sealing the Bid Package?	19		