



**MINISTRY OF EDUCATION
SOUTHERN PROVINCE**

BIDDING DOCUMENT

FOR

**RENOVATION OF BOUNDARY WALL AT H/AL AMEER
MUSLIM M.V.**

Issued to :

Date :

Contract No :

Employer : Secretary,
Ministry of Education,
Southern Province.

CONTENTS

Volume 1

Section 1	Instructions to Bidders
Section 2	Standard Forms (Contract)
Section 3	Conditions of Contract

Volume 2

Invitation for Bids

Section 4	Form of Bid and Qualification Information
Section 5	Schedule
Section 6	Specifications
Section 7	Bills of Quantities
Section 8	Drawings
Section 9	Standard Forms (Bid)

Volume 1 consisting of section 1, section 2, section 3 will be applicable for this contract shall be given volume 1 of “Standard Bidding Document, Procurement of Works, Minor Contracts”, CIDA publication no: CIDA/SBD/03, Second Edition, January 2007, publish by Construction Industry Development Authority (CIDA), Savusiripaya, 123. Wijerama Mawatha, Colombo 07.

The above Document will not be issued with the Bidding Document and Bidder is advised to purchase it from CIDA.

INVITATION FOR BIDS

ප්‍රසම්පාදන දැන්වීම

දකුණු පළාත් අධ්‍යාපන, ඉඩම් හා ඉඩම් සංවර්ධන, මහා මාර්ග හා ප්‍රවාහන අමාත්‍යාංශය
දකුණු පළාත් සභාව

පළාත් නිශ්චිත සංවර්ධන ප්‍රදාන, ක්ලීන් ශ්‍රී ලංකා වැඩසටහන හා නඩත්තු සැලැස්ම 2025 යටතේ ක්‍රියාත්මක කරනු ලබන පහත සඳහන් වැඩ යෝජනා සඳහා සුදුසුකම් ලත් කොන්ත්‍රාත් කරුවන්ගෙන්, දකුණු පළාත් අධ්‍යාපන අමාත්‍යාංශයේ ප්‍රසම්පාදන කමිටු සභාපති විසින් ලංසු පත් කැඳවනු ලැබේ.

අනු අංකය	ව්‍යාපෘති අංකය	පාසල	වැඩ විස්තරය	කර්මාන්තය ඉටු කරනු ලබන ව්‍යාපෘති සැලැස්ම	ආපසු නොගෙවනු ලබන ඇප තැන්පත් මුදල රු.	ලංසු සුරක්ෂණ වටිනාකම රු.	අවශ්‍ය CIDA ලියාපදිංචිය	මුළු පිරිවැය ඇස්තමේන්තු මුදල vat සමග රු. මි.
1	G/C/25/34	ගා/උඩුගම ම.වි	70*25 දෙමහල් ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	පළාත් නිශ්චිත	2,500.00	34,000.00	C 8 හෝ ඉහළ	4.34
2	G/C/25/35	ගා/හියාරේ නැහෙනහිර ක.වි	90*25 ගොඩනැගිල්ලේ කොරිඩෝර් ඉදිකිරීම	පළාත් නිශ්චිත	1,500.00	26,000.00	C 9 හෝ ඉහළ	3.40
3	G/C/25/36	ගා/තිත්තගල්ල අධ්‍යාපන ක.වි	180*25 ප්‍රධාන ශාලාවේ වහල අලුත්වැඩියාව	පළාත් නිශ්චිත	2,500.00	35,000.00	C 8 හෝ ඉහළ	4.41
4	G/C/25/37	ගා/හපුගල ප්‍රා.වි	මායිම් තාප්පය ඉදි කිරීම	නඩත්තු සැලැස්ම	1,500.00	27,000.00	C 9 හෝ ඉහළ	3.46
5	G/C/25/38	ගා/නරාවල ම.වි	80*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	32,000.00	C 8 හෝ ඉහළ	4.10
6	G/C/25/39	ගා/පංචාලිය ප්‍රා.වි	පාසල් ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	21,000.00	C 9 හෝ ඉහළ	2.73
7	G/C/25/40	ගා/කළාණනිස්ස විද්‍යාලය	80*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	22,000.00	C 9 හෝ ඉහළ	2.88

8	G/C/25/41	ගා/ජයවර්ධන විද්‍යාලය	80*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	25,000.00	C 9 හෝ ඉහළ	3.14
9	G/C/25/42	ගා/පැදිත්තොරුව සරණපාල ජයන්ති ප්‍රා.වි	60*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	26,000.00	C 9 හෝ ඉහළ	3.35
10	G/C/25/43	ගා/ඇත්තිලිගොඩ සුදර්ශි ම.වි	100*25 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	30,000.00	C 9 හෝ ඉහළ	3.91
11	G/C/25/44	ගා/මීගහගොඩ ක.වි	50*20 විද්‍යාගාර ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	31,000.00	C 9 හෝ ඉහළ	3.93
12	G/C/25/45	ගා/කඩිනිංගල ම.වි	70*20 දෙමහල් ගොඩනැගිල්ලේ විදුලි පද්ධතිය නවීකරණය	නඩත්තු සැලැස්ම	1,500.00	17,000.00	C 9 හෝ ඉහළ	2.12
13	G/C/25/46	අම්බලන්ගොඩ කලාප අධ්‍යාපන කාර්යාලය	කාර්යාල ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	20,000.00	C 9 හෝ ඉහළ	2.49
14	G/C/25/47	ගා/වටරැක ශ්‍රී සෝභිත විද්‍යාලය	40*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	25,000.00	C 9 හෝ ඉහළ	3.22
15	G/C/25/48	ගා/විද්‍යානන්ද ක.වි	පැති බැම්ම අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	34,000.00	C 8 හෝ ඉහළ	4.40
16	G/C/25/49	ගා/උනන්තවිටිය රේවත ම.වි	90*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	36,000.00	C 8 හෝ ඉහළ	4.66
17	G/C/25/50	ගා/සිරි පඬංකර ප්‍රා.වි	80*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	25,000.00	C 9 හෝ ඉහළ	3.15
18	G/C/25/51	ගා/බටදූව සිරි රතනජෝති ම.වි	90*25 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	26,000.00	C 9 හෝ ඉහළ	3.28
19	G/C/25/52	ගා/අක්මීමණ ම.වි	100*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	38,000.00	C 8 හෝ ඉහළ	4.97
20	G/C/25/53	ගා/ආනන්ද විජය විද්‍යාලය	90*25 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	25,000.00	C 9 හෝ ඉහළ	3.21
21	G/C/25/54	ගා/ඉදුරුව ම.වි	120*20 ගොඩනැගිල්ල	නඩත්තු සැලැස්ම	3,000.00	49,000.00	C 8 හෝ ඉහළ	6.47

			අලුත්වැඩියාව					
22	G/C/25/55	ගා/තලංගහ සරස්වතී දෙමළ පාසල	වැසිකිළ පද්ධතිය ඉදි කිරීම	පළාත් නිශ්චිත	1,000.00	16,000.00	C 9 හෝ ඉහළ	1.99
23	G/C/25/56	ගා/දික්කුඹුර සිද්ධාර්ථ ම.වි	120*30 ප්‍රධාන ශාලාව නවීකරණය	පළාත් නිශ්චිත	2,500.00	40,000.00	C 8 හෝ ඉහළ	5.29
24	G/C/25/57	ගා/ලේල්වල ක.වි	80*20 ගොඩනැගිල්ල අලුත්වැඩියාව	පළාත් නිශ්චිත	3,500.00	75,000.00	C 8 හෝ ඉහළ	9.93
25	G/C/25/58	ගා/පොරවගම ක.වි	පැති බැම්ම අලුත්වැඩියාව	පළාත් නිශ්චිත	2,500.00	34,000.00	C 8 හෝ ඉහළ	4.39
26	G/C/25/59	ගා/ගනේගම රෝමානු කතෝලික පාසල	80*20 නව ගොඩනැගිල්ල ඉදි කිරීම	පළාත් නිශ්චිත	1,500.00	20,000.00	C 9 හෝ ඉහළ	2.60
27	G/C/25/60	ගා/ශ්‍රීපති ම.වි	80*20 දෙමහල් ගොඩනැගිල්ල ඉදි කිරීම	පළාත් නිශ්චිත	2,500.00	37,000.00	C 8 හෝ ඉහළ	4.79
28	G/C/25/61	ගා/මාමනදොළ ක.වි	90*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	පළාත් නිශ්චිත	2,500.00	32,000.00	C 8 හෝ ඉහළ	4.15
29	G/C/25/62	ගා/උක්වත්ත විද්‍යාලය	90*25 තෙමහල් ගොඩනැගිල්ලේ ඉදි කිරීම (ඉතිරි වැඩ)	පළාත් නිශ්චිත	2,500.00	41,000.00	C 8 හෝ ඉහළ	5.42
30	G/C/25/63	ගා/අක්කරවිස්ස ක.වි	මායිම් තාප්පය අලුත්වැඩියාව	පළාත් නිශ්චිත	1,500.00	25,000.00	C 9 හෝ ඉහළ	3.21
31	G/C/25/64	ගා/කළුවලගල ක.වි	40*20 ගොඩනැගිල්ල ඉදි කිරීම	පළාත් නිශ්චිත	3,000.00	46,000.00	C 8 හෝ ඉහළ	6.07
32	G/C/25/65	ගා/අවිත්තාව නාලන්දා ම.වි	80*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	පළාත් නිශ්චිත	1,500.00	29,000.00	C 9 හෝ ඉහළ	3.73
33	G/C/25/66	ගා/මනින්ද රාජපක්ෂ ම.වි	මායිම් තාප්පය අලුත්වැඩියාව	පළාත් නිශ්චිත	3,000.00	61,000.00	C 8 හෝ ඉහළ	7.88
34	G/C/25/67	ගා/ගුණානන්ද ප්‍රා.වි	50*25 ගොඩනැගිල්ල අලුත්වැඩියාව	පළාත් නිශ්චිත	1,500.00	17,000.00	C 9 හෝ ඉහළ	2.16

35	G/C/25/68	ගා/බී.ටී.එස් විද්‍යාලය	80*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	32,000.00	C 8 හෝ ඉහළ	4.07
36	G/C/25/69	ගා/මාවඩවිල ම.වි	90*25 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	24,000.00	C 9 හෝ ඉහළ	3.01
37	G/C/25/70	ගා/සිරිනිවාස ම.වි	100*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	40,000.00	C 8 හෝ ඉහළ	5.31
38	G/C/25/71	ගා/දොළහේන ක.වි	80*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	43,000.00	C 8 හෝ ඉහළ	5.69
39	G /C/25/72	ගා/පිලාන තක්ෂිලා ප්‍රා.වි.	මායිම් තාප්පය නවීකරණය	පළාත් නිශ්චිත	1,000.00	14,000.00	C9 හෝ ඉහළ	1.8
40	G /C/25/73	ගා/සංසරනන ප්‍රා.වි.	100*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව.	පළාත් නිශ්චිත	2,500.00	34,000.00	C8 හෝ ඉහළ	4.4
41	G/C/25/74	ගා/තෙලිකඩ ම.වි.	80*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	පළාත් නිශ්චිත	2,500.00	35,000.00	C8 හෝ ඉහළ	4.5
42	G/C/25/75	ගා/කරන්දෙණිය ක.වි.	80*20 ගොඩනැගිල්ල අලුත්වැඩියාව	පළාත් නිශ්චිත	1,500.00	29,000.00	C9හෝ ඉහළ	3.7
43	G/C/25/76	ගා/ලේනගල්පලා ත ක.වි.	80*20 ගොඩනැගිල්ල අලුත්වැඩියාව	පළාත් නිශ්චිත	1,500.00	27,000.00	C9 හෝ ඉහළ	3.4
44	G /C/25/77	ගා/රතනසාර ම.වි.	100*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	පළාත් නිශ්චිත	1,500.00	23,000.00	C9 හෝ ඉහළ	2.9
45	G /C/25/78	ගා/යටගල ම.වි.	මායිම් තාප්පය අලුත්වැඩියා කිරීම.	පළාත් නිශ්චිත	2,500.00	39,000.00	C8 හෝ ඉහළ	5.1
46	G /C/25/79	ගා/ඔල්කට ම.වි	80*20 ගොඩනැගිල්ල අලුත්වැඩියාව	පළාත් නිශ්චිත	2,500.00	40,000.00	C8 හෝ ඉහළ	5.3
47	G /C/25/80	ගා/තෙල්ලඹුර විජය ක.වි.	පැති බැම්ම ඉදි කිරීම.	පළාත් නිශ්චිත	2,500.00	34,000.00	C8 හෝ ඉහළ	4.3
48	G /C/25/81	ගා/හියාරේ ම.වි.	80*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	පළාත් නිශ්චිත	2,500.00	45,000.00	C8 හෝ ඉහළ	5.8
49	G /C/25/82	ගා/උස්වතුන් හසානා ම.වි.	160*25 තෙමහල් ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව.	පළාත් නිශ්චිත	2,500.00	34,000.00	C8 හෝ ඉහළ	4.4
50	G /C/25/83	ගා/බුද්ධදත්ත ප්‍රා.වි.	120*20 ප්‍රධාන ශාලාව අලුත්වැඩියාව	පළාත් නිශ්චිත	3,500.00	64,000.00	C8 හෝ ඉහළ	8.4
51	G /C/25/84	ගා/සිරි අභයනිස්ස ක.වි.	දෙමහල් ගොඩනැගිල්ලේ යකඩ ග්‍රිල් සවි කිරීම.	නඩත්තු සැලැස්ම	1,000.00	16,000.00	C9 හෝ ඉහළ	1.9
52	M/C/25/31	මාර/පර්සි අබේවර්ධන	80*20 ගොඩනැගිල්ලේ	නඩත්තු	2,500.00	40,000.00	C8 හෝ ඉහළ	5.3

		විද්‍යාලය	වහල අලුත්වැඩියාව.	සැලැස්ම				
53	M/C/25/4 4	මාර/පීනරාජ ක.වි.	වැසිකිළි පද්ධතිය අලුත්වැඩියා කිරීම.	පළාත් නිශ්චිත	1,500.00	22,000.00	C9 හෝ ඉහළ	2.1
54	M/C/25/5 2	අකුරැස්ස කලාප අධ්‍යාපන කාර්යාලය	පැති බැම්ම ප්‍රතිසංස්කරණය කිරීම	නඩත්තු සැලැස්ම	1,500.00	28,000.00	C 9 හෝ ඉහළ	3.59
55	M/C/25/5 3	මාර/කරගොඩ උයන්ගොඩ ම.වි	වැසිකිළි පද්ධතිය ඉදි කිරීම	පළාත් නිශ්චිත	1,500.00	20,000.00	C 9 හෝ ඉහළ	2.57
56	M/C/25/5 4	මාර/බැරගම ක.වි	වැසිකිළි පද්ධතිය ඉදි කිරීම	පළාත් නිශ්චිත	1,500.00	19,000.00	C 9 හෝ ඉහළ	2.42
57	M/C/25/5 5	මාර/පොල්වත්ත ප්‍රා.වි	ප්‍රධාන ශාලාව අලුත්වැඩියා කිරීමේ ඉතිරි වැඩ සම්පූර්ණ කිරීම	පළාත් නිශ්චිත	2,500.00	34,000.00	C 8 හෝ ඉහළ	4.48
58	M/C/25/5 6	මාර/මාතර ආදර්ශ ප්‍රා.වි	වැසි ජලය කළමනාකරණ පද්ධතිය නවීකරණය කිරීම	පළාත් නිශ්චිත	1,500.00	21,000.00	C 9 හෝ ඉහළ	2.69
59	M/C/25/5 7	මාර/කිරින්ද ආදර්ශ ප්‍රා.වි	70*25 දෙමහල් ගොඩනැගිල්ල නවීකරණය කිරීම	පළාත් නිශ්චිත	4,000.00	79,000.00	C 7 හෝ ඉහළ	10.43
60	M/C/25/5 8	මාර/තල්පාවිල ම.ම.වි	ක්‍රීඩා පිටිය සංවර්ධනය කිරීම	පළාත් නිශ්චිත	2,500.00	42,000.00	C 8 හෝ ඉහළ	5.47
61	M/C/25/5 9	මාර/කඹුරුගමුව ම.වි	80*20 තනි මහල් ගොඩනැගිල්ල 90*25 දෙමහල් ගොඩනැගිල්ලට නවීකරණය කිරීම (අදියර 01)	පළාත් නිශ්චිත සංවර්ධන ප්‍රදාන	4,000.00	88,000.00	C 7 හෝ ඉහළ	11.69
62	M/C/25/6 0	මාර/බෙලිදෙණිය ම.වි	60*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියා කිරීම	පළාත් නිශ්චිත	1,500.00	27,000.00	C 9 හෝ ඉහළ	3.57
63	H/C/25/2 6	හ/මහගල්වැව ක.වි	90*25 දෙමහල් ගොඩනැගිල්ලේ බිම් මහලේ කාර්යාල කාමරය සකස් කිරීම	නඩත්තු සැලැස්ම	1,500.00	21,000.00	C 9 හෝ ඉහළ	2.73
64	H/C/25/2 7	හ/දුටුගැමුණු ම.වි	90*25 තෙමහල් ගොඩනැගිල්ලේ වහලය අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	23,000.00	C 9 හෝ ඉහළ	3.05
65	H/C/25/2 8	හ/සපුතන්ත්‍රිකන්ද ප්‍රා.වි	පැති බැම්ම හා ජල කුළුණ ඉදි කිරීම	පළාත් නිශ්චිත	1,500.00	20,500.00	C 9 හෝ ඉහළ	2.7
66	H/C/25/2 9	හ/මිද්දෙනිය ම.වි	රැඳවුම් තාප්පය ඉදිකිරීම (ක්‍රීඩා පිටිය සඳහා ආරක්ෂක තාප්පය)	පළාත් නිශ්චිත	3,000.00	47,500.00	C 8 හෝ ඉහළ	6.27
67	H/C/25/3 0	හ/ගඟේයාය ක.වි	80*20 ගොඩනැගිල්ල අලුත්වැඩියාව	පළාත් නිශ්චිත	1,500.00	27,000.00	C 9 හෝ ඉහළ	3.55
68	H/C/25/3 1	තංගල්ල කලාප අධ්‍යාපන කාර්යාලයේ	මායිම් තාප්පය ඉදිකිරීම(ඉතිරි වැඩ)	පළාත් නිශ්චිත	1,000.00	12,000.00	C 9 හෝ ඉහළ	1.49

69	H/C/25/3 2	හ/බෙලිඅත්ත ම.ම.වී	100*20 තාක්ෂණික විද්‍යාගාරය ගොඩනැගිල්ල නවීකරණය	පළාත් නිශ්චිත	3,500.00	67,500.00	C 8 හෝ ඉහළ	8.91
70	H/C/25/3 3	හ/කදිරගොඩ ප්‍රා.වී	වැසිකිළි අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	18,000.00	C 9 හෝ ඉහළ	2.28
71	H/C/25/3 4	හ/ගොඩවානගොඩ ක.වී	වැසිකිළි අලුත්වැඩියාව සහ මායිම් තාප්පය අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	21,000.00	C 9 හෝ ඉහළ	2.67
72	H/C/25/3 5	හ/කුඩාවැල්ල ක.වී	වැසිකිළි අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,000.00	14,000.00	C 9 හෝ ඉහළ	1.82
73	H/C/25/3 6	හ/රදනිආර ම.වී	පරිගණක විද්‍යාගාරය අලුත්වැඩියා කිරීම	නඩත්තු සැලැස්ම	1,500.00	23,000.00	C 9 හෝ ඉහළ	2.94
74	H/C/25/3 7	හ/කිරම ධම්මානන්ද ප්‍රා.වී	80*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	37,000.00	C 8 හෝ ඉහළ	4.80
75	H/C/25/3 8	හ/කැරදෙනිය ක.වී	40*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	28,000.00	C 9 හෝ ඉහළ	3.69
76	H/C/25/3 9	හ/අගලබඩ ක.වී	60*20 ගොඩනැගිල්ල අලුත්වැඩියා කිරීම	නඩත්තු සැලැස්ම	1,500.00	23,000.00	C 9 හෝ ඉහළ	2.97
77	H/C/25/4 0	හ/අල්අමීර් මුස්ලිම් විද්‍යාලය	මායිම් තාප්පය අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	16,000.00	C 9 හෝ ඉහළ	2.08
78	H/C/25/4 1	හ/පල්ලෙපුලම්පිටිය ම.වී	60*20 ගොඩනැගිල්ල අලුත්වැඩියා කිරීම	නඩත්තු සැලැස්ම	1,500.00	30,000.00	C 9 හෝ ඉහළ	3.93
79	H/C/25/4 2	හ/කැකිරිඔබඩ ක.වී	පුස්තකාල ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	39,000.00	C 8 හෝ ඉහළ	5.1
80	H/C/25/4 3	හ/බෙරලිහෙල ම.වී	80*20 ගොඩනැගිල්ල සහ 50*25 කාර්යාල ගොඩනැගිල්ල වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	21,000.00	C 9 හෝ ඉහළ	2.74
81	H/C/25/4 4	හ/ගැටමාන්ත දකුණ ම.වී	100*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	37,000.00	C 8 හෝ ඉහළ	4.87
82	H/C/25/4 5	හ/ගැටමාන්ත උතුර ක.වී	100*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	39,000.00	C 8 හෝ ඉහළ	5.07
83	H/C/25/4 6	හ/බුන්දල ක.වී	80*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	32,000.00	C 8 හෝ ඉහළ	4.22
84	H/C/25/4 7	හ/පලපොත ම.වී	100*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	27,000.00	C 9 හෝ ඉහළ	3.55
85	H/C/25/4 8	හ/බටඅත දකුණ ක.වී	40*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	19,000.00	C 9 හෝ ඉහළ	2.49
86	H/C/25/4 9	හ/කහවත්ත ම.වී	නෙප්පුන් ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	3,000.00	61,000.00	C 8 හෝ ඉහළ	8.00

87	H/C/25/5 0	හ/කණුකැටිය ක.වි	80*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	24,000.00	C 9 හෝ ඉහළ	3.06
88	H/C/25/5 1	හ/දෙබරවැව ජනාධිපති විද්‍යාලය	120*20 ගොඩනැගිල්ල වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	40,000.00	C 8 හෝ ඉහළ	5.25
89	H/C/25/5 2	හ/දෙනිය පිංගම ක.වි	80*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	19,000.00	C 9 හෝ ඉහළ	2.44
90	H/C/25/5 3	හ/මීගහවෙල ක.වි	120*20 ගොඩනැගිල්ලේ වහල සහ වැසිකිළි අලුත්වැඩියාව	පළාත් නිශ්චිත	1,500.00	17,000.00	C 9 හෝ ඉහළ	2.2
91	H/C/25/5 4	හ/මොරයාය ම.වි	120*20 ගොඩනැගිල්ල අලුත්වැඩියාව	පළාත් නිශ්චිත	3,000.00	60,000.00	C 8 හෝ ඉහළ	7.94
92	H/C/25/5 5	හ/වැකඳවල ජනපද ම.වි	120*20 ගොඩනැගිල්ල අලුත්වැඩියාව	පළාත් නිශ්චිත	3,500.00	63,000.00	C 8 හෝ ඉහළ	8.33
93	H/C/25/5 6	හ/හිඟුරකන්ද ම.වි	72*16 ගොඩනැගිල්ල ප්‍රතිසංස්කරණය කිරීම	පළාත් නිශ්චිත	1,000.00	14,000.00	C 9 හෝ ඉහළ	1.81
94	H/C/25/5 7	හ/ලුණුගම්වෙහෙර ම.වි	වැසිකිළි පද්ධතිය ඉදිකිරීම	පළාත් නිශ්චිත	1,500.00	16,000.00	C 9 හෝ ඉහළ	2.00
95	H/C/25/5 8	හ/කටුවන ප්‍රා.වි	විද්‍යාලයේ පැති පැමිම ඉදි කිරීම	පළාත් නිශ්චිත සංවර්ධන ප්‍රදාන	2,500.00	35,000.00	C 8 හෝ ඉහළ	4.55
96	H/C/25/5 9	හ/රතනපෝති ප්‍රා.වි,ගඟලන්දෙනි ය	පැතිබැමිම ඉදි කිරීම (ක්‍රීඩා පිටිය ඉදිරිපස)	පළාත් නිශ්චිත	2,500.00	40,000.00	C 8 හෝ ඉහළ	5.28
97	H/C/25/6 0	හ/වැවේගම ක.වි	60*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	24,000.00	C 9 හෝ ඉහළ	3.10
98	H/C/25/6 1	හ/පොළොම්මාරුව ආදර්ශ විද්‍යාලය	වැසිකිළි අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	17,000.00	C 9 හෝ ඉහළ	2.2
99	G/CSL/25 /01	ගා/උනන්විටිය රේවත ම.වි.	පැති බැමිම ඉදි කිරීම	ක්ලීන් ශ්‍රී ලංකා	1,500.00	23,000.00	C 9 හෝ ඉහළ	2.8
100	G/CSL/25 /02	ගා/ඇත්තිලිගොඩ සුදර්ශි ම.වි.	80 X 20 ගොඩනැගිල්ල නවීකරණය	ක්ලීන් ශ්‍රී ලංකා	1,000.00	16,000.00	C 9 හෝ ඉහළ	1.9
101	G/CSL/25 /03	ගා/දෙල්ලව ම.වි.	පැති බැමිම ඉදි කිරීම	ක්ලීන් ශ්‍රී ලංකා	1,500.00	29,000.00	C 9 හෝ ඉහළ	3.6
102	M/CSL/25 /01	මාර/දම්පැල්ල ම.වි.	සංගීත හා නැටුම් කාමර නවීකරණය	ක්ලීන් ශ්‍රී ලංකා	1,000.00	9,000.00	C 9 හෝ ඉහළ	1.1
103	G/CSL/2 5/04	ගා/ රතනසිරි රාජකීය විද්‍යාලය	ගැහැණු වැසිකිළි ඉදි කිරීම	ක්ලීන් ශ්‍රී ලංකා	1,500.00	29,000.00	C 9 හෝ ඉහළ	3.7
104	G/CSL/2 5/05	ගා/ අනුරුද්ධ ක.වි.	වැසිකිළි නවීකරණය (පිරිමි වැසිකිළි 02 හා ගැහැණු වැසිකිළි	ක්ලීන් ශ්‍රී ලංකා	1,000.00	8,000.00	C 9 හෝ ඉහළ	1.0

			04)					
105	G/CSL/2 5/06	ගා/සිරි අභයනිස්ස ම.වි.	ගුරුවරුන්ගේ සහ සිසුන්ගේ වැසිකිලි නවීකරණය	ක්ලීන් ශ්‍රී ලංකා	1,500.00	22,000.00	C 9 හෝ ඉහළ	2.8
106	G/CSL/2 5/07	ගා/දික්කුමුර ප්‍රා.වි.	වැසිකිලි පද්ධතියක් ඉදි කිරීම	ක්ලීන් ශ්‍රී ලංකා	2,500.00	33,000.00	C 8 හෝ ඉහළ	4.2
107	G/CSL/2 5/08	ගා/හවිසේ ම.වි.	වැසිකිලි නවීකරණය	ක්ලීන් ශ්‍රී ලංකා	1,000.00	7,000.00	C 9 හෝ ඉහළ	0.9
108	G/CSL/2 5/09	ගා/හස්පිටිය ක.වි.	ගුරුවරුන්ගේ වැසිකිලි ඉදි කිරීම	ක්ලීන් ශ්‍රී ලංකා	1,500.00	29,000.00	C 9 හෝ ඉහළ	3.7
109	G/CSL/2 5/10	ගා/බටපොල ම.ම.වි.	වැසිකිලි ඉදි කිරීම	ක්ලීන් ශ්‍රී ලංකා	2,500.00	34,000.00	C 8 හෝ ඉහළ	4.3

02. ජාතික තරඟකාරී ලංසු පටිපාටිය මත ලංසු ඉදිරිපත් කළ යුතුය. කොන්ත්‍රාත් ප්‍රදානයේදී සුදුසුකම් ලබන සාර්ථක ලංසුකරුවන් අසාධු ලේඛනගත නොවිය යුතු අතර ඉදිකිරීම් කර්මාන්ත සංවර්ධන අධිකාරියේ ඉහත කාණ්ඩ යටතේ ලියාපදිංචි වී සිටිය යුතුය.

03.ලංසු අයදුම්පත් 2025.06.18 දින සිට 2025.07.03 දින දක්වා පෙ.ව 9.00 සිට ප.ව 3.00 දක්වා ඉහත දක්වා ඇති පරිදි ආපසු නොගෙවන ගාස්තුව අධ්‍යාපන අමාත්‍යාංශයේ ගිණුම් අංශයේ සරප් වෙත මුදල් ගෙවීමෙන් අනතුරුව ලබාදෙන මුදල් කුවිතාන්සිය ඉදිරිපත් කර හෝ ආපසු නොගෙවන ගාස්තුව අධ්‍යාපන අමාත්‍යාංශ ලේකම් නමින් ගාල්ල කොටුව ලංකා බැංකුවේ ඇති ගිණුම් අංක 1587423 ට බැර කර රිසිට් පත සමග ඔබගේ ඉල්ලීම් ලිපිය ද.ප. අධ්‍යාපන අමාත්‍යාංශයේ **070 7130700** දරණ වටිස්අප් අංකයට පමණක් හෝ acc.moesp@gmail.com ඊ මේල් ලිපිනයට පමණක් යොමු කිරීමෙන් ඔබට අවශ්‍ය ලංසු පත්‍රිකා තැපැල් මගින් හෝ කුරියර් කර හෝ ඊමේල් මගින් හෝ වටස්අප් මගින් ගෙන්වා ගැනීමට හෝ ලබුදුව,දක්ෂිණපාය අධ්‍යාපන අමාත්‍යාංශයෙන් (බිම් මහල) ගිණුම් අංශයෙන් ලබා ගත හැකිය. වැඩි විස්තර අමාත්‍යාංශයේ 091-2030700 දුරකථන අංකයට වැඩ කරන දින ඇමතීමෙන් හෝ ද.ප. අධ්‍යාපන අමාත්‍යාංශ වෙබ් අඩවියට www.edumin.sp.gov.lk පිවිසීමෙන් අදාල ලංසු පත්‍රිකා පරීක්ෂා කළ හැකිය.

04. මුද්‍රා තබන ලද ලංසු පත්‍රිකා 2025.07.04 පෙ.ව 11.00 ට පෙර ලැබෙන සේ ලේකම්, දකුණු පළාත් අධ්‍යාපන අමාත්‍යාංශය, දක්ෂිණපාය, ලබුදුව, ගාල්ල යන ලිපිනයට ලියාපදිංචි තැපෑලෙන් එවීමට හෝ අතින් රැගෙන විත් ප්‍රධාන ගණකාධිකාරී නිල කාමරයේ තබා ඇති ටෙන්ඩර් පෙට්ටියට බහාලිය හැකිය. ප්‍රමාද වී ලැබෙන ලංසු ප්‍රතික්ෂේප කරනු ලැබේ.

05.ලංසු විවෘත කිරීම 2025.07.04 දින පෙ.ව 11.00 ට ලංසු පත්‍රිකා භාරගෙන අවසන් වූ වහාම දකුණු පළාත් අධ්‍යාපන අමාත්‍යාංශයේ ප්‍රසම්පාදන කමිටු සභාපතිගේ ප්‍රධානත්වයෙන් අමාත්‍යාංශයේදී සිදු කරන අතර එම අවස්ථාවට ලංසුකරුට හෝ ලංසුකරුගේ බලයලත් නියෝජිතයන් හට සහභාගී විය හැක.

06. ලංසුව සමඟ ඉදිරිපත් කරන ලංසු සුරක්ෂණය ශ්‍රී ලංකා වාණිජ බැංකුවකින් දකුණු පළාත් අධ්‍යාපන අමාත්‍යාංශයේ ලේකම් නමට ලබා ගත් 2025.07. 04 දින සිට 2025.10.04 දක්වා වලංගු ලංසු ඇපකරයක් හෝ අධ්‍යාපන අමාත්‍යාංශයේ ගිණුම් අංශය වෙත මුදල් ගෙවීමෙන් අනතුරුව ලබාදෙන මුදල් කුවිතාන්සියේ පිටපත ලංසු පත්‍රිකාව සමඟ ඉදිරිපත් කළ යුතුය.

07. ලංසු වලංගු කාලය දින 77 කි.

08. ඉදිරිපත් කරනු ලබන කර්මාන්තයට අදාළ ලංසු පිටපත් දෙකකින් යුතුව ඉදිරිපත් කළයුතු අතර එහි මුල් පිටපතෙහි “ මුල් පිටපත” යනුවෙන් සඳහන් කළ යුතු අතර අනු පිටපතෙහි “ අනුපිටපත” යනුවෙන් සඳහන් කළ යුතුය. ලංසුපත් වල මුල් පිටපත හා අනුපිටපත වෙන වෙනම කවරවල බහා මුද්‍රා තබා එම කවර දෙක එක් කවරයක බහා එම කවරය මුද්‍රා තබා කවරයේ වම් පස උඩකෙළවරේ කර්මාන්තයේ නම සහ අංකය සඳහන් කළ යුතුය.

09. ඔබ විසින් ඉදිරිපත් කිරීමට නියමිත සෑම ලංසු පත්‍රිකාවෙහිම මිල ගණන් සඳහන් කර ඇති පිටු අංකයන්හි ඔබ විසින් සඳහන් කළ යුතු ඒකක මිල ගණන් හා මුළු මුදල දැක්වෙන තීරය සහ සාරාංශයද (වට්ටම් දැක්වෙන තීරයද ඇතුළත්ව) විනිවිද පෙනෙන සේ සෙලෝටේප් කර ලංසු ඉදිරිපත් කිරීම අනිවාර්ය වේ.

10. ද.ප. අධ්‍යාපන අමාත්‍යාංශය දැනටමත් දකුණු පළාතේ පාසල්වල ඉදිකිරීම් අලුත්වැඩියා හා නඩත්තු කටයුතුවලට අදාළ ව්‍යාපෘති සියයක පමණ ප්‍රසම්පාදන කටයුතු අවසන් කර ඉදිකිරීම් කටයුතු ආරම්භ කර ඇත. එමෙන්ම මෙම ව්‍යාපෘති එකසිය නමයෙහි ද ප්‍රසම්පාදන කටයුතු හැකි ඉක්මනින් අවසන් කර ව්‍යාපෘතිවල වැඩ 2025 වසරේ දෙසැම්බර් මස වනවිට අවසන් කළ යුතු බැවින් ලංසුකරුවන්ගේ ධාරිතාවය පිළිබඳ ලංසු ප්‍රදානයේදී සලකා බලනු ලැබේ.

11. අඩුපාඩු සහිත ලංසුපත්‍රිකා ප්‍රතික්ෂේප කරනු ලබන ලැබේ. මෙම ප්‍රසම්පාදනය සම්බන්ධයෙන් ප්‍රසම්පාදන කමිටුවේ තීරණය අවසාන තීරණය බව සැලකිය යුතුය.

ඒ.යූ.වේලාරත්න,

ප්‍රසම්පාදන කමිටු සභාපති,

දකුණු පළාත් අධ්‍යාපන අමාත්‍යාංශය,

පළමු මහල, දක්ෂිණපාය, ලබුදූව, ගාල්ල.

2025.06.18

දුරකථන අංකය - 0912030700 ඊමේල් - acc.moesp@gmail.com

SECTION 4

FORM OF BID AND QUALIFICATION INFORMATION

FORM OF BID

Name of Contract : Renovation of boundary wall at H/Al Ameer Muslim M.V.

To : Secretary, Ministry of Education, Southern Province.

Gentleman,

Having examined the Standard Bidding Document - Procurement of Works - Minor Contracts [ICTAD/ SBD/ 03 - Second Edition, January 2007], Schedule, Specifications, Drawings and Bills of Quantities and addenda for the execution of the above named Works, we/I the undersigned, offer to execute and complete such Works and remedy any defect therein in conformity with the aforesaid Conditions of Contract, Schedule, Specifications, Drawings, Bill of Quantities and Addenda for the sum of Sri Lankan Rupees

..... (LKR) or such other sums as may be ascertained in accordance with the said Conditions.

We/I acknowledge that the Schedule forms part of our/my Bid.

We/I undertake, if our Bid is accepted, to commence the Works as stipulated in the Schedule, and to complete the whole of the Works comprised in the Contract within the time stated in the Schedule.

We/I agree to abide by this bid for the period stated in the Sub-Clause 15 of Instructions to Bidders or any extended period and it shall remain binding upon us and may be accepted at any time before the expiration of that period.

Unless and until a formal agreement is prepared and executed this Bid, together with your written acceptance thereof, shall constitute a binding contract between us/me.

We/I understand that you are not bound to accept the lowest or any Bid you may receive.

Dated this day of 20.... in the capacity of duly authorized to sign tenders for and on behalf of

..... (IN BLOCK CAPITALS)

Signature :

Name :

Designation :

Address :

Witness :

Qualification Information

(to be completed by the bidder and submitted with the Bid)

	Eligibility Requirement	Bidder's Qualification
ICTAD Registration		
Registration number		
Grade	C9 or Above	
Speciality	Buildings	
Expiry Date		
Backlisted Contractors		
Have you been declared as a defaulted contractor by NPA or any other Agency?		Yes /No
IF yes provide details		
VAT Registration Number		
Construction Program	(attach as annex)	
Legal status	Public company/Private Company/Partnership/Sole proprietor	
	Eligibility Requirement	Bidder's Qualification
Qualification and experience of key staff	Category, Experience and Qualifications <i>(Insert requirement)*</i>	Required Nos.* Proposed by bidder (Name, experience and Qualifications)
	1	
	2	
	3	
List Other information required		

Signature of the Bidder :

SECTION 5

SCHEDULE

Schedule

ITB Clause	Conditions of Contract Clause	Item	Data
1.	1.1.8	Employer is :	Name : Secretary Address: Ministry of Education, Southern Province.
	1.1.10	Engineer is:	Name : District Engineer (Buildings) Address: District Engineer (Buildings) Office, 2nd Floor, Administrative Complex, Hambantota.
1 & 13	1.1.21	Summary of Works	The Works consists of: Located at : H/Al Ameer Muslim M.V. Contract Name : Renovation of boundary Wall Contract Number H/C/25/40
	1.1.14	Intended Completion Date	Intended Completion Date is 60 Days from the Start Date
2.		Source of Funds	The source of funds is
3.		Eligibility	The requirement is CIDA C9 or Above or Approved Societies * shall be included in the List of “Approved Societies” issued by the General Treasury.
12.		Documents of the Bid	Any other information
13.	10.10	Price Adjustment	The Contract is / is not subject to price adjustment in accordance with Sub-Clause 10.10 of the Conditions of Contract. The price adjustment shall be computed in accordance with Option B under sub clause 10.10. Non adjustable element shall be: BOQ Item Numbers : Option B: Type of Construction: Non residential buildings

16.		Bid Security	<p>Bid shall include a Bid Security:</p> <p>for an amount LKR 16,000.00 issued by an agency acceptable to Employer using the form for bid security (unconditional guarantee) included in Section 9, Standard Forms, remain valid till 2025.10.04</p> <p>or</p> <p>if paid by cash to the Employer, LKR 16,000.00</p>
31.	4.4	Performance Security	<p>Amount of Performance Security required is 5% of the Initial Contract Price</p> <p>The form acceptable is unconditional guarantee as standard form as per SBD/03</p>
	6.4	Late Completion	The amount to be paid is 0.05 % of Initial Contract Price per Day, subjected to maximum of 10 % of Initial Contract Price.
	8.1	Notification of Defects	The period for Defect Notification is 180 Days from Taking Over.
	10.3	Retention	<p>The amount of retention is 10 % of certified work done.</p> <p>The maximum amount of retention is 5 % of Initial Contract Price.</p>
	10.12	Advance Payment	Upon the payment of the advance payment in full the Employer shall return the original of the advance payment guarantee to the Contractor.
	13.1 (c)	Insurance, third party	Minimum amount for third party insurance is LKR 100,000.00
	13.1 (a)	Insurance for Works, Material and plant	The minimum cover for insurance of the works and plant and materials is 110% of initial contract price.
	13.1	Insurance for Contractor's Personnel	Minimum amount for Insurance is LKR 500,000.00
33.	1.1.11	Adjudicator	<i>CIDA</i>
	14.0	Resolution of Disputes	<p>Deputy Chief Secretary (Engineering Services), Southern Province</p> <p><i>Fees and types of reimbursable expenses to be paid to the Adjudicator shall be on a case to case basis and shall be shared by the Contractor and the Employer.</i></p>

SECTION 6

SPECIFICATIONS

TECHNICAL SPECIFICATIONS

Technical specification that are applicable to this project are listed below:

SCA/3/1	-	Irrigation and Land Drainage
SCA/3/2	-	Water Supply Sewerage and Storm Water Drainage
SCA/3/3	-	Reclamation Works
SCA/3/4	-	Ground Water Exploration & Exploitation
SCA/4/I	-	Building Works (Vol I)
SCA/4/II	-	Building Works (Vol II)
SCA/5	-	Roads and Bridges
SCA/6	-	Coastal Harbour Engineering Works
SCA/8	-	Electrical and Mechanical Works
ICTAD/DEV/16	-	Board & Cast In situ Reinforced Concrete Piles
ICTAD/DEV/17	-	Site Investigation for Building Works & Sample Bill of Quantities

Any other specification approved by the Government.

Above publications shall be purchase from the Construction Industry Development Authority (CIDA), Savusiripaya, 123. Wijerama Mawatha, Colombo 07.

SECTION 7

BILL OF QUANTITIES

RENOVATION OF BOUNDARY WALL AT H/AL AMEER MUSLIM M.V.

ID	Description	Unit	Qty.	Rate	Amount
New boundary wall					
	<u>DEMOLISH WORKS</u>				
1	Uprooting fence post , rolling up and stacking barbed wire and all . other materials (Length of fencing to be measured)	m	21.50		
	<i>Total carried to summary</i>				
	<u>EARTH WORKS</u>				
2	Earth cutting and levelling site by manually in any material except rock requiring blasting, including transporting within 1/4 mile, depositing and levelling	cu.m	8.00		
3	Excavation for foundation by manually in any material except rock requiring blasting, part return fill in and ram, and disposing surplus within site as directed. (not exceeding 5ft depth)	cu.m	6.00		
	<i>Total carried to summary</i>				
	<u>BRICK WORKS</u>				
4	Brickwork 112mm in cement : sand mortar 1:5 (Ground Floor)	sq.m	30.00		
	<i>Total carried to summary</i>				
	<u>CONCRETE WORKS</u>				
5	Cement concrete 1:3:6 (1") up to 3.00 m3(Shuttering paid separately) incl: curing(Grade 15)	cu.m	0.15		

6	Cement concrete 1:2:4(3/4") (Gr.20 concrete) (R/F and Shuttering paid separately)incl: curing.Rate to include using mixture & vibrator for column footing.	cu.m	0.50		
7	Cement concrete 1:2:4(3/4") (Gr.20 concrete) (R/F and Shuttering paid separately)incl: curing.Rate to include using mixture & vibrator for column shaft up to D.P.C	cu.m	0.50		
8	Cement concrete 1:2:4(3/4") (Gr.20 concrete) (R/F and Shuttering paid separately)incl: curing.Rate to include using mixture & vibrator for plinth beam.	cu.m	1.00		
9	Cement concrete 1:2:4(3/4") in column shafts in ground floor, using mixer and vibrator.Rate to include curing.(Reinforcement, shuttering and finishes paid separately) -Gr.20	cu.m	0.60		
10	Cement concrete 1:2:4(3/4") (Gr.20 concrete) (R/F and Shuttering paid separately)incl: curing(manual mixing up to 3m3) for copping	cu.m	0.20		

District Engineer's (Buildings) Office - Hambanthota

ID	Description	Unit	Qty.	Rate	Amount
	<i>Total carried to summary</i>				
	<u>REINFORCEMENT WORKS</u>				
11	10mm dia r/f for column footing	kg	28.00		
12	10mm dia r/f for column shaft up to dpc	kg	33.00		
13	10mm dia r/f for column shaft Ground floor	kg	30.00		
14	10mm dia r/f for plinth beam	kg	58.00		
15	6mm dia r/f for coping	kg	10.00		
16	6mm dia r/f for column shaft up to dpc stirrups	kg	11.00		
17	6mm dia r/f for column shaft Ground floor	kg	15.00		
	<i>Total carried to summary</i>				
	<u>RRM WORKS</u>				
18	Random Rubble Masonry in cement mortar 1:5 in substructure (6"- 9" rubble)	cu.m	7.00		
	<i>Total carried to summary</i>				
	<u>PLASTER WORKS</u>				
19	Cement Sand plastering to wall 1:5, (5/8") thick semi rough G: floor rate to include curing	sq.m	62.00		
20	3/8 " Thick plastering to RCC column in cement and sand 1:3 (G: Floor)	sq.m	6.00		
21	1:3 Rendering cement ,1" thick cement coping finish smooth with neat cement floating (in Ground Floor)	sq.m	5.70		

22	3/4" thk Rendering in Cement and sand 1:3 in floors finished smooth Rate to include curing, - Ground floor for plinth plaster	sq.m	26.00		
	<i>Total carried to summary</i>				
<u>PAINTING WORKS</u>					
23	Painting walls with one coats of Acrylic wall filler for external wall (new work or after preparation of old wall) -Ground floor	sq.m	68.00		
24	Wethershield paint to external faces of wall 02coat apply using roller brush 2" brush (ground Floor)	sq.m	68.00		
	<i>Total carried to summary</i>				
<u>FORM WORK</u>					
25	Sawn timber (class II) formwork for sides of foundation footings.	sq.m	4.00		

District Engineer's (Buildings) Office - Hambanthota

ID	Description	Unit	Qty.	Rate	Amount
26	Sawn timber (class II) formwork for column shaft up to dpc	sq.m	9.50		
27	Shuttering for column shaft 225x225mm including 2mm iron plate and 25mm x 25mm x3mm angle iron welded to bended plate horizontally at 300mm c/c. Rate to include U clips,acro jacks.and dismantling same when required (Rate to include 100mm high 3mm thick sponge layer stick on around concrete column at every lapping face) - (As per detail Drawing No SPES/Rate 23/Fw-09)Ground floor	sq.m	11.00		
28	Form work for plinth beam by using 15mm thick plywood sheets.Flywood board should be fixed to timber frame with 2"x2"timber vertically at 600mm c/c and 50x50mm timber horizontally at top and bottom.Prepared shuttering board should be fixing to required measurements by using wooden props.(2/16'-0"x1'-6"=48.00ft2)(As per detail Drawing No SPES/Rate 23/Fw-02)	sq.m	10.00		
29	Shuttering for 4 1/2"X 3"concrete coping using Class (II) timber planks (Rate to include dismantling same when required).for both sides	m	22.00		
	<i>Total carried to summary</i>				

Old boundary wall

DEMOLISH WORKS

30	Demolishing brickwork in cement clearing debris away from site	cu.m	5.00		
----	--	------	------	--	--

31	Demolishing rubble masonry in cement, stacking rubble and clearing debris away from site (super structure)	cu.m	1.70		
32	Demolishing reinforced cement concrete in suspended floors, removing reinforcement and clearing debris away from site (for minor works)	cu.m	0.10		
33	Removing lime plastering and clearing debris away from site	sq.m	5.00		
	<i>Total carried to summary</i>				
	<u>EARTH WORKS</u>				
34	Excavation for foundation by manually in any material except rock requiring blasting, part return fill in and ram, and disposing surplus within site as directed. (not exceeding 5ft depth)	cu.m	4.50		
	<i>Total carried to summary</i>				
	<u>BRICK WORKS</u>				
35	Brickwork 112mm in cement : sand mortar 1:5 (Ground Floor)	sq.m	44.00		
	<i>Total carried to summary</i>				

District Engineer's (Buildings) Office - Hambanthota

ID	Description	Unit	Qty.	Rate	Amount
	<u>CONCRETE WORKS</u>				
36	Cement concrete 1:3:6 (1") up to 3.00 m ³ (Shuttering paid separately) incl: curing(Grade 15)	cu.m	0.20		
37	Cement concrete 1:2 1/2:5(1") mix: up to 3.0 m ³ (Shuttering paid separately) incl: curing	cu.m	1.00		
38	Cement concrete 1:2:4(3/4") (Gr.20 concrete) (R/F and Shuttering paid separately)incl: curing.Rate to include using mixture & vibrator for column footing	cu.m	0.55		
39	Cement concrete 1:2:4(3/4") (Gr.20 concrete) (R/F and Shuttering paid separately)incl: curing.Rate to include using mixture & vibrator for up to D.P.C	cu.m	0.70		
40	Cement concrete 1:2:4(3/4") (Gr.20 concrete) (R/F and Shuttering paid separately)incl: curing.Rate to include using mixture & vibrator for plinth beam	cu.m	1.40		
41	Cement concrete 1:2:4(3/4") in column shafts in ground floor, using mixer and vibrator.Rate to include curing.(Reinforcement, shuttering and finishes paid separately) -Gr.20	cu.m	0.80		
42	Cement concrete 1:2:4(3/4") (Gr.20 concrete) (R/F and Shuttering paid separately)incl: curing(manual mixing up to 3m ³) for copping	cu.m	0.50		
	<i>Total carried to summary</i>				
	<u>REINFORCEMENT WORKS</u>				
43	10mm r/f for column footing	kg	28.00		
44	10mm r/f for column shaft up to dpc	kg	45.00		

45	10mm r/f for column shaft above dpc	kg	39.00		
46	10mm dia r/f for plinth beam	kg	71.00		
47	6mm r/f for column shaft up to dpc stirrups	kg	15.00		
48	6mm r/f for above dpc column shaft to stirrups	kg	19.00		
49	6mm r/f for plinth beam stirrups	kg	30.00		
	<i>Total carried to summary</i>				
	<u>RRM WORKS</u>				
50	Random Rubble Masonry in cement mortar 1:5 in substructure (6"- 9" rubble)	cu.m	3.50		
	<i>Total carried to summary</i>				
	<u>PLASTER WORKS</u>				

District Engineer's (Buildings) Office - Hambanthota

ID	Description	Unit	Qty.	Rate	Amount
51	Cement Sand plastering to wall 1:5, (5/8") thick semi rough G: floor rate to include curing	sq.m	75.00		
52	3/8 " Thick plastering to RCC column in cement and sand 1:3 (G: Floor)	sq.m	7.00		
53	1:3 Rendering cement ,1" thick cement copping finish smooth with neat cement floating (in Ground Floor)	sq.m	8.00		
54	3/4" thk Rendering in Cement and sand 1:3 in floors finished smooth Rate to include curing, - Ground floor for plinth plaster	sq.m	22.00		
55	1/2" thk 1:3 Cement Rendering finished smooth with neat cement floating, Ground floor(sand to be sieved with 1/8" nets) Rate to include curing	sq.m	16.00		
	<i>Total carried to summary</i>				
	<u>PAINTING WORKS</u>				
56	Painting walls with one coats of Acrylic wall filler for external wall (new work or after preparation of old wall) -Ground floor	sq.m	82.00		
57	Wethershield paint to external faces of wall 02coat apply using roller brush 2" brush (ground Floor)	sq.m	82.00		
	<i>Total carried to summary</i>				
	<u>FORM WORK</u>				
58	Sawn timber (class II) formwork for sides of foundation footings.	sq.m	5.00		

59	Sawn timber (class II) formwork for sides of column shaft up to dpc	sq.m	11.50		
60	Shuttering for column shaft 225x225mm including 2mm iron plate and 25mm x 25mm x3mm angle iron welded to bended plate horizontally at 300mm c/c. Rate to include U clips,acro jacks.and dismantling same when required (Rate to include 100mm high 3mm thick sponge layer stick on around concrete column at every lapping face) -(As per detail Drawing No SPES/Rate 23/Fw-09)Ground floor	sq.m	15.00		
61	Form work for plinth beam by using 15mm thick plywood sheets.Flywood board should be fixed to timber frame with 2"x2"timber vertically at 600mm c/c and 50x50mm timber horizontally at top and bottom.Prepared shuttering board should be fixing to required measurements by using wooden props.(2/16'-0"x1'-6"=48.00ft2)(As per detail Drawing No SPES/Rate 23/Fw-02)	sq.m	13.50		
62	Shuttering for 4 1/2"X 3"concrete copping using Class (II) timber planks (Rate to include dismantling same when required).for both sides	m	29.50		
	<i>Total carried to summary</i>				

District Engineer's (Buildings) Office - Hambanthota

ID	Description	Unit	Qty.	Rate	Amount
	<u>GENERAL WORKS</u>				
63	Clearing site and grubbing up all small trees not exceeding 500mm girth and including bushes, scrubs, undergrowth hedges etc.	sq.m	16.00		
	<i>Total carried to summary</i>				

RENOVATION OF BOUNDARY WALL AT H/AL AMEER MUSLIM M.V.

SUMMARY

new boundary wall

Demolish Works Earth Works

Brick Works Concrete Works

Reinforcement Works RRM Works

Plaster Works Painting Works

Form Work

Demolish Works Earth Works

Brick Works Concrete Works

Reinforcement Works RRM Works

Plaster Works Painting Works old boundary wall

Form Work General Items

.....

.....

.....

.....

SUB TOTAL

SUB TOTAL

RENOVATION OF BOUNDARY WALL AT H/AL AMEER MUSLIM M.V.

(A) BOQ Total	:	LKR
(B) Less for Provisional Sums	:	LKR -
(C) Sub Total (A-B)	:	LKR
(D) Less for Discount (If Any) (..... %)	:	LKR
(E) Sub Total (C-D)	:	LKR
(F) Add for Provisional Sums	:	LKR -
Total Bid Amount (E+F) (Excluding VAT, Carried to Form of Bid))	:	LKR =====

Total Bid Amount in Words

.....

18 % VAT : LKR

Grand Total : LKR =====

Note:

Bidders are requested to provide discounts, if any, as a percentage. Otherwise, it will be converted to a percentage. Your discount will also be applied to variations in quantity."

.....
Signature of Bidder

SECTION 8

DRAWINGS

SECTION 9

STANDARD FORMS

- **Form of Bid Security**
- **Form of Letter of Acceptance**
- **Form of Performance Security**
 - **Agreement**

[Letter heading paper of the procuring entity]

BID SECURITY

[this Guarantee form shall be filled in accordance with the instructions indicated in brackets]

----- *[insert issuing agency's name, and address of issuing branch or office]*

Beneficiary: Secretary, Ministry of Education, Southern Province.

Date: ----- *[insert date (by issuing agency)]*

BID GUARANTEE No.: ----- *[insert (by issuing agency) number]*

We have been informed that -----
[insert (by issuing agency) name of the bidder] (hereinafter called "the bidder") has submitted to you its bid dated ----- *[insert (by issuing agency) date]* (hereinafter called "the Bid") for the execution of **Renovation of boundary wall at H/Al Ameer Muslim M.V.**, under Invitation for Bids No. ----- *[insert IFB number]* ("the IFB").

Furthermore, we understand that, according to your conditions, Bids must be supported by a Bid Guarantee.

At the request of the bidder, we -----
[insert name of issuing agency] hereby irrevocably undertake to pay you any sum or sums not exceeding in total an amount of ----- *[insert amount in figures]* -----
 ----- *[insert amount in words]* upon receipt by us of your first demand in writing accompanied by a written statement stating that the Bidder is in breach of its obligation(s) under the bid conditions, because the Bidder:

- (a) has withdrawn its Bid during the period of bid validity specified; or
- (b) does not accept the correction of errors in accordance with the Instructions to Bidders (hereinafter "the ITB"); or
- (c) having been notified of the acceptance of its Bid by the Employer during the period of bid validity, (i) fails or refuses to execute the Contract Form, if required, or (ii) fails or refuses to furnish the Performance Security, in accordance with the ITB.

This Guarantee shall expire: (a) if the bidder is the successful bidder, upon our receipt of copies of the Contract signed by the bidder and of the Performance Security issued to you by the bidder; or (b) if the bidder is not the successful bidder, upon the earlier of the successful bidder furnishing the performance security, otherwise it will remain in force up to ----- *(insert date)*

Consequently, any demand for payment under this Guarantee must be received by us at the office on or before that date.

[signature(s) of authorized representative(s)]

[Letter heading paper of the procuring entity]

LETTER OF ACCEPTANCE

.....*[Date]*

To:
[Name and address of the Contractor]

This is to notify you that your bid dated *[insert date]* for the construction and remedying defects of the

[name of the Contract and identification number] for the Contract price ofLKR

[amount in figures and words] as corrected in accordance with Instructions to Bidders, is hereby accepted.

The adjudicator shall be *[Name & Address of the Adjudicator, if agreed]* shall be appointed by the Institute for Construction Training & Development (ICTAD)

You are hereby instructed to proceed with the execution of the said Works in accordance with the Contract documents.

The Start Date shall be: *(fill the date as per Conditions of Contract).*

The amount of Performance Security is : *(fill as per Conditions of Contract).*

The Performance Security shall be submitted on or before *(fill as per Conditions of Contract).*

Authorized Signature :

Name and title of Signatory :

Name of Agency :

[Letter heading paper of the procuring entity]

PERFORMANCE SECURITY

[this Guarantee form shall be filled in accordance with the instructions indicated in brackets]

----- *[insert issuing agency's name, and address of issuing branch or office]*

Beneficiary: Secretary, Ministry of Education, Southern Province.

Date: ----- *[insert date (by issuing agency)]*

PERFORMANCE GUARANTEE No.: ----- *[insert (by issuing agency) number]*

We have been informed that -----
[insert (by issuing agency) name of the contractor] (hereinafter called "the Contractor") has entered into Contract No. ----- *[reference number of the contract]* dated ----- with you, for the execution of **Renovation of boundary wall at H/Al Ameer Muslim M.V.** (hereinafter called "the Contract").

Furthermore, we understand that, according to the conditions of the Contract a performance guarantee is required.

At the request of the Contractor, we -----
[insert name of issuing agency] hereby irrevocably undertake to pay you any sum or sums not exceeding in total an amount of ----- *[insert amount in figures]* -----
 ----- *[insert amount in words]* upon receipt by us of your first demand in writing accompanied by a written statement stating that the Contractor is in breach of its obligation(s) under the Contract, without your needing to prove or to show grounds for your demand or the sum specified therein.

This guarantee shall expire, no later than the day of, 20..... *[insert date, 28 days beyond the scheduled contract completion date]* and any demand for payment under it must be received by us at this office on or before that date.

[signature(s) of authorized representative(s)]

AGREEMENT

This AGREEMENT, made the [day] day of [month] 20..... [year] between
 [name and address of Employer] (hereinafter called “the Employer”) of the one part, and
 [name and address of Contractor] (hereinafter called “the Contractor”) of the other part.

WHEREAS the Employer desires that the Contractor execute **Renovation of boundary wall at H/Al Ameer Muslim M.V.** (hereinafter called “the Works”) and the Employer has accepted the Bid by the Contractor for the execution and completion of such Works and the remedying of any defects therein.

NOW THIS AGREEMENT WITNESSETH as follows:

1. In this Agreement, words and expressions shall have the same meanings as are respectively assigned to them in the Conditions of Contract hereinafter referred to, and they shall be deemed to form and be read and construed as part of this Agreement.
2. In consideration of the payments to be made by the Employer to the Contractor as hereinafter mentioned, the Contractor hereby covenants with the Employer to execute and complete the Works and remedy any defects therein in conformity in all respects with the provisions of the Contract.
3. The Employer hereby covenants to pay the Contractor in consideration of the execution and completion of the Works and the remedying of defects wherein the Contract Price or such other sum as may become payable under the provisions of the Contract at the times and in the manner prescribed by the Contract.

In Witness whereof the parties thereto have caused this Agreement to be executed the day and year aforementioned, in accordance with laws of Sri Lanka.

.....

Authorized signature of Contractor

.....

Authorized signature of Employer

COMMON SEAL

COMMON SEAL

In the presence of:
 Witnesses:

1. Name and NIC No.
 Signature
 Address
2. Name and NIC No.
 Signature
 Address

Check List for Bidders

Bidders are advised to fill the following table:

ITEM	ITB Clause	YES (tick)	REFERENCE
Form of Bid			
Addressed to the Employer ?	18		
Completed?	18		
Signed?	18		
Bid Security (if required)			
Addressed to the Employer ?	16		
Format as required?	16		
Issuing Agency as specified?	16		
Amount as requested?	16		
Validity 28 days beyond the validity of Bid?	16		
Qualification Information			
All relevant information completed?	4		
Signed?	4		
Addendum			
Content of the addendum (if any) taken in to account?	10		
BID Package			
All the documents given in ITB Clause 12 enclosed in the original and copy?	12		
ITB Clause 19 followed before Sealing the Bid Package?	19		