



**MINISTRY OF EDUCATION
SOUTHERN PROVINCE**

BIDDING DOCUMENT

FOR

H/KAHAWATTA M.V. REPAIR NEPCHOON BUILDING

Issued to :

Date :

Contract No :

Employer : Secretary,
Ministry of Education,
Southern Province.

CONTENTS

Volume 1

Section 1	Instructions to Bidders
Section 2	Standard Forms (Contract)
Section 3	Conditions of Contract

Volume 2

	Invitation for Bids
Section 4	Form of Bid and Qualification Information
Section 5	Schedule
Section 6	Specifications
Section 7	Bills of Quantities
Section 8	Drawings
Section 9	Standard Forms (Bid)

Volume 1 consisting of section 1, section 2, section 3 will be applicable for this contract shall be given volume 1 of “Standard Bidding Document, Procurement of Works, Minor Contracts”, CIDA publication no: CIDA/SBD/03, Second Edition, January 2007, publish by Construction Industry Development Authority (CIDA), Savusiripaya, 123. Wijerama Mawatha, Colombo 07.

The above Document will not be issued with the Bidding Document and Bidder is advised to purchase it from CIDA.

INVITATION FOR BIDS

ප්‍රසම්පාදන දැන්වීම

දකුණු පළාත් අධ්‍යාපන, ඉඩම් හා ඉඩම් සංවර්ධන, මහා මාර්ග හා ප්‍රවාහන අමාත්‍යාංශය
දකුණු පළාත් සභාව

පළාත් නිශ්චිත සංවර්ධන ප්‍රදාන, ක්ලීන් ශ්‍රී ලංකා වැඩසටහන හා නඩත්තු සැලැස්ම 2025 යටතේ ක්‍රියාත්මක කරනු ලබන පහත සඳහන් වැඩ යෝජනා සඳහා සුදුසුකම් ලත් කොන්ත්‍රාත් කරුවන්ගෙන්, දකුණු පළාත් අධ්‍යාපන අමාත්‍යාංශයේ ප්‍රසම්පාදන කමිටු සභාපති විසින් ලංසු පත් කැඳවනු ලැබේ.

අනු අංකය	ව්‍යාපෘති අංකය	පාසල	වැඩ විස්තරය	කර්මාන්තය ඉටු කරනු ලබන ව්‍යාපෘති සැලැස්ම	ආපසු නොගෙවනු ලබන ඇප තැන්පත් මුදල රු.	ලංසු සුරක්ෂණ වටිනාකම රු.	අවශ්‍ය CIDA ලියාපදිංචිය	මුළු පිරිවැය ඇස්තමේන්තු මුදල vat සමග රු. මි.
1	G/C/25/34	ගා/උඩුගම ම.වි	70*25 දෙමහල් ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	පළාත් නිශ්චිත	2,500.00	34,000.00	C 8 හෝ ඉහළ	4.34
2	G/C/25/35	ගා/භියාරේ නැහෙනහිර ක.වි	90*25 ගොඩනැගිල්ලේ කොරිඩෝව ඉදිකිරීම	පළාත් නිශ්චිත	1,500.00	26,000.00	C 9 හෝ ඉහළ	3.40
3	G/C/25/36	ගා/තිත්තගල්ල අපානිකිත ක.වි	180*25 ප්‍රධාන ශාලාවේ වහල අලුත්වැඩියාව	පළාත් නිශ්චිත	2,500.00	35,000.00	C 8 හෝ ඉහළ	4.41
4	G/C/25/37	ගා/හපුගල ප්‍රා.වි	මායිම් තාප්පය ඉදි කිරීම	නඩත්තු සැලැස්ම	1,500.00	27,000.00	C 9 හෝ ඉහළ	3.46
5	G/C/25/38	ගා/නරාවල ම.වි	80*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	32,000.00	C 8 හෝ ඉහළ	4.10
6	G/C/25/39	ගා/පංචාලිය ප්‍රා.වි	පාසල් ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	21,000.00	C 9 හෝ ඉහළ	2.73
7	G/C/25/40	ගා/කළුගානුතිස්ස විද්‍යාලය	80*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	22,000.00	C 9 හෝ ඉහළ	2.88
8	G/C/25/41	ගා/ජයවර්ධන විද්‍යාලය	80*20 ගොඩනැගිල්ල	නඩත්තු සැලැස්ම	1,500.00	25,000.00	C 9 හෝ ඉහළ	3.14

			අලුත්වැඩියාව					
9	G/C/25/42	ගා/පැදිත්තොරුව සරණපාල ජයන්ති ප්‍රා.වි	60*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	26,000.00	C 9 හෝ ඉහළ	3.35
10	G/C/25/43	ගා/ඇත්තිලිගොඩ සුදර්ශි ම.වි	100*25 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	30,000.00	C 9 හෝ ඉහළ	3.91
11	G/C/25/44	ගා/මීගහගොඩ ක.වි	50*20 විද්‍යාගාර ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	31,000.00	C 9 හෝ ඉහළ	3.93
12	G/C/25/45	ගා/කඩිනි-ගල ම.වි	70*20 දෙමහල් ගොඩනැගිල්ලේ විදුලි පද්ධතිය නවීකරණය	නඩත්තු සැලැස්ම	1,500.00	17,000.00	C 9 හෝ ඉහළ	2.12
13	G/C/25/46	අම්බලන්ගොඩ කලාප අධ්‍යාපන කාර්යාලය	කාර්යාල ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	20,000.00	C 9 හෝ ඉහළ	2.49
14	G/C/25/47	ගා/වටරැක ශ්‍රී සෝභිත විද්‍යාලය	40*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	25,000.00	C 9 හෝ ඉහළ	3.22
15	G/C/25/48	ගා/විද්‍යානන්ද ක.වි	පැති බැම්ම අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	34,000.00	C 8 හෝ ඉහළ	4.40
16	G/C/25/49	ගා/උනන්තවිටිය රේවත ම.වි	90*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	36,000.00	C 8 හෝ ඉහළ	4.66
17	G/C/25/50	ගා/සිරි පබ්බත ප්‍රා.වි	80*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	25,000.00	C 9 හෝ ඉහළ	3.15
18	G/C/25/51	ගා/බටදූව සිරි රතනසේන ම.වි	90*25 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	26,000.00	C 9 හෝ ඉහළ	3.28
19	G/C/25/52	ගා/අක්මීමණ ම.වි	100*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	38,000.00	C 8 හෝ ඉහළ	4.97
20	G/C/25/53	ගා/ආනන්ද විජය විද්‍යාලය	90*25 ගොඩනැගිල්ලේ	නඩත්තු සැලැස්ම	1,500.00	25,000.00	C 9 හෝ ඉහළ	3.21

			වහල අලුත්වැඩියාව					
21	G/C/25/54	ගා/ඉඳුරුව ම.වි	120*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	3,000.00	49,000.00	C 8 හෝ ඉහළ	6.47
22	G/C/25/55	ගා/තලංගහ සරස්වතී දෙමළ පාසල	වැසිකිළ පද්ධතිය ඉදි කිරීම	පළාත් නිශ්චිත	1,000.00	16,000.00	C 9 හෝ ඉහළ	1.99
23	G/C/25/56	ගා/දික්කුඹුර සිද්ධාර්ථ ම.වි	120*30 ප්‍රධාන ශාලාව නවීකරණය	පළාත් නිශ්චිත	2,500.00	40,000.00	C 8 හෝ ඉහළ	5.29
24	G/C/25/57	ගා/ලේල්වල ක.වි	80*20 ගොඩනැගිල්ල අලුත්වැඩියාව	පළාත් නිශ්චිත	3,500.00	75,000.00	C 8 හෝ ඉහළ	9.93
25	G/C/25/58	ගා/පොරවගම ක.වි	පැති බැම්ම අලුත්වැඩියාව	පළාත් නිශ්චිත	2,500.00	34,000.00	C 8 හෝ ඉහළ	4.39
26	G/C/25/59	ගා/ගනේගම රෝමානු කතෝලික පාසල	80*20 නව ගොඩනැගිල්ල ඉදි කිරීම	පළාත් නිශ්චිත	1,500.00	20,000.00	C 9 හෝ ඉහළ	2.60
27	G/C/25/60	ගා/ශ්‍රීපති ම.වි	80*20 දෙමහල් ගොඩනැගිල්ල ඉදි කිරීම	පළාත් නිශ්චිත	2,500.00	37,000.00	C 8 හෝ ඉහළ	4.79
28	G/C/25/61	ගා/මාමනදොළ ක.වි	90*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	පළාත් නිශ්චිත	2,500.00	32,000.00	C 8 හෝ ඉහළ	4.15
29	G/C/25/62	ගා/උක්වත්ත විද්‍යාලය	90*25 තෙමහල් ගොඩනැගිල්ලේ ඉදි කිරීම (ඉතිරි වැඩ)	පළාත් නිශ්චිත	2,500.00	41,000.00	C 8 හෝ ඉහළ	5.42
30	G/C/25/63	ගා/අක්කරවිස්ස ක.වි	මායිම් තාප්පය අලුත්වැඩියාව	පළාත් නිශ්චිත	1,500.00	25,000.00	C 9 හෝ ඉහළ	3.21
31	G/C/25/64	ගා/කඵවලගල ක.වි	40*20 ගොඩනැගිල්ල ඉදි කිරීම	පළාත් නිශ්චිත	3,000.00	46,000.00	C 8 හෝ ඉහළ	6.07
32	G/C/25/65	ගා/අවිත්තාව නාලන්දා ම.වි	80*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	පළාත් නිශ්චිත	1,500.00	29,000.00	C 9 හෝ ඉහළ	3.73

H/C/25/49/01

33	G/C/25/66	ගා/මහින්ද රාජපක්ෂ ම.වි	මායිම් තාප්පය අලුත්වැඩියාව	පළාත් නිශ්චිත	3,000.00	61,000.00	C 8 හෝ ඉහළ	7.88
34	G/C/25/67	ගා/ගුණානන්ද ප්‍රා.වි	50*25 ගොඩනැගිල්ල අලුත්වැඩියාව	පළාත් නිශ්චිත	1,500.00	17,000.00	C 9 හෝ ඉහළ	2.16
35	G/C/25/68	ගා/බී.ටී.එස් විද්‍යාලය	80*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	32,000.00	C 8 හෝ ඉහළ	4.07
36	G/C/25/69	ගා/මාවඩවිල ම.වි	90*25 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	24,000.00	C 9 හෝ ඉහළ	3.01
37	G/C/25/70	ගා/සිරිනිවාස ම.වි	100*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	40,000.00	C 8 හෝ ඉහළ	5.31
38	G/C/25/71	ගා/දොළහේන ක.වි	80*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	43,000.00	C 8 හෝ ඉහළ	5.69
39	G /C/25/72	ගා/පිලාන තක්ෂිලා ප්‍රා.වි.	මායිම් තාප්පය නවීකරණය	පළාත් නිශ්චිත	1,000.00	14,000.00	C9 හෝ ඉහළ	1.8
40	G /C/25/73	ගා/සංසරතන ප්‍රා.වි.	100*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව.	පළාත් නිශ්චිත	2,500.00	34,000.00	C8 හෝ ඉහළ	4.4
41	G/C/25/74	ගා/තෙලිකඩ ම.වි.	80*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	පළාත් නිශ්චිත	2,500.00	35,000.00	C8 හෝ ඉහළ	4.5
42	G/C/25/75	ගා/කරන්දෙණිය ක.වි.	80*20 ගොඩනැගිල්ල අලුත්වැඩියාව	පළාත් නිශ්චිත	1,500.00	29,000.00	C9 හෝ ඉහළ	3.7
43	G/C/25/76	ගා/ලේනගල්පලා ත ක.වි.	80*20 ගොඩනැගිල්ල අලුත්වැඩියාව	පළාත් නිශ්චිත	1,500.00	27,000.00	C9 හෝ ඉහළ	3.4
44	G /C/25/77	ගා/රත්නසාර ම.වි.	100*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	පළාත් නිශ්චිත	1,500.00	23,000.00	C9 හෝ ඉහළ	2.9
45	G /C/25/78	ගා/යටගල ම.වි.	මායිම් තාප්පය අලුත්වැඩියා කිරීම.	පළාත් නිශ්චිත	2,500.00	39,000.00	C8 හෝ ඉහළ	5.1
46	G /C/25/79	ගා/ඕල්කට් ම.වි	80*20 ගොඩනැගිල්ල අලුත්වැඩියාව	පළාත් නිශ්චිත	2,500.00	40,000.00	C8 හෝ ඉහළ	5.3
47	G /C/25/80	ගා/තෙල්ලඹුර විජය ක.වි.	පැති බැම්ම ඉදි	පළාත් නිශ්චිත	2,500.00	34,000.00	C8 හෝ	4.3

			කිරීම.				ඉහළ	
48	G /C/25/81	ගා/නියාර් ම.වි.	80*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	පළාත් නිශ්චිත	2,500.00	45,000.00	C8 හෝ ඉහළ	5.8
49	G /C/25/82	ගා/උස්වතුන් හසානා ම.වි.	160*25 තෙමහල් ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව.	පළාත් නිශ්චිත	2,500.00	34,000.00	C8 හෝ ඉහළ	4.4
50	G /C/25/83	ගා/බුද්ධදත්ත ප්‍රා.වි.	120*20 ප්‍රධාන ශාලාව අලුත්වැඩියාව	පළාත් නිශ්චිත	3,500.00	64,000.00	C8 හෝ ඉහළ	8.4
51	G /C/25/84	ගා/සිරි අභයතිස්ස ක.වි.	දෙමහල් ගොඩනැගිල්ලේ යකඩ ග්‍රිල් සවි කිරීම.	නඩත්තු සැලැස්ම	1,000.00	16,000.00	C9 හෝ ඉහළ	1.9
52	M/C/25/31	මාර/පර්සි අබේවර්ධන විද්‍යාලය	80*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව.	නඩත්තු සැලැස්ම	2,500.00	40,000.00	C8 හෝ ඉහළ	5.3
53	M/C/25/44	මාර/ජිනරාජ ක.වි.	වැසිකිළි පද්ධතිය අලුත්වැඩියා කිරීම.	පළාත් නිශ්චිත	1,500.00	22,000.00	C9 හෝ ඉහළ	2.1
54	M/C/25/52	අකුරැස්ස කලාප අධ්‍යාපන කාර්යාලය	පැති බැම්ම ප්‍රතිසංස්කරණය කිරීම	නඩත්තු සැලැස්ම	1,500.00	28,000.00	C 9 හෝ ඉහළ	3.59
55	M/C/25/53	මාර/කරගොඩ උයන්ගොඩ ම.වි	වැසිකිළි පද්ධතිය ඉදි කිරීම	පළාත් නිශ්චිත	1,500.00	20,000.00	C 9 හෝ ඉහළ	2.57
56	M/C/25/54	මාර/බැරගම ක.වි	වැසිකිළි පද්ධතිය ඉදි කිරීම	පළාත් නිශ්චිත	1,500.00	19,000.00	C 9 හෝ ඉහළ	2.42
57	M/C/25/55	මාර/පොල්වත්ත ප්‍රා.වි	ප්‍රධාන ශාලාව අලුත්වැඩියා කිරීමේ ඉතිරි වැඩ සම්පූර්ණ කිරීම	පළාත් නිශ්චිත	2,500.00	34,000.00	C 8 හෝ ඉහළ	4.48
58	M/C/25/56	මාර/මාතර ආදර්ශ ප්‍රා.වි	වැසි ජලය කළමනාකරණ පද්ධතිය නවීකරණය කිරීම	පළාත් නිශ්චිත	1,500.00	21,000.00	C 9 හෝ ඉහළ	2.69
59	M/C/25/57	මාර/කිරිින්ද ආදර්ශ ප්‍රා.වි	70*25 දෙමහල් ගොඩනැගිල්ල නවීකරණය කිරීම	පළාත් නිශ්චිත	4,000.00	79,000.00	C 7 හෝ ඉහළ	10.43
60	M/C/25/58	මාර/තල්පාවිල ම.ම.වි	ක්‍රීඩා පිටිය සංවර්ධනය කිරීම	පළාත් නිශ්චිත	2,500.00	42,000.00	C 8 හෝ ඉහළ	5.47
61	M/C/25/59	මාර/කඹුරුගමුව ම.වි	80*20 තනි මහල් ගොඩනැගිල්ල 90*25 දෙමහල් ගොඩනැගිල්ලට නවීකරණය කිරීම (අදියර 01)	පළාත් නිශ්චිත සංවර්ධන ප්‍රදාන	4,000.00	88,000.00	C 7 හෝ ඉහළ	11.69
62	M/C/25/60	මාර/බෙලිදෙණිය ම.වි	60*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියා කිරීම	පළාත් නිශ්චිත	1,500.00	27,000.00	C 9 හෝ ඉහළ	3.57
63	H/C/25/26	හ/මහගල්වැව ක.වි	90*25 දෙමහල් ගොඩනැගිල්ලේ	නඩත්තු සැලැස්ම	1,500.00	21,000.00	C 9 හෝ	2.73

			බිම් මහලේ කාර්යාල කාමරය සකස් කිරීම				ඉහළ	
64	H/C/25/27	හ/දුටුගැමුණු ම.වි	90*25 තෙමහල් ගොඩනැගිල්ලේ වහලය අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	23,000.00	C 9 හෝ ඉහළ	3.05
65	H/C/25/28	හ/සපුතන්ත්‍රිකන්ද ප්‍රා.වි	පැති බැම්ම හා ජල කුළුණ ඉදි කිරීම	පළාත් නිශ්චිත	1,500.00	20,500.00	C 9 හෝ ඉහළ	2.7
66	H/C/25/29	හ/මිද්දෙනිය ම.වි	රැඳවුම් තාප්පය ඉදිකිරීම (ක්‍රීඩා පිටිය සඳහා ආරක්ෂක තාප්පය)	පළාත් නිශ්චිත	3,000.00	47,500.00	C 8 හෝ ඉහළ	6.27
67	H/C/25/30	හ/ගණේයාය ක.වි	80*20 ගොඩනැගිල්ල අලුත්වැඩියාව	පළාත් නිශ්චිත	1,500.00	27,000.00	C 9 හෝ ඉහළ	3.55
68	H/C/25/31	තංගල්ල කලාප අධ්‍යාපන කාර්යාලයේ	මායිම් තාප්පය ඉදිකිරීම(ඉතිරි වැඩ)	පළාත් නිශ්චිත	1,000.00	12,000.00	C 9 හෝ ඉහළ	1.49
69	H/C/25/32	හ/බෙලිඅත්ත ම.ම.වි	100*20 තාක්ෂණික විද්‍යාගාරය ගොඩනැගිල්ල නවීකරණය	පළාත් නිශ්චිත	3,500.00	67,500.00	C 8 හෝ ඉහළ	8.91
70	H/C/25/33	හ/කදිරගොඩ ප්‍රා.වි	වැසිකිළි අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	18,000.00	C 9 හෝ ඉහළ	2.28
71	H/C/25/34	හ/ගොඩවානගොඩ ක.වි	වැසිකිළි අලුත්වැඩියාව සහ මායිම් තාප්පය අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	21,000.00	C 9 හෝ ඉහළ	2.67
72	H/C/25/35	හ/කුඩාවැල්ල ක.වි	වැසිකිළි අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,000.00	14,000.00	C 9 හෝ ඉහළ	1.82
73	H/C/25/36	හ/රදනිආර ම.වි	පරිගණක විද්‍යාගාරය අලුත්වැඩියා කිරීම	නඩත්තු සැලැස්ම	1,500.00	23,000.00	C 9 හෝ ඉහළ	2.94
74	H/C/25/37	හ/කිරම ධම්මානන්ද ප්‍රා.වි	80*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	37,000.00	C 8 හෝ ඉහළ	4.80
75	H/C/25/38	හ/කැරදෙනිය ක.වි	40*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	28,000.00	C 9 හෝ ඉහළ	3.69
76	H/C/25/39	හ/අගලබඩ ක.වි	60*20 ගොඩනැගිල්ල අලුත්වැඩියා කිරීම	නඩත්තු සැලැස්ම	1,500.00	23,000.00	C 9 හෝ ඉහළ	2.97
77	H/C/25/40	හ/අල්අමීර් මුස්ලිම් විද්‍යාලය	මායිම් තාප්පය අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	16,000.00	C 9 හෝ ඉහළ	2.08
78	H/C/25/41	හ/පල්ලෙපුලම්පිටිය ම.වි	60*20 ගොඩනැගිල්ල අලුත්වැඩියා කිරීම	නඩත්තු සැලැස්ම	1,500.00	30,000.00	C 9 හෝ ඉහළ	3.93
79	H/C/25/42	හ/කැකිරිඹබඩ ක.වි	පුස්තකාල ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	39,000.00	C 8 හෝ ඉහළ	5.1

H/C/25/49/01

80	H/C/25/43	හ/බෙරලිහෙල ම.වි	80*20 ගොඩනැගිල්ල සහ 50*25 කාර්යාල ගොඩනැගිල්ල වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	21,000.00	C 9 හෝ ඉහළ	2.74
81	H/C/25/44	හ/ගැටමාන්න දකුණ ම.වි	100*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	37,000.00	C 8 හෝ ඉහළ	4.87
82	H/C/25/45	හ/ගැටමාන්න උතුර ක.වි	100*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	39,000.00	C 8 හෝ ඉහළ	5.07
83	H/C/25/46	හ/බුන්දල ක.වි	80*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	32,000.00	C 8 හෝ ඉහළ	4.22
84	H/C/25/47	හ/පලපොත ම.වි	100*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	27,000.00	C 9 හෝ ඉහළ	3.55
85	H/C/25/48	හ/බටහන දකුණ ක.වි	40*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	19,000.00	C 9 හෝ ඉහළ	2.49
86	H/C/25/49	හ/කහවත්ත ම.වි	නෙප්පුන් ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	3,000.00	61,000.00	C 8 හෝ ඉහළ	8.00
87	H/C/25/50	හ/කණුකැටිය ක.වි	80*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	24,000.00	C 9 හෝ ඉහළ	3.06
88	H/C/25/51	හ/දෙබරවැව ජනාධිපති විද්‍යාලය	120*20 ගොඩනැගිල්ල වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	2,500.00	40,000.00	C 8 හෝ ඉහළ	5.25
89	H/C/25/52	හ/දෙතිය පිංගම ක.වි	80*20 ගොඩනැගිල්ලේ වහල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	19,000.00	C 9 හෝ ඉහළ	2.44
90	H/C/25/53	හ/මීගහවෙල ක.වි	120*20 ගොඩනැගිල්ලේ වහල සහ වැසිකිළි අලුත්වැඩියාව	පළාත් නිශ්චිත	1,500.00	17,000.00	C 9 හෝ ඉහළ	2.2
91	H/C/25/54	හ/මොරයාය ම.වි	120*20 ගොඩනැගිල්ල අලුත්වැඩියාව	පළාත් නිශ්චිත	3,000.00	60,000.00	C 8 හෝ ඉහළ	7.94
92	H/C/25/55	හ/වැකදවල ජනපද ම.වි	120*20 ගොඩනැගිල්ල අලුත්වැඩියාව	පළාත් නිශ්චිත	3,500.00	63,000.00	C 8 හෝ ඉහළ	8.33
93	H/C/25/56	හ/හිඟුරකන්ද ම.වි	72*16 ගොඩනැගිල්ල ප්‍රතිසංස්කරණය කිරීම	පළාත් නිශ්චිත	1,000.00	14,000.00	C 9 හෝ ඉහළ	1.81
94	H/C/25/57	හ/ලුණුගම්වෙහෙර ම.වි	වැසිකිළි පද්ධතිය ඉදිකිරීම	පළාත් නිශ්චිත	1,500.00	16,000.00	C 9 හෝ ඉහළ	2.00
95	H/C/25/58	හ/කටුවන ප්‍රා.වි	විද්‍යාලයේ පැති පැමිම ඉදි කිරීම	පළාත් නිශ්චිත සංවර්ධන	2,500.00	35,000.00	C 8 හෝ ඉහළ	4.55

H/C/25/49/01

				ප්‍රදාන				
96	H/C/25/59	හ/රක්‍ෂකපෝති ප්‍රා.වි.ගහලන්දෙනිය	පැතිබැම්ම ඉදිකිරීම (ක්‍රීඩා පිටිය ඉදිරිපස)	පළාත් නිශ්චිත	2,500.00	40,000.00	C 8 හෝ ඉහළ	5.28
97	H/C/25/60	හ/වැවේගම ක.වි	60*20 ගොඩනැගිල්ල අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	24,000.00	C 9 හෝ ඉහළ	3.10
98	H/C/25/61	හ/පොළොම්මාරුව ආදර්ශ විද්‍යාලය	වැසිකිළි අලුත්වැඩියාව	නඩත්තු සැලැස්ම	1,500.00	17,000.00	C 9 හෝ ඉහළ	2.2
99	G/CSL/25/01	ගා/උනන්විටිය රේවත ම.වි.	පැති බැම්ම ඉදිකිරීම	ක්ලීන් ශ්‍රී ලංකා	1,500.00	23,000.00	C 9 හෝ ඉහළ	2.8
100	G/CSL/25/02	ගා/ඇත්තිලිගොඩ සුදර්ශි ම.වි.	80 X 20 ගොඩනැගිල්ල නවීකරණය	ක්ලීන් ශ්‍රී ලංකා	1,000.00	16,000.00	C 9 හෝ ඉහළ	1.9
101	G/CSL/25/03	ගා/දෙල්ලව ම.වි.	පැති බැම්ම ඉදිකිරීම	ක්ලීන් ශ්‍රී ලංකා	1,500.00	29,000.00	C 9 හෝ ඉහළ	3.6
102	M/CSL/25/01	මාර/දම්පැල්ල ම.වි.	සංගීත හා නැටුම් කාමර නවීකරණය	ක්ලීන් ශ්‍රී ලංකා	1,000.00	9,000.00	C 9 හෝ ඉහළ	1.1
103	G/CSL/25/04	ගා/ රක්‍ෂකසිරි රාජකීය විද්‍යාලය	ගැහැණු වැසිකිළි ඉදි කිරීම	ක්ලීන් ශ්‍රී ලංකා	1,500.00	29,000.00	C 9 හෝ ඉහළ	3.7
104	G/CSL/25/05	ගා/ අනුරුද්ධ ක.වි.	වැසිකිළි නවීකරණය (පිරිමි වැසිකිළි 02 හා ගැහැණු වැසිකිළි 04)	ක්ලීන් ශ්‍රී ලංකා	1,000.00	8,000.00	C 9 හෝ ඉහළ	1.0
105	G/CSL/25/06	ගා/සිරි අභයනිස්ස ම.වි.	ගුරුවරුන්ගේ සහ සිසුන්ගේ වැසිකිළි නවීකරණය	ක්ලීන් ශ්‍රී ලංකා	1,500.00	22,000.00	C 9 හෝ ඉහළ	2.8
106	G/CSL/25/07	ගා/දික්කුඹුර ප්‍රා.වි.	වැසිකිළි පද්ධතියක් ඉදි කිරීම	ක්ලීන් ශ්‍රී ලංකා	2,500.00	33,000.00	C 8 හෝ ඉහළ	4.2
107	G/CSL/25/08	ගා/හවිසේ ම.වි.	වැසිකිළි නවීකරණය	ක්ලීන් ශ්‍රී ලංකා	1,000.00	7,000.00	C 9 හෝ ඉහළ	0.9
108	G/CSL/25/09	ගා/හස්පිටිය ක.වි.	ගුරුවරුන්ගේ වැසිකිළි ඉදි කිරීම	ක්ලීන් ශ්‍රී ලංකා	1,500.00	29,000.00	C 9 හෝ ඉහළ	3.7
109	G/CSL/25/10	ගා/බටපොල ම.ම.වි.	වැසිකිළි ඉදි කිරීම	ක්ලීන් ශ්‍රී ලංකා	2,500.00	34,000.00	C 8 හෝ ඉහළ	4.3

02. ජාතික තරඟකාරී ලංසු පටිපාටිය මත ලංසු ඉදිරිපත් කළ යුතුය. කොන්ත්‍රාත් ප්‍රදානයේදී සුදුසුකම් ලබන සාර්ථක ලංසුකරුවන් අසාධු ලේඛනගත නොවිය යුතු අතර ඉදිකිරීම් කර්මාන්ත සංවර්ධන අධිකාරියේ ඉහත කාණ්ඩ යටතේ ලියාපදිංචි වී සිටිය යුතුය.

H/C/25/49/01

03.ලංසු අයදුම්පත් 2025.06.18 දින සිට 2025.07.03 දින දක්වා පෙ.ව 9.00 සිට ප.ව 3.00 දක්වා ඉහත දක්වා ඇති පරිදි ආපසු නොගෙවන ගාස්තුව අධ්‍යාපන අමාත්‍යාංශයේ ගිණුම් අංශයේ සරප් වෙත මුදල් ගෙවීමෙන් අනතුරුව ලබාදෙන මුදල් කුවිතාන්සිය ඉදිරිපත් කර හෝ ආපසු නොගෙවන ගාස්තුව අධ්‍යාපන අමාත්‍යාංශ ලේකම් නමින් ගාල්ල කොටුව ලංකා බැංකුවේ ඇති ගිණුම් අංක 1587423 ට බැර කර රිසිට් පත සමග ඔබගේ ඉල්ලීම් ලිපිය ද.ප. අධ්‍යාපන අමාත්‍යාංශයේ **070 7130700** දරණ වටිස්අප් අංකයට පමණක් හෝ acc.moesp@gmail.com ඊ මේල් ලිපිනයට පමණක් යොමු කිරීමෙන් ඔබට අවශ්‍ය ලංසු පත්‍රිකා තැපැල් මගින් හෝ කුරියර් කර හෝ ඊමේල් මගින් හෝ වටිස්අප් මගින් ගෙන්වා ගැනීමට හෝ ලබුදුව,දක්ෂිණපාය අධ්‍යාපන අමාත්‍යාංශයෙන් (බිම් මහල) ගිණුම් අංශයෙන් ලබා ගත හැකිය. වැඩි විස්තර අමාත්‍යාංශයේ 091-2030700 දුරකථන අංකයට වැඩ කරන දින ඇමතීමෙන් හෝ ද.ප. අධ්‍යාපන අමාත්‍යාංශ වෙබ් අඩවියට www.edumin.sp.gov.lk පිවිසීමෙන් අදාල ලංසු පත්‍රිකා පරීක්ෂා කල හැකිය.

04. මුද්‍රා තබන ලද ලංසු පත්‍රිකා 2025.07.04 පෙ.ව 11.00 ට පෙර ලැබෙන සේ ලේකම්, දකුණු පළාත් අධ්‍යාපන අමාත්‍යාංශය, දක්ෂිණපාය, ලබුදුව, ගාල්ල යන ලිපිනයට ලියාපදිංචි තැපෑලෙන් එවීමට හෝ අතින් රැගෙන විත් ප්‍රධාන ගණකාධිකාරී නිල කාමරයේ තබා ඇති ටෙන්ඩර් පෙට්ටියට බහාලිය හැකිය. ප්‍රමාද වී ලැබෙන ලංසු ප්‍රතික්ෂේප කරනු ලැබේ.

05.ලංසු විවෘත කිරීම 2025.07.04 දින පෙ.ව 11.00 ට ලංසු පත්‍රිකා භාරගෙන අවසන් වූ වහාම දකුණු පළාත් අධ්‍යාපන අමාත්‍යාංශයේ ප්‍රසම්පාදන කමිටු සභාපතිගේ ප්‍රධානත්වයෙන් අමාත්‍යාංශයේදී සිදු කරන අතර එම අවස්ථාවට ලංසුකරුට හෝ ලංසුකරුගේ බලයලත් නියෝජිතයන් හට සහභාගී විය හැක.

06. ලංසුව සමඟ ඉදිරිපත් කරන ලංසු සුරක්ෂණය ශ්‍රී ලංකා වාණිජ බැංකුවකින් දකුණු පළාත් අධ්‍යාපන අමාත්‍යාංශයේ ලේකම් නමට ලබා ගත් 2025.07.04 දින සිට 2025.10.04 දක්වා වලංගු ලංසු ඇපකරයක් හෝ අධ්‍යාපන අමාත්‍යාංශයේ ගිණුම් අංශය වෙත මුදල් ගෙවීමෙන් අනතුරුව ලබාදෙන මුදල් කුවිතාන්සියේ පිටපත ලංසු පත්‍රිකාව සමඟ ඉදිරිපත් කළ යුතුය.

07. ලංසු වලංගු කාලය දින 77 කි.

08. ඉදිරිපත් කරනු ලබන කර්මාන්තයට අදාල ලංසු පිටපත් දෙකකින් යුතුව ඉදිරිපත් කළයුතු අතර එහි මුල් පිටපතෙහි “මුල් පිටපත” යනුවෙන් සඳහන් කළ යුතු අතර අනු පිටපතෙහි “අනුපිටපත” යනුවෙන් සඳහන් කළ යුතුය. ලංසුපත් වල මුල් පිටපත හා අනුපිටපත වෙන වෙනම කවරවල බහා මුද්‍රා තබා එම කවර දෙක එක් කවරයක බහා එම කවරය මුද්‍රා තබා කවරයේ වම් පස උඩකෙළවරේ කර්මාන්තයේ නම සහ අංකය සඳහන් කළ යුතුය.

09. ඔබ විසින් ඉදිරිපත් කිරීමට නියමිත සෑම ලංසු පත්‍රිකාවෙහිම මිල ගණන් සඳහන් කර ඇති පිටු අංකයන්හි ඔබ විසින් සඳහන් කළ යුතු ඒකක මිල ගණන් හා මුළු මුදල දැක්වෙන තීරය සහ සාරාංශයද (වට්ටම් දැක්වෙන තීරයද ඇතුලත්ව) විනිවිද පෙනෙන සේ සෙලෝටේප් කර ලංසු ඉදිරිපත් කිරීම අනිවාර්ය වේ.

10. ද.ප. අධ්‍යාපන අමාත්‍යාංශය දැනටමත් දකුණු පළාතේ පාසල්වල ඉදිකිරීම් අලුත්වැඩියා හා නඩත්තු කටයුතුවලට අදාල ව්‍යාපෘති සියයක පමණ ප්‍රසම්පාදන කටයුතු අවසන් කර ඉදිකිරීම් කටයුතු ආරම්භ කර ඇත.එමෙන්ම මෙම ව්‍යාපෘති එකසිය නමයෙහි ද ප්‍රසම්පාදන කටයුතු හැකි ඉක්මනින් අවසන් කර ව්‍යාපෘතිවල වැඩ 2025 වසරේ දෙසැම්බර් මස වනවිට අවසන් කල යුතු බැවින් ලංසුකරුවන්ගේ ධාරිතාවය පිළිබඳ ලංසු ප්‍රදානයේදී සලකා බලනු ලැබේ.

11.අඩුපාඩු සහිත ලංසුපත්‍රිකා ප්‍රතික්ෂේප කරනු ලබන ලැබේ. මෙම ප්‍රසම්පාදනය සම්බන්ධයෙන් ප්‍රසම්පාදන කමිටුවේ තීරණය අවසාන තීරණය බව සැලකිය යුතුය.

ඒ.යු.වේලාරත්න,

ප්‍රසම්පාදන කමිටු සභාපති,

දකුණු පළාත් අධ්‍යාපන අමාත්‍යාංශය,

පළමු මහල, දක්ෂිණපාය, ලබුදුව, ගාල්ල.

2025.06.18

දුරකථන අංකය - 0912030700 ඊමේල් - acc.moesp@gmail.com

SECTION 4

FORM OF BID AND QUALIFICATION INFORMATION

FORM OF BID

Name of Contract : **H/Kahawatta M.V. – Repair Nepchoon building**

To : **Secretary, Ministry of Education, Southern Province.**

Gentleman,

1. Having examined the Standard Bidding Document - Procurement of Works - Minor Contracts [ICTAD/ SBD/ 03 - Second Edition, January 2007], Schedule, Specifications, Drawings and Bills of Quantities and addenda for the execution of the above named Works, we/I the undersigned, offer to execute and complete such Works and remedy any defect therein in conformity with the aforesaid Conditions of Contract, Schedule, Specifications, Drawings, Bill of Quantities and Addenda for the sum of Sri Lankan Rupees
..... (LKR) or such other sums as may be ascertained in accordance with the said Conditions.
2. We/I acknowledge that the Schedule forms part of our/my Bid.
3. We/I undertake, if our Bid is accepted, to commence the Works as stipulated in the Schedule, and to complete the whole of the Works comprised in the Contract within the time stated in the Schedule.
4. We/I agree to abide by this bid for the period stated in the Sub-Clause 15 of Instructions to Bidders or any extended period and it shall remain binding upon us and may be accepted at any time before the expiration of that period.
5. Unless and until a formal agreement is prepared and executed this Bid, together with your written acceptance thereof, shall constitute a binding contract between us/me.
6. We/I understand that you are not bound to accept the lowest or any Bid you may receive.

Dated this day of 20.... in the capacity of duly authorized to
sign tenders for and on behalf of
..... (IN BLOCK CAPITALS)

Signature :

Name :

Designation :

Address :

Witness :

Qualification Information

(to be completed by the bidder and submitted with the Bid)

	Eligibility Requirement	Bidder's Qualification
ICTAD Registration		
Registration number		
Grade	C8 or Above	
Speciality	Buildings	
Expiry Date		
Backlisted Contractors		
Have you been declared as a defaulted contractor by NPA or any other Agency?		Yes /No
IF yes provide details		
VAT Registration Number		
Construction Program	(attach as annex)	
Legal status	Public company/Private Company/Partnership/Sole proprietor	
	Eligibility Requirement	Bidder's Qualification
Qualification and experience of key staff	Category, Experience and Qualifications <i>(Insert requirement) *</i>	Required Nos. *
	1	
	2	
	3	
List Other information required		

Signature of the Bidder :

SECTION 5

SCHEDULE

Schedule

ITB Clause	Conditions of Contract Clause	Item	Data
1.	1.1.8	Employer is :	Name : Secretary Address: Ministry of Education, Southern Province.
	1.1.10	Engineer is:	Name : District Engineer (Buildings) Address: District Engineer (Buildings) Office, 2nd Floor, Administrative Complex, Hambantota.
1 & 13	1.1.21	Summary of Works	The Works consists of: Located at : H/Kahawatta M.V. Contract Name : Repair Nepchoon building Contract Number H/C/25/49
	1.1.14	Intended Completion Date	Intended Completion Date is 120 Days from the Start Date
2.		Source of Funds	The source of funds is
3.		Eligibility	The requirement is CIDA C8 or Above
12.		Documents of the Bid	Any other information
13.	10.10	Price Adjustment	The Contract is is not subject to price adjustment in accordance with Sub-Clause 10.10 of the Conditions of Contract. The price adjustment shall be computed in accordance with Option B under sub clause 10.10. Non adjustable element shall be: BOQ Item Numbers : Option B: Type of Construction: Non residential buildings

ITB Clause	Conditions of Contract Clause	Item	Data
16.		Bid Security	<p>Bid shall include a Bid Security:</p> <ul style="list-style-type: none"> for an amount LKR 61,000.00 issued by an agency acceptable to Employer using the form for bid security (unconditional guarantee) included in Section 9, Standard Forms, remain valid till 2025.10.04 or if paid by cash to the Employer, LKR 61,000.00
31.	4.4	Performance Security	<p>Amount of Performance Security required is 5% of the Initial Contract Price</p> <p>The form acceptable is unconditional guarantee as standard form as per SBD/03</p>
	6.4	Late Completion	The amount to be paid is 0.05 % of Initial Contract Price per Day, subjected to maximum of 10 % of Initial Contract Price.
	8.1	Notification of Defects	The period for Defect Notification is 180 Days from Taking Over.
	10.3	Retention	<p>The amount of retention is 10 % of certified work done.</p> <p>The maximum amount of retention is 5 % of Initial Contract Price.</p>
	10.12	Advance Payment	Upon the payment of the advance payment in full the Employer shall return the original of the advance payment guarantee to the Contractor.
	13.1 (c)	Insurance, third party	Minimum amount for third party insurance is LKR 100,000.00
	13.1 (a)	Insurance for Works, Material and plant	The minimum cover for insurance of the works and plant and materials is 110% of initial contract price.
	13.1	Insurance for Contractor's Personnel	Minimum amount for Insurance is LKR 500,000.00
33.	1.1.11	Adjudicator	<i>CIDA</i>
	14.0	Resolution of Disputes	<p>Deputy Chief Secretary (Engineering Services), Southern Province</p> <p><i>Fees and types of reimbursable expenses to be paid to the Adjudicator shall be on a case to case basis and shall be shared by the Contractor and the Employer.</i></p>

SECTION 6

SPECIFICATIONS

TECHNICAL SPECIFICATIONS

Technical specification that are applicable to this project are listed below:

- SCA/3/1 - Irrigation and Land Drainage
- SCA/3/2 - Water Supply Sewerage and Storm Water Drainage
- SCA/3/3 - Reclamation Works
- SCA/3/4 - Ground Water Exploration & Exploitation
- SCA/4/I - Building Works (Vol I)
- SCA/4/II - Building Works (Vol II)
- SCA/5 - Roads and Bridges
- SCA/6 - Coastal Harbour Engineering Works
- SCA/8 - Electrical and Mechanical Works
- ICTAD/DEV/16 - Board & Cast In situ Reinforced Concrete Piles
- ICTAD/DEV/17 - Site Investigation for Building Works & Sample Bill of Quantities
- Any other specification approved by the Government.

Above publications shall be purchase from the Construction Industry Development Authority (CIDA), Savusiripaya, 123. Wijerama Mawatha, Colombo 07.

SECTION 7

BILL OF QUANTITIES

H/KAHAWATTA M.V -REPAIR NEPCHOON BUILDING

ID	Description	Unit	Qty.	Rate	Amount
(No Topic Assigned)					
<u>DEMOLISH WORKS</u>					
1	Removing roof tiles and timber of roof completely, stacking serviceable materials and clearing debris in single storied buildings	sq.m	283.00		
2	Removing Unloading existing Truss (Timber , steel etc.)	nr	8.00		
3	Removing existing Ceiling(Asbestos) with timber frame stacking materials and clearing debris away from site GF	sq.m	35.50		
4	Demolishing floors 3" thick brick paved, stacking reuseable bricks and clearing debris away from site	sq.m	88.50		
5	Demolishing brickwork in cement clearing debris away from site	cu.m	1.00		
6	Removing lime plastering and clearing debris away from site	sq.m	18.50		
	<i>Total carried to summary</i>				
<u>EARTH WORKS</u>					
7	Excavation for foundation by manually in any material except rock requiring blasting, part return fill in and ram, and disposing surplus within site as directed. (not exceeding 5ft depth)	cu.m	0.70		
	<i>Total carried to summary</i>				
<u>BRICK WORKS</u>					
8	Brickwork 112mm in cement : sand mortar 1:5 (Second Floor).	sq.m	16.50		
	<i>Total carried to summary</i>				
<u>CONCRETE WORKS</u>					
9	Cement concrete 1:2 1/2:5(1")mix: above 3.0 m3 (Shuttering paid separately) incl: curing. Using mixture.	cu.m	7.00		
10	Drain for single storied building Corrugated asbestos sheet roof with 900mm eave in front ,back & 900mm eave in gable sides, 225mm internal width and minium starting depth 150mm drain, 75mm thick cement concrete in 1:21/2:5 (1") mix: to required slop (20feet to 1 inch) , cement rendering, 1/2" thick, 1:3 cement sand motor finished smooth with neat cement floating including curing.(Sigle storied building)(As per detail drawing No SPES/Rate 23/Ct-15)	m	76.00		

ID	Description	Unit	Qty.	Rate	Amount
11	Cement concrete 1:2:4(3/4") (Gr.20 concrete) (R/F and Shuttering paid separately)incl: curing(manual mixing up to 3m3) for sill beam &stiner	cu.m	0.50		
12	Pad stones in cement concrete 1:2:4(3/4") (Gr.20) precast or in site (size 131/2"x131/2"x9") (Rate including shuttering & curing)	nr	22.00		
	<i>Total carried to summary</i>				
	<u>REINFORCEMENT WORKS</u>				
13	10mm for stiffner& sillbeam	kg	29.00		
	<i>Total carried to summary</i>				
	<u>RRM WORKS</u>				
14	Random Rubble Masonry in cement mortar 1:5 in substructure (6"- 9" rubble)	cu.m	0.70		
	<i>Total carried to summary</i>				
	<u>PLASTER WORKS</u>				
15	1/2" thk 1:3 Cement Rendering finished smooth with neat cement floating, Ground floor(sand to be sieved with 1/8" nets) Rate to include curing	sq.m	91.00		
16	Skirting in Cement mortar 1:3, 1/2" X 4" projected to wall finish with floating including forming groove. (G: floor)	m	52.50		
17	Cement Sand plastering to wall 1:5, (5/8") thick semi rough G: floor rate to include curing	sq.m	45.00		
18	3/4" thk Rendering in Cement and sand 1:3 in floors finished smooth Rate to include curing, - for plinth plaster	sq.m	23.00		
	<i>Total carried to summary</i>				
	<u>ELECTRICAL WORKS</u>				
19	Supply and fixing 56" sweep ceiling fan with electronic fan speed controller concealed conduit wiring (1/1.13 wire 1.0mm2, 1/1.13 earth wire 1mm2 including gang switch)all complete as per instruction Make (USHA ATOM EX 56 " / Telesonic Supreme with safety switch and cable) with 2 years warenty (SLSI Approved makes) (Switches - ACL/Chint/Krypton/Orange) (Cable - ACL/Kelani/Orange/Sierra) (Conduit - krypton/Polycrome) (fittings -krypton/Polycrome/Orange)	nr	2.00		

ID	Description	Unit	Qty.	Rate	Amount
20	Supplying and fixing 13Amp socket outlet with necessary concealed conduit wiring 7/0.53 (Cu/PVC/PVC) single wire 1.5mm ² 1Cx2, 7/0.53 (1.5mm ²) Earth wire all complete as per instruction (Socket - ACL/Chint/Krypton/Orange) (Cable - ACL/Kelani/Orange/Sierra) (Conduit - Krypton/Polycrome) (fittings - krypton/Polycrome/Orange)	nr	3.00		
21	Refixing of existing ceiling fan including fixing materials / cleaning all complete as per the instruction.	nr	1.00		
22	Supply and Fixing concealed 1Nr point wiring (PVC) including 1/1.13 1mm ² 1Cx2 wire/ gang switch/ sunk box and fixing materials. All complete as per instruction. (Switch - ACL/Chint/Krypton/Orange) (Cable - ACL/Kelani/Orange/Sierra) (fittings - krypton/Polycrome/Orange) (Conduit - krypton/Polycrome)	nr	1.00		
23	Supplying and fixing consumer unit 06 way surface mounted M.C.B type (incl.32 Amp. D.P MCB,40 Amp/30 mA-D.P RCCB, 6 nrs M.C.B (6 Amp.-16 Amp.)700 encloser box & bus bar fixing Philips screws (MCB-Make -Orange electric 10kA/ Schneider/Chint NB 7/EB) (RCCB Make -Orange electric 10kA/Schneider/Chint NL1) (Enclosure- Polycrome) Original Makes with company warranty Certificate. all complete as per instruction	nr	1.00		
24	Supplying and fixing 2" dia galvanized iron earth pipe 6'-0" (1800 mm) long (heavy duty) and connected the 7/1.04 earth wire (6mm ²) with cable LUG . Including brick chamber with cover slab as per Drawing. (DB to Earth pipe cable/ conduit length 8 m) [Cable SLS 733] (Cable - ACL/Kelani/Orange/Sierra)) (for 30A , single/ three phase supplies only)	nr	1.00		
25	Supplying and fixing 2"x2"x1/4" Angle iron bracket for main supply electricity connection about 5'-0" long. Angle iron bar, bent to " L" shape and fixed to roof end with necessary bolt and nut. Apply two coats of anticorrosive paint to angle iron.	nr	1.00		
26	Supplying and fixing Ceramic pulley with "D" bracket for Electricity connection. all complete as per instruction	nr	1.00		
27	Supply and fixing 01 No. Pendent type lamp(9 W LED Bulb - efficacy:85 lumen/W or above with two years warranty) with GANG switch Complete with necessary concealed conduit wiring as per working order.(Switch - ACL/Chint/Krypton/Orange) (Cable - ACL/Kelani/Orange/Sierra) (fittings - krypton/Polycrome/Orange) (Conduit - krypton/Polycrome) (Bulb - Orange electric ECO LITE/ ZENOI/ Kelani) [Cable SLS 733, Switch SLS 1000 Bulb SLS 984]	nr	8.00		
	Total carried to summary				

	ROOF WORKS
--	-------------------

ID	Description	Unit	Qty.	Rate	Amount
28	Corrugated asbestos sheets supplied and fixed to roof or wall on existing framework with necessary roofing screws and limpet washers or hook bolts.	sq.m	285.00		
29	Ridging, Calicut pattern, bedded in cement and lime mortar 1:1:4, colour to match tiles. (Keep went opening every vally point).	m	33.00		
	<i>Total carried to summary</i>				
	<u>CARPENTRY WORKS</u>				
30	Ceiling , asbestos, flat, fixed with clout headed nails to (100 x50mm) joists @ 1200 mm c/c & (50 x 50 mm) bearers @ 600 mm c/c of Imported timber prepared by using multi purpose wood working machine, including 11/2" x1/2" beading & 11/2 "x 11/2" moulding. Applying one coat of aluminium primer & two coat enamel paint to beading & moulding (class II timber). Applying one coat of wall pillar & two coats emulsion paint to sheets (Rate to include applying two coats of wood preservative to timber framework & use 11/2" Iron screws for moulding & Beading at 600mm c/c	sq.m	70.50		
	<i>Total carried to summary</i>				
	<u>IRON WORKS</u>				
31	Supplying and fixing 20'-0 span and 22 degree pitch with 900mm wide eaves with both side , steel roof truss for asbestos purlin roof, with 2 nrs 50 x 50 x 6 mm top and bottom chord and 1/50x50x6mm struts, Angle iron members 62 x 62 x 6mm 150 mm long cleats, 6 mm thick Gusset plates and 10mm thick base plates and shoe plate. and 100mm long 50 x 6 mm thk separators . Rate to include applying one coat of metal primer , 2 coats of anticorrosive paint. (Applying paint under the T.O.'s supervision)(Different colours) Draw. No. SPES/Rate23/Ir-03.	nr	8.00		
32	Supplying and fixing Angle iron purlin 62 x 62 x6 mm angle iron purlin at maximum spacing of 3'-6" centre & maximum span of 10'-0" including necessary 300mm long, 50 x 50 x 6mm angle iron for inside & 300mm long 50 x 6 mm flat iron for out side of purlin joints , 1/2, dia 1 1/2" M.S bolt washers and nut etc. and application of one coat of metal primer & two coats of anticorrosive paint different clour in single storied Building. (Applying paint under the T.O.'s supervision) Draw. No.SPES/Rate23/Ir-12 .	m	330.00		

ID	Description	Unit	Qty.	Rate	Amount
33	Supplying fabricated and hoisting 50 x 50 x 6 mm double angle iron sleeper with 3 nr 16mm dia. 250mm long mild steel rod should be insert to 300 X 225 X 225 mm size 1:2:4 (3/4) concrete pad on gable wall. Including 100 mm long ,50 x 6 mm flat iron separators at 2000 mm spacing & 150 mm long, 62 x 62 x 6 mm angle iron cleat with one coat of metal primer & two coats of anticorrosive paint (Applying paint under the T.O.'s supervision)(different colours) - (Single storied building) (Draw.No.SPES/Rate23/Ir-13).	m	26.00		
34	Supplying and making 6mm dia. M.S. rod grills for windows with 6mm dia. M.S. rods weld to 12 x 6 mm thick M.S. flat iron outer frame, at 75 mm ctrs. & to 700angle both ways, horizontal & vertical distance should be 75mm & 200mm respectively, fixed to window frame with 1" iron screws & applying one coats of metal primer & 2 coats of approved quality enamel paint.(Differnt colour) (all complete as per detail Draw. No :SPES/Rate23/Ir-22)	sq.m	37.00		
35	Iron door with 6 mm dia. M.S. grill - Fabricating and fixing Iron door Door Frame with 32 x 32 x 6 mm angle Iron (Heavy quality) and Sash with 20 mm dia. G.I pipe outer frame (Heavy quality) with 1nr middle bar. 6mm M.S steel bars welded to upper part of sash frame at 75mm c/c bothways at 700 Angle .12x6 mm thick flat iron welded around the lower part of the frame and 2 nr 20x6 mm thick intermediate flat iron welded horizontally ,and 0.47 thick Zn/Al sheet fixed to flat iron frame with pop rivets. Door sash fixed to frame with 03nr 100 x75mm steel hinges. Applying one coat of metal primer and two coats of enamel paint(Differant colour) . Rate to include 6" Hasp and staple with approved quality 50mm Brass pad lock. Draw.No.SPES/Rate23/Ir-28.	sq.m	4.50		
	<i>Total carried to summary</i>				
	<u>PAINTING WORKS</u>				
36	Applying skim coat & one coats of wall filler for internal wall. (semi rough plastered new work or after preparation of old wall)	sq.m	41.50		
37	Painting walls with one coats of wall filler (internal)(new work or after preparation of old wall)	sq.m	212.00		
38	Prepare and Painting New walls with two coats of emulsion paint to internal wall (Using roller brush)	sq.m	254.00		
39	Painting walls with one coats of Acrylic wall filler for external wall (new work or after preparation of old wall) -Ground floor	sq.m	155.00		
40	Wethershield paint to external faces of wall 02coat apply using roller brush 2" brush (ground Floor)	sq.m	155.00		
	<i>Total carried to summary</i>				

H/C/25/49/01

District Engineer's (Buildings) Office - Hambanthota

ID	Description	Unit	Qty.	Rate	Amount
	<u>FORM WORK</u>				
41	Shuttering for 4 1/2"X 3"concrete coping using Class (II) timber planks (Rate to include dismantling same when required).for both sides	m	22.50		
42	Shuttering for 0'-4 1/2"x0'-9"concrete stiffener including Class (II) timber planks and joists necessary props. (Rate to include dismantling same when required).	sq.m	2.30		
	<i>Total carried to summary</i>				

H/KAHAWATTA M.V. – REPAIR NEPCHOON BUILDING

SUMMARY

Demolish	Works
Earth	Works
Brick	Works
Concrete Works	
Reinforcement	Works
RRM Works	
Plaster	Works
Electrical	Works
Roof	Works
Carpentary	Works
Iron	Works
Painting	Works
Form Works	
SUB TOTAL		=====

H/KAHAWATTA M.V. – REPAIR NEPCHOON BUILDING

(A) BOQ Total	:	LKR
(B) Less for Provisional Sums	:	LKR -
(C) Sub Total (A-B)	:	LKR
(D) Less for Discount (If Any) (..... %)	:	LKR
(E) Sub Total (C-D)	:	LKR
(F) Add for Provisional Sums	:	LKR -
<i>Total Bid Amount (E+F)</i>		
<i>(Excluding VAT, Carried to Form of Bid)</i>	:	LKR =====

Total Bid Amount in Words

.....

18 % VAT	:	LKR
Grand Total	:	LKR =====

Note:

Bidders are requested to provide discounts, if any, as a percentage. Otherwise, it will be converted to a percentage. Your discount will also be applied to variations in quantity."

..... Signature
of Bidder

SECTION 8

DRAWINGS

SECTION 9

STANDARD FORMS

- **Form of Bid Security**
- **Form of Letter of Acceptance**
- **Form of Performance Security**
 - **Agreement**

[Letter heading paper of the procuring entity]

BID SECURITY

[this Guarantee form shall be filled in accordance with the instructions indicated in brackets]

----- *[insert issuing agency's name, and address of issuing branch or office]*

Beneficiary: Secretary, Ministry of Education, Southern Province.

Date: ----- *[insert date (by issuing agency)]*

BID GUARANTEE No.: ----- *[insert (by issuing agency) number]*

We have been informed that -----
[insert (by issuing agency) name of the bidder] (hereinafter called "the bidder") has submitted to you its bid dated ----- *[insert (by issuing agency) date]* (hereinafter called "the Bid") for the execution of **H/Kahawatta M.V. – Repair Nepchoon building** under Invitation for Bids No. -----
----- *[insert IFB number]* ("the IFB").

Furthermore, we understand that, according to your conditions, Bids must be supported by a Bid Guarantee.

At the request of the bidder, we -----
[insert name of issuing agency] hereby irrevocably undertake to pay you any sum or sums not exceeding in total an amount of ----- *[insert amount in figures]* -----
----- *[insert amount in words]* upon receipt by us of your first demand in writing accompanied by a written statement stating that the Bidder is in breach of its obligation(s) under the bid conditions, because the Bidder:

- (a) has withdrawn its Bid during the period of bid validity specified; or
- (b) does not accept the correction of errors in accordance with the Instructions to Bidders (hereinafter "the ITB"); or
- (c) having been notified of the acceptance of its Bid by the Employer during the period of bid validity, (i) fails or refuses to execute the Contract Form, if required, or (ii) fails or refuses to furnish the Performance Security, in accordance with the ITB.

This Guarantee shall expire: (a) if the bidder is the successful bidder, upon our receipt of copies of the Contract signed by the bidder and of the Performance Security issued to you by the bidder; or (b) if the bidder is not the successful bidder, upon the earlier of the successful bidder furnishing the performance security, otherwise it will remain in force up to ----- *(insert date)*

Consequently, any demand for payment under this Guarantee must be received by us at the office on or before that date.

[signature(s) of authorized representative(s)]

[Letter heading paper of the procuring entity]

LETTER OF ACCEPTANCE

.....*[Date]*

To:
[Name and address of the Contractor]

This is to notify you that your bid dated *[insert date]* for the construction and remedying defects of the
.....
[name of the Contract and identification number] for the Contract price ofLKR
.....
[amount in figures and words] as corrected in accordance with Instructions to Bidders, is hereby accepted.

The adjudicator shall be *[Name & Address of the Adjudicator, if agreed]* shall be appointed by the Institute for Construction Training & Development (ICTAD)

You are hereby instructed to proceed with the execution of the said Works in accordance with the Contract documents.

The Start Date shall be: *(fill the date as per Conditions of Contract)*.

The amount of Performance Security is : *(fill as per Conditions of Contract)*.

The Performance Security shall be submitted on or before *(fill as per Conditions of Contract)*.

Authorized Signature :

Name and title of Signatory :

Name of Agency :

[Letter heading paper of the procuring entity]

PERFORMANCE SECURITY

[this Guarantee form shall be filled in accordance with the instructions indicated in brackets]

----- *[insert issuing agency's name, and address of issuing branch or office]*

Beneficiary: Secretary, Ministry of Education, Southern Province.

Date: ----- *[insert date (by issuing agency)]*

PERFORMANCE GUARANTEE No.: ----- *[insert (by issuing agency) number]*

We have been informed that -----
[insert (by issuing agency) name of the contractor] (hereinafter called "the Contractor") has entered into Contract No. ----- *[reference number of the contract]* dated ----- with you, for the execution of **H/Kahawatta M.V. – Repair Nepchoon building** (hereinafter called "the Contract").

Furthermore, we understand that, according to the conditions of the Contract a performance guarantee is required.

At the request of the Contractor, we -----
[insert name of issuing agency] hereby irrevocably undertake to pay you any sum or sums not exceeding in total an amount of ----- *[insert amount in figures]* -----
----- *[insert amount in words]* upon receipt by us of your first demand in writing accompanied by a written statement stating that the Contractor is in breach of its obligation(s) under the Contract, without your needing to prove or to show grounds for your demand or the sum specified therein.

This guarantee shall expire, no later than the day of, 20..... *[insert date, 28 days beyond the scheduled contract completion date]* and any demand for payment under it must be received by us at this office on or before that date.

[signature(s) of authorized representative(s)]

AGREEMENT

This AGREEMENT, made the [day] day of [month] 20..... [year] between
[name and address of Employer] (hereinafter called “the Employer”) of the one part, and
.....
[name and address of Contractor] (hereinafter called “the Contractor”) of the other part.

WHEREAS the Employer desires that the Contractor execute **H/Kahawatta M.V. – Repair Nepchoon building** (hereinafter called “the Works”) and the Employer has accepted the Bid by the Contractor for the execution and completion of such Works and the remedying of any defects therein.

NOW THIS AGREEMENT WITNESSETH as follows:

1. In this Agreement, words and expressions shall have the same meanings as are respectively assigned to them in the Conditions of Contract hereinafter referred to, and they shall be deemed to form and be read and construed as part of this Agreement.
2. In consideration of the payments to be made by the Employer to the Contractor as hereinafter mentioned, the Contractor hereby covenants with the Employer to execute and complete the Works and remedy any defects therein in conformity in all respects with the provisions of the Contract.
3. The Employer hereby covenants to pay the Contractor in consideration of the execution and completion of the Works and the remedying of defects wherein the Contract Price or such other sum as may become payable under the provisions of the Contract at the times and in the manner prescribed by the Contract.

In Witness whereof the parties thereto have caused this Agreement to be executed the day and year aforementioned, in accordance with laws of Sri Lanka.

.....

Authorized signature of Contractor

.....

Authorized signature of Employer

COMMON SEAL

COMMON SEAL

In the presence of:
Witnesses:

1. Name and NIC No.
Signature
Address
2. Name and NIC No.
Signature
Address

Check List for Bidders

Bidders are advised to fill the following table:

ITEM	ITB Clause	YES (tick)	REFERENCE
Form of Bid			
Addressed to the Employer ?	18		
Completed?	18		
Signed?	18		
Bid Security (if required)			
Addressed to the Employer ?	16		
Format as required?	16		
Issuing Agency as specified?	16		
Amount as requested?	16		
Validity 28 days beyond the validity of Bid?	16		
Qualification Information			
All relevant information completed?	4		
Signed?	4		
Addendum			
Content of the addendum (if any) taken in to account?	10		
BID Package			
All the documents given in ITB Clause 12 enclosed in the original and copy?	12		
ITB Clause 19 followed before Sealing the Bid Package?	19		